

External wall finishes by others

All internal finishes including mastic joints against mullions by others

Cement board by others



Architect to confirm setting out dimension of screens. This varies from design intent as the screen has been moved outwards to allow the mullions to run past the steelwork

INTERNAL

NOTE: FOR SETTING OUT OF SCREEN TYPE L RELATIVE TO STEELWORK IN THAT LOCATION, REFER HEAD DETAIL

EPDM by Oxted Windows bonded to mullion and face of cement board and glazed in to system

EXTERNAL

Metal Technology System 17 HR Curtain Walling.

Aluminium pressing by Oxted Windows. RAL 7016

External mastic pointing by Oxted Windows.

Dashed red line indicates structural opening. All structural opening sizes on schedules and elevation drawings taken to this point

**1** Typical Jamb Detail Type 1  
A121 1 : 2


25 mm Mullion to S/O

P2	ARCHITECT COMMENTS INCORPORATED	17/03/18
P1	FIRST ISSUE	10/03/18
REV	COMMENT	DATE

COPYRIGHT REMAINS WITH THE COMPANY. REPRODUCTION PROHIBITED

Drawing Status	FOR APPROVAL
Drawing Title	Typical Curtain Wall Types A & B Jamb Detail
Project	Parliament Hill LA Swap Building
Client	Farrans Construction

Drawn By	SA	Scale	1 : 2 @ A3	Date	10/03/18
Project No	3381	Drawing No	3381-A121	Rev	P2



**OXTED WINDOW SYSTEMS LTD.**

34A Hobbs Industrial Estate  
Eastburne Road, New Chapel  
Lingfield, Surrey  
RH7 6HN  
t:01342 836630 f:01342 836631  
e: info@oxtedwindows.co.uk