



NOTE: EPDM to slot into the mullions at each location

Underside of transom to be machined to fit over bolt head

EPDM by Oxted Windows bonded to transom and internal structure

Galvanised steel bracket by Oxted Windows

All internal finishes and insulation by others

Metal Technology System 17 HR Curtain Walling.

Aluminium cill by Oxted Windows. RAL 7016



Architect to confirm top level of upstand



External finish levels to be coordinated with screen cills

1 Typical Cill Detail Type 1
A122 1 : 2

P2	ARCHITECT COMMENTS INCORPORATED	17/03/18
P1	FIRST ISSUE	10/03/18
REV	COMMENT	DATE

Drawing Status	FOR APPROVAL
Project	Parliament Hill LA Swap Building

Drawing Title	Typical Curtain Wall Types A & B Cill Detail
Client	Farrans Construction

Drawn By	SA	Scale	1 : 2 @ A3	Date	10/03/18
Project No	3381	Drawing No	3381-A122	Rev	P2

OWS

OXTED WINDOW SYSTEMS LTD.

34A Hobbs Industrial Estate
Eastburne Road, New Chapel
Lingfield, Surrey
RH7 6HN
t:01342 836630 f:01342 836631
e: info@oxtedwindows.co.uk

COPYRIGHT REMAINS WITH THE COMPANY. REPRODUCTION PROHIBITED