Hampstead Green

Discharge Condition Schedule Five

Prior to commencement of development (excluding demolition and site preparation works), full details of hard and soft landscaping, including biodiversity enhancements and a lighting strategy, and means of enclosure of all un-built, open areas shall be submitted to and approved by the local planning authority in writing. Such details shall include details of proposed highway improvement and resurfacing works on Rowland Hill Street. The revelant part of the works shall not be carried out otherwise than in accordance with the details thus approved.

PegasusLife 04.05.2018



Filename: Discharge Condition Schedule Five

Issue History:

Revision:	Date:	Written by:	Checked by:
-	06.01.2016	-	-
A	04.05.2018	JN	AN



Summary of Proposed Changes

Omission of 2 No. CAP precast walls in central courtyard

Removal of walls allow an opening of the space, it will create views from the courtyard and building out into the gardens and green space ensuring the courtyard is less enclosing.

RC boundary retaining walls (school boundaries) to be faced up with timber hit and miss slatted cladding, brickwork cladding to be omitted

Trellis will provide a softer finish than the current brick, more in keeping with a garden context. Climbing plants specified along the boundary are not all self-attaching, a trellis will help support the plants allowing maintenance to fix the plants as they grow and establish. Extension of the trellis above the boundary wall will also mitigate concerns of overlooking from and to the neighbouring school.

Resin bound aggregate in lieu of clay paving to courtyards and all external areas up to side gate by car parker entrance into building

Resin bound surface is a more forgiving surface and less coarse in texture allowing greater comfort for wheel chair access. It is a permeable surface reducing the extent of surface drainage. Dutch clay pavers will be retained to form edging to paths, resin bound colour/specification will be selected to ensure a high aesthetic is maintained.

Hospital boundary party wall rebuild to remain as Camlins tender design but with possibility to be moved inboard on PL site and built off mass concrete temporary works bases near car parker entrance into building.

Raising external hard landscaping levels to the south elevation of Block D

Levels have been adjusted due to existing site beams constructed above current landscape levels. The change in height will remain below previous external finishes from the original site and will not affect the current landscape layout. Green buffers to neighbouring boundaries will be unchanged and maintained at the current offset.

Removal of access steps to café

Following design development it has been noted the slab levels of the lower ground pile caps are higher than the finished levels of the paving/steps at Ground Level. To mitigate this, we are proposing remove the steps and extend the retaining wall, planting will also be extended to screen any exposed structure. Access to the café and residential entrance will be maintained by the ramp.











