

	Ellis Williams Architects
project name	EJM UK 52-53 Russell Square
project number	2262
Schedule Number & Title	AX(3)01 - Proposed Internal Door Schedule
Date	28.2.2018
Issue number	P2 - Planning Application

General Notes:

1. Confirm all dimensions of existing structural openings on site
2. Existing Fire Doors generally to be upgraded: provide new intumescent and smoke seals.
3. All existing doors to occupied rooms have new suited Eurocylinder locks fitted with thumb-turn release to inside.
4. Lock suiting: Master (all); Submaster 1: Classrooms, offices, stores; Sub-m 2: Laboratories, prep rooms.
5. All doors to be fitted with full-height Finger Guards.

* - Dimensions to match existing S.O., check on site

Floor Level	Door Ref	Room Name	Room No.	Door Type	Description	Height S/O	Width S/O	Clear Width	Finish	Status	VP	Acoustic Rating	Fire Rating	Closer	Undercut	Ironmongery Set	Notes
Courtyard	D/C/N01	Classroom	C-03	1	Flush	2100	910	775	Painted	New	Y		FD30S	Y	Y	Classroom	
Courtyard	D/C/N02	Lobby	C-03	1	Flush	2100	910	775	Painted	New	Y		FD30S	Y	Y	Office	
Courtyard	D/C/N03	Shower	C-05	3	Moisture Resist	2100	910	775	HPL	New	N			Rising hinges	Y	Bathroom	
Courtyard	Ex	Plant room	C-10	Ex	Upgraded Extg	Existing	Existing		Painted	Existing	N		Upgrade with acoustic foam backing			Ex	
Ground Floor	D/G/N01	Lift Lobby	G-03	4	Panelled	2100*	1010*	800	Painted	New	N		FD30S	Y	Y	FD	
Ground Floor	D/G/N02	Link to Mews	G-03	4a	Panelled	2100*	1010*	800	Painted	New	Y		FD30S	Y	Y	FD	
Ground Floor	D/G/N03	Group Room	G-05	5	Flush	2100	910	775	Painted	New	N	30dB	FD30S	Y	N	Classroom	
Ground Floor	D/G/N04	Waste Store room	G-15	2	Flush	2100	910	775	Painted	New	N		FD30S	Y	N	Office	
Ground Floor	D/G/N05	Cycle Store room	G-16	1	Flush	2100	910	775	Painted	New	Y		FD30S	Y	N	Office	
Ground Floor	D/G/Ex01	Entrance lobby	G-03	Ex	Existing, fixed closed + sealed	Ex	Ex	n/a	Painted	Existing	N		FD30S	N	N	Removed, and sealed closed	
Ground Floor	D/G/Ex02	Reception	G-02	Ex	Existing, fixed closed + sealed	Ex	Ex	n/a	Painted	Existing	N		FD30S	N	N	Removed, and sealed closed	
First Floor	D/1/N01	Lift Lobby	F-02	4	Panelled	2100*	820*	tbc	Painted	New	N		FD30S	Y	Y	FD	
First Floor	D/1/N02	Classroom	F-03	4	Panelled	2100*	810*	tbc	Painted	New	N	30dB	FD30S	Y	Y	FD	
First Floor	D/1/N03	Office	F-07	5	Flush	2100	910	775	Painted	New	N	30dB	FD30S	Y	N	Office	
First Floor	D/1/N04	Store	F-07a	5	Flush	2100	910	775	Painted	New	N		FD30	Y	N	Store	
First Floor	D/1/Ex01	Classroom	F-05	Ex	Existing, fixed closed + sealed	Ex	Ex	n/a	Painted	Existing	N		FD30S	N	N	Removed, and sealed closed	
First Floor	D/1/Ex02	Classroom	S-05	Ex Double	Existing, fixed RH leaf closed + sealed	Ex	Ex	n/a	Painted	Existing	N		FD30S	N	N	Removed, and sealed closed	
Second Floor	D/2/N01	Lift Lobby	S-02	4	Panelled	2100*	860*	775	Painted	New	N		FD30S	Y	Y	FD	
Second Floor	D/2/N02	Classroom	S-03	4	Panelled	2100*	860*	775	Painted	New	N	30dB	FD30S	Y	Y	FD	
Second Floor	D/2/N03	Office	S-07	5	Flush	2100	910	775	Painted	New	N	30dB	FD30S	Y	N	Office	
Second Floor	D/2/N04	Store	S07a	5	Flush	2100	910	775	Painted	New	N		FD30	Y	N	Classroom	
Second Floor	D/2/Ex01	Classroom	S-05	Ex	Existing, fixed closed + sealed	Ex	Ex	n/a	Painted	Existing	N		FD30S	N	N	Removed, and sealed closed	
Second Floor	D/2/Ex02	Classroom	S-05	Ex Double	Existing, fixed RH leaf closed + sealed	Ex	Ex	n/a	Painted	Existing	N		FD30S	N	N	Removed, and sealed closed	
Third Floor	D/3/N01	Lift Lobby	T-02	4	Panelled	2100*	810*	tbc	Painted	New	N		FD30S	Y	Y	FD	
Third Floor	D/3/N02	Lobby	T-06	4	Panelled	2100*	880*	775	Painted	New	N		FD30S	Y	Y	FD	
Third Floor	D/3/N03	Prep Room	T-07	1	Flush	2100	910	775	Painted	New	Y		FD30S	Y	N	Office	
Third Floor	D/3/N04	Classroom	T-08	1	Flush	2100	910	775	Painted	New	Y	30dB	FD30S	Y	N	Classroom	
Third Floor	D/3/N05	Store	T-04	2	Flush	2100	910	775	Painted	New	N		FD30	Y	Y	Office	
Third Floor	D/3/N06	Prep Room	T-05	1	Flush	2100	910	775	Painted	New	Y		FD30S	Y	N	Office	
Fourth Floor	D/4/N01	Lift Lobby	Fo-02	4	Panelled	2100*	820*	tbc	Painted	New	N		FD30S	Y	Y	FD	
Fourth Floor	D/4/Ex-01	Lift Lobby	F-02	Ex	Remove door and Frame, M.G. walls												Remove door
Fourth Floor	D/4/Ex-02	Corridor	Fo-05	Ex	Upgrade acoustics - add new seals												
Fourth Floor	D/4/Ex-03	Corridor	Fo-05	Ex	Upgrade acoustics - add new seals, And new threshold												
Glazed Screens																	
Ground Floor	S/G01	Smoke Lobby	G-04	S1	Fixed FR Screen	2700	865	n/a	Painted	New	Fully-glazed	30dB	30/30/30				
Ground Floor	S/G02	Window guard	G-05	S2	Fixed acrylic screen	900	1750		Clear acrylic			n/a	n/a				
First Floor	S/101	Smoke Lobby	F-06	S1	Fixed FR Screen	2700	1800	n/a	Painted	New	Fully-glazed	30dB	30/30/30				
Second Floor	S/101	Smoke Lobby	S-06	S1	Fixed FR Screen	2400	1800	n/a	Painted	New	Fully-glazed	30dB	30/30/30				
Second Floor	S/202 a and b	Window guards	S-03	2x S2	2x Fixed acrylic screens	900	1300		Clear acrylic			n/a	n/a				
Third Floor	S/101	Smoke Lobby	S-06	S1	Fixed FR Screen	2400	1400	n/a	Painted	New	Fully-glazed	30dB	30/30/30				