



## ARBORICULTURAL IMPACT ASSESSMENT REPORT FOR:

South Lodge  
Heathside  
London  
NW3 1BL

## INSTRUCTING PARTY:

Greenway Architects  
Branch Hill Mews  
London  
NW3 7LT

## REPORT PREPARED BY

Adam Hollis  
MSc ARB MICFor FArbor A MRICS C Env

Ref: GWY/SLG/AIA/01b

Date: 4<sup>th</sup> May 2018

The content and format of this report are for the exclusive use of the client in planning. It may not be sold, lent, hired out or divulged to any third party, not directly involved in the subject matter without Landmark Trees' written consent

**Web:** [www.landmarktrees.co.uk](http://www.landmarktrees.co.uk)  
**e-mail:** [info@landmarktrees.co.uk](mailto:info@landmarktrees.co.uk)  
**Tel:** 0207 851 4544

**London Office:** Holden House, 4th Floor, 57 Rathbone Place London W1T 1JU

**Registered Office:** 15 Abbey Road, Oxford OX2 0AD

Landmark Trees is the trading name of Landmark trees Ltd. Registered in Wales. Reg No. 3882076



**PART 1: MAIN TEXT**

<b>Section</b>	<b>Content</b>	<b>Page N°</b>
1.0	SUMMARY	3
2.0	INTRODUCTION	4
3.0	OBSERVATIONS	6
4.0	DEVELOPMENT CONSTRAINTS	8
5.0	ARBORICULTURAL IMPACTS	11
6.0	DISCUSSION	12
7.0	CONCLUSION	15
8.0	RECOMMENDATIONS	16
9.0	REFERENCES	19

**PART 2 - APPENDICES**

APPENDIX 1	Survey Data	21
APPENDIX 2	Recommended Tree Works	25

**PART 3 - PLANS**

PLAN 1	Tree Constraints Plan	29
PLAN 2	Impact Assessment Plan(s)	31

## 1. SUMMARY

- 1.1 There are 12 trees within the application site with the and 1 standing on adjoining land outside of the application boundary that are within close proximity and need to be assessed.
- 1.3 Of these 13 trees, 1 is category A (High Quality, 3 are category B (Moderate Quality), 5 are category C (Low Quality) and 4 are category U (Poor Quality). It is judged that the Root Protection Area (RPA) of the off-site tree will be modified by existing boundary wall foundations and limited if not entirely excluded from the application site. Estimates below of percentage encroachment most likely overstate the impact in reality.
- 1.4 The report has assessed the impacts of the development proposals and concludes there would be at most a low impact on trees: A small proportion (7%) of the RPA of the off-site T13 would be impacted by the proposals. However, this gross figure is based on an even distribution of roots into the site / circular RPA, rather than their likely disruption by boundary wall foundations and existing hard standing. Net impacts are assessed as being very low – low impact.
- 1.5 Notwithstanding the above assurances, the report sets out a series of recommendations prior and during construction. This includes the need for trial pits prior to construction to confirm the extent or absence of tree roots within the application site, and a Full Arboricultural Method Statement with Tree Protection Plan to reconcile construction activities with the tree protection measures. These can be secured by planning condition, though we recommend the trial pits be undertaken now. We know at least from the site investigations that the existing extension walls are founded at more than 1m depth.
- 1.6 Trial pits may require some (minor) root pruning be agreed with the local authority as necessary. It would be prudent to undertake the trial pits ahead of planning. Minor cutting back of the canopy of T13 is also proposed and assessed as being low impact, given pruning works have already been undertaken in the past.
- 1.7 In conclusion, the proposal, through following the above recommendations, will have no, or very limited, impact on the existing trees and is acceptable.

\* British Standards Institute: Trees in relation to design, demolition and construction BS 5837: 2012 HMSO, London

## 2. INTRODUCTION

### 2.1 Terms of Reference

- 2.1.1 This Arboricultural Impact Assessment report has been prepared by Landmark Trees (LT) on behalf of Greenway Architects ('the Agent'), to support a full planning application submitted to the London Borough of Camden ('LBC').
- 2.1.2 The application relates to the removal and replacement of the existing single-storey rear extension with a ground floor + basement extension of larger size.
- 2.1.3 This report will assess the impact on the trees and their constraints, identified in our survey. Although the proposals were known at the time of the survey, Landmark Trees endeavour to survey each site blind, working from a topographical survey, wherever possible, with the constraints plan informing their evolution.
- 2.1.4 I am a Registered Consultant and Fellow of the Arboricultural Association and a Chartered Forester, with a Masters Degree in Arboriculture and 25 years' experience of the landscape industry - including the Forestry Commission and Agricultural Development and Advisory Service. I am a UK Registered Expert Witness, trained in single and joint expert witness duties. I am also Chairman of the UK & I Regional Plant Appraisal Committee, inaugurated to promote international standards of valuation in arboriculture.

### 2.2 Drawings Supplied

- 2.2.1 The drawings supplied by the client and relied upon by Landmark Trees in the formulation of our survey plans are:
- Existing site survey: 1938\_Existing floor plans
- Proposals: 1938\_Planning drawings

## 2.3 Scope of Survey

- 2.3.1 As Landmark Trees' (LT) arboricultural consultant, I surveyed the trees on site on 25<sup>th</sup> September 2017, recording relevant qualitative data in order to assess both their suitability for retention and their constraints upon the site, in accordance with British Standard 5837:2012 Trees in relation to design, demolition and construction – Recommendations [BS5837:2012].
- 2.3.2 Our survey of the trees, the soils and any other factors, is of a preliminary nature. The trees were SURVEYED on the basis of the Visual Tree Assessment method expounded by Mattheck and Breloer (The Body Language of Trees, DoE booklet Research for Amenity Trees No. 4, 1994). LT have not taken any samples for analysis and the trees were not climbed, but inspected from ground level.
- 2.3.3 A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two - three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter.
- 2.3.4 The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

## 2.4 Survey Data & Report Layout

- 2.4.1 Detailed records of individual trees are given in the survey schedule in Appendix. General husbandry recommendations are distinguished at Appendix 2 from minimum requirements to facilitate development which form part of the planning application at Appendix 3. The former may still be relevant to providing a safe site of work, of course. Planning considerations notwithstanding, we trust these necessary recommendations are passed on to relevant parties with due diligence and the trees be managed appropriately.
- 2.4.2 A site plan identifying the surveyed trees, based on the Instructing Party's drawings / topographical survey is provided in Part 3 of this report. This plan also serves as the Tree Constraints Plan with the theoretical Recommended Protection Areas (RPA's), tree canopies and shade constraints, (from BS5837: 2012) overlain onto it. These constraints are then overlain in turn onto the Instructing Party's proposals to create a second Arboricultural Impact Assessment Plan in Part 3. General observations and discussion follow, below.

### 3.0 OBSERVATIONS

#### 3.1 Site Description



Photograph 1: Existing rear extension to South Lodge, Heathside, London NW3 1BL

- 3.1.1 This property is located off the south-west corner of East Heath Road and comprises a Grade II listed Georgian house arranged over five floors and standing in extensive gardens.
- 3.1.2 The site is relatively level throughout.
- 3.1.3 In terms of the British Geological Survey, the site overlies the Claygate Member / Beds (see dark area on plan extract overleaf). As the youngest part of the London Clay, they form a transition between the clay and the sandier Bagshot Beds above (shown in yellow). Unlike the Bagshot Beds, more typical of Hampstead Heath, the associated soils are generally, highly shrinkable clay; e.g. slowly permeable seasonally waterlogged fine loam over clay. Such highly plastic soils are prone to movement: subsidence and heave.
- 3.1.4 The actual limits of soil series are not as clearly defined on the ground as on plan and there may be anomalies between them. Further advice from the relevant experts on the specific soil properties can be sought as necessary.
- 3.1.5 Clay soils are prone to compaction during development. Damage to soil structure can have a serious impact on tree health. Design of foundations near problematic tree species will also need to take into consideration subsidence risk.




Figure 1: Extract from the BGS Geology of Britain Viewer

### 3.2 Subject Trees

- 3.2.1 Of the 13 surveyed trees, 1 is category A (High Quality), 3 are category B (Moderate Quality), 5 are category C (Low Quality) and 4 are category U (Poor Quality).
- 3.2.2 The tree species found on and adjacent to the site comprise saucer magnolia, copper beech, cherry, Indian bean tree, Japanese cherry, olive, apple, pink chestnut, black walnut and weeping willow.
- 3.2.3 In terms of age demographics there are predominantly early mature and mature specimens present with a few young or semi-mature trees present.

\*page 9 of: [British Standards Institute: Trees in relation to design, demolition and construction BS 5837: 2012 HMSO, London](#)

- 3.2.4 Full details of the surveyed trees can be found in Appendix 1 of this report.
- 3.2.5 There are recommended works for 11 on-site trees. These are listed in Appendix 2.

### 3.3 Planning Status

- 3.3.1 We are not aware of the existence of any Tree Preservation Orders, but understand the site stands within the Hampstead Conservation Area, which will affect the subject trees: it is a criminal offence to prune, damage or fell such trees without permission from the local authority.
- 3.3.2 Relevant local planning policies comprise Policy 7.21 of the London Plan 2016 and Policies A3, D1 and D3 of the Camden Local Plan (adopted 3rd July 2017).

## 4.0 DEVELOPMENT CONSTRAINTS

### 4.1 Primary Constraints

- 4.1.1 BS5837: 2012 gives Recommended Protection Areas (RPA's) for any given tree size. The individual RPA's are calculated in the Tree Schedule in Appendix 1 to this report, or rather the notional radius of that RPA, based on a circular protection zone. The prescribed radius is 12-x stem diameter at 1.5m above ground level, except where composite formulae are used in the case of multi-stemmed trees.
- 4.1.2 Circular RPA's are appropriate for individual specimen trees grown freely, but where there is ground disturbance, the morphology of the RPA can be modified to an alternative polygon, as shown in the diagram below (Figure 2). Alternatively, one need principally remember that RPA's are area-based and not linear – notional rather than fixed entities.




Figure 2 – Generic BS 5837 RPA Adjustments

- 4.1.3 In BS5837, paragraph 4.6.2 states that RPA's should reflect the morphology and disposition of the roots; where pre-existing site conditions or other factors indicate that rooting has occurred asymmetrically, a polygon of equivalent area should be produced. Modifications to the shape of the RPA should reflect a soundly based arboricultural assessment of likely root distribution.
- 4.1.4 **No *a priori* modifications have been made in this instance, though our working assumption is that the boundary wall between T13 and the application site (and existing extension) will have significantly inhibited root development into the site.**



4.1.5 The quality of trees will also be a consideration: U Category trees are discounted from the planning process in view of their limited service life. Again, Category-C trees would not normally constrain development individually, unless they provide some external screening function.


4.1.6 At paragraph 5.1.1. BS5837: 2012 notes that "Care should be exercised over misplaced tree preservation; attempts to retain too many or unsuitable trees on a site are liable to result in excessive pressure on the trees during demolition or construction work, or post-completion demands on their removal."

4.1.7 Only moderate quality trees and above are significant material constraints on development. However, low quality trees comprise a constraint in aggregate, in terms of any collective loss / removal, where replacement planting is generally considered appropriate.


4.1.8 In this instance, the high and moderate quality trees have the potential to pose significant constraints upon development. Low-quality willow, T13, lies outside that range.

## 4.2 Secondary Constraints

4.2.1 The second type of constraint produced by trees that are to be retained is that the proximity of the proposed development to the trees should not threaten their future with ever increasing demands for tree surgery or felling to remove nuisance shading (Figure 3), honeydew deposition or perceived risk of harm.



4.2.2 The shading constraints are crudely determined from BS5837 by drawing an arc from northwest to east of the stem base at a distance equal to the height of the tree, as shown in the diagram opposite. Shade is less of a constraint on non-residential developments, particularly where rooms are only ever temporarily occupied.



4.2.3 This arc (see Figure 4) represents the effects that a tree will have on layout through shade, based on shadow patterns of 1x tree height for a period May to Sept inclusive 10.00-18.00 hrs daily.

4.2.4 The orientation of the on-site trees will ensure that shading constraints are minimal, with leaf deposition and honey-dew likely to be as it is today. However, the off-site T13 has the potential to provide a variety of secondary constraints, including shading, organic deposition and the potential need to maintain crown clearance in the future. The significance of these constraints will vary depending on the location and proximity to the proposed re-development which is considered below (in Sections 5 & 6). As specified by BS5837, this section (4) of the report considers only the site as it is, not in the light of pending proposals.

*Note: Sections 5 & 6 below will now assess the impacts of the proposals upon constraints identified in Section 4 above. Table 1 in Section 5 presents the impacts in tabular form (drawing upon survey data presented in Appendices 1 & 2). Impacts are presented in terms of whole tree removal and the effect on the landscape or partial encroachment (% of RPA) and its effect on individual tree health. Section 6 discusses the table data, elaborating upon the impacts' significance and mitigation.*

## Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to Matheny & Clark (1998))



Ref: GWY\_SLG\_AIA

B.S. Cat.	Tree No.	Species	Impact	Tree / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation
C	13	Willow, Weeping	Building Construction within RPA  Building Demolition within RPA	17.9 m <sup>2</sup> 7.03 %	Mature	Moderate	Moderate	Very Low	Very Low	Low-invasive foundation design  Light plant / mini-rigs only & from outside RPA

## 6.0 DISCUSSION

### 6.1 Rating of Primary Impacts

- 6.1.1 The principal impact in the current proposals comprises the removal and replacement of the existing extension within the theoretical circular RPA of the off-site willow T13. The slightly larger footprint of the replacement extension means that the existing encroachment of the RPA will increase by 7%. In gross terms, this is assessed as being of very low impact to the tree with the actual impact likely to be significantly less due to the inhibiting effect on root development the existing boundary wall will have. Trial pits can of course be provided to confirm this assessment.
- 6.1.2 The rebuilding of the extension within the existing footprint is not considered an impact as the distribution of an RPA below the existing building is in principle, unjustified: notwithstanding a reduced probability of rooting below significant structures (a 1m+ foundation depth as determined by the site investigations), the principle of protecting and promoting root colonisation below vulnerable building foundations conflicts with other responsibilities of / liabilities for the council.
- 6.1.3 Provided that the demolition of the existing extension is undertaken in a controlled manner, this process will be of negligible impact to the tree.
- 6.1.4 There will be a need to cut back the canopy of T13 to provide construction (and occupational) clearance but this is necessary regardless of development and given the tolerance of the species to pruning is not likely to be of significance to the future health of the tree.

- 6.1.5 The principal of RPA encroachment is established within BS5837:2012 and supported by the source document, National Joint Utilities Guidelines 10 / Vol. 4 1995 / 2010. NJUG introduced the x12 diameter *Precautionary Zone* for supervised working and *Prohibited Zone* at a universal 1m from the base of the tree. RPA's are frequently confused with the NJUG Prohibited Zone, when they clearly correlate with the NJUG Precautionary Zone.
- 6.1.6 An RPA encroachment of <20% of RPA may be considered as low impact, given the permissive references to 20% RPA relocation and impermeable paving within BS5837:2012 and other published references to healthy trees tolerating up to 30-50% root severance (Coder, Helliwell and Watson in CEH 2006). The trees in question are healthy specimens of species with a good resistance to development impacts, and quite capable of tolerating these low impacts.

- 6.1.7 “**In practice 50% of roots can sometimes be removed with little problem**, provided there are vigorous roots elsewhere. Inevitably, this degree of root loss will temporarily slow canopy growth and even lead to some dieback” (Thomas 2000). LT do not recommend annexing such high proportions of the root system; rather that within the context of the published science, planning should not be unduly concerned by impacts that are well below the subcritical threshold – *tree health is not at stake*.
- 6.1.8 BS5837 recommends (at 5.3.a) that if operations within the RPA are proposed, the project arboriculturist should demonstrate that the tree(s) can remain viable and that the area lost to encroachment can be compensated for elsewhere, contiguous with its RPA. On the basis of Thomas et al, above, it is possible to demonstrate that the tree can remain viable, and on the basis that the tree will be rooting no less freely in the garden / lawn / border /pavement than within the proposed footprint, with the RPA encroachment compensated elsewhere on contiguous land. The guide also recommends (at 5.3.b) the arboriculturist propose a series of mitigation measures (to improve the soil environment that is used by the tree for growth). These are provided at 6.3 below.

## 6.2 Rating of Secondary Impacts

- 6.2.1 There will always be marginal secondary impacts of honeydew / litter deposition and partial shade on this site, regardless of development. Whilst the proposals do entail building closer to the off-site T13, as Photograph 1 demonstrates, this tree already encroaches upon the existing extension and thus the status quo is unlikely to change with further development, which is the salient point for planning to consider. Currently, the tree does not exhibit vigorous regrowth from the last round of pruning and is diseased. Thus, the secondary impacts of development are minimal.

### 6.3 Mitigation of Impacts

6.3.1 All plant and vehicles engaged in demolition works should either operate outside the RPA, or should run on a temporary surface designed to protect the underlying soil structure. The demolition of the building should proceed inwards in a “pull down” fashion. Hard surfacing can be lifted with caution by a skilled machine operator again working away from the tree.

6.3.2 The path of foundations / limits of excavation through the RPA will be manually excavated to 750mm depth under arboricultural supervision; any roots encountered within the trenches / pits will be cleanly pruned back to an appropriate junction with a sharp pruning saw or secateurs back to a junction. Roots larger than 25mm diameter may only be cut in consultation with an arboriculturalist.

6.3.3 Nuisance deposition can be further mitigated with routine maintenance, light pruning / deadwooding and the fitting of filtration traps on guttering (see Figure 5 below).

6.3.4 The shading impacts can be mitigated by building design, with the provision of dual aspect windows and choice of room layout. Some minor crown reduction may be necessary, but not such as to impose a burden of frequent, repetitive management.




Figure 5: Filtration traps, as shown above, could be fitted on the gutters which can easily be maintained at 2-3m above ground.

## 7.0 CONCLUSION

- 7.1 The potential impacts of development are very low in terms of RPA encroachments of trees retained with no tree removal necessary to facilitate the proposals.
- 7.2 The full potential of the impacts can be largely mitigated through design and precautionary measures. These measures can be elaborated in Method Statements in the discharge of planning conditions.
- 7.3 The species affected are generally tolerant of root disturbance / crown reduction and the retained trees are generally in good health and capable of sustaining these nominal impacts.
- 7.4 Therefore, the proposals will not have any significant impact on either the retained trees or wider landscape thereby complying with Policy 7.21 of the London Plan 2016 and Policies A3, D1 and D3 of the Camden Local Plan (adopted 3rd July 2017). Thus, with suitable mitigation and supervision the scheme is recommended to planning.

## 8.0 RECOMMENDATIONS

### 8.1 Specific Recommendations

- 8.1.1 Tree works recommendations in Appendix 2 are not part of the current application, but requirements of general maintenance that will need to be applied for (subject to para. 3.3 of this report and any other relevant constraints in planning or leasehold) by the client separately. Consent for the current planning application does not impart any consent for the Appendix 2 maintenance works. Please note, though, the owner and / or manager of a property have a duty to maintain a safe site of work and to protect occupiers of the surrounding land / members of the public from tree hazards. Works recommended in this report should be enacted in a timely fashion by the relevant party regardless of the progress of the development.
- 8.1.2 Excavation and construction impacts within the RPA's of trees identified in Table 1 above, will need to be controlled by method statements specifying mitigation methods suggested in para 6.3 above and by consultant supervision as necessary. These method statements can be provided as part of the discharge of conditions.



## 8.2 General Recommendations for Sites Being Developed with Trees

- 8.2.1 Any trees which are in close proximity to the proposed development should be protected with a Tree Protection Barrier (TPB). Protective barrier fencing should be installed immediately following the completion of the tree works, remaining in situ for the entire duration of the development unless otherwise agreed in writing by the Council. It should be appropriate for the intensity and proximity of the development, usually comprising steel, mesh panels 2.4m in height ('Heras') and should be mounted on a scaffolding frame (shown in Fig 2 of BS5837:2012). The position of the TPB can be shown on plan as part of the discharge of conditions, once the layout is agreed with the planning authority. The TPB should be erected prior to commencement of works, remain in its original form on-site for the duration of works and be removed only upon full completion of works.
- 8.2.2 A TPB may no longer be required during soft landscaping work but a full arboricultural assessment must be performed prior to the undertaking of any excavations within the RPA of a tree. This will inform a decision about the requirement of protection measures. It is important that all TPBs have permanent, weatherproof notices denying access to the RPA.
- 8.2.3 The use of heavy plant machinery for building demolition, removal of imported materials and grading of surfaces should take place in one operation. The necessary machinery should be located above the existing grade level and work away from any retained trees. This will ensure that any spoil is removed from the RPAs. It is vital that the original soil level is not lowered as this is likely to cause damage to the shallow root systems.
- 8.2.4 Any pruning works must be in accordance with British Standard 3998:2010 Tree work [BS3998].
- 8.2.5 Where sections of hard surfacing are proposed in close proximity to trees, it is recommended that "No-Dig" surfacing be employed in accordance with BS5837:2012 and 'The Principles of Arboricultural Practice: Note 1, Driveways Close to Trees, AAIS 1996 [APN1]'.
- 8.2.6 If the RPA of a tree is encroached by underground service routes then BS5837:2012 and NJUG VOLUME 4 provisions should be employed. If it is deemed necessary, further arboricultural advice must be sought.
- 8.2.7 Numerous site activities are potentially damaging to trees e.g. parking, material storage, the use of plant machinery and all other sources of soil compaction. In operating plant, particular care is required to ensure that the operational arcs of excavation and lifting machinery, including their loads, do not physically damage trees when in use.

- 8.2.8 To enable the successful integration of the proposal with the retained trees, the following points will need to be taken into account:
- 1) Plan of underground services.
  - 2) Schedule of tree protection measures, including the management of harmful substances.
  - 3) Method statements for constructional variations regarding tree proximity (e.g. foundations, surfacing and scaffolding).
  - 4) Site logistics plan to include storage, plant parking/stationing and materials handling.
  - 5) Tree works: felling, required pruning and new planting. All works must be carried out by a competent arborist in accordance with BS3998.
  - 6) Site supervision: the Site Agent must be nominated to be responsible for all arboricultural matters on site. This person must:
    - be present on site for the majority of the time;
    - be aware of the arboricultural responsibilities;
    - have the authority to stop work that is causing, or may cause harm to any tree;
    - ensure all site operatives are aware of their responsibilities to the trees on site and the consequences of a failure to observe these responsibilities;
    - make immediate contact with the local authority and/or a retained arboriculturalist in the event of any tree related problems occurring.
- 8.2.9 These points can be resolved and approved through consultation with the planning authority via their Arboricultural Officer.
- 8.2.10 The sequence of works should be as follows:
- i) initial tree works: felling, stump grinding and pruning for working clearances;
  - ii) installation of TPB for demolition & construction;
  - iii) installation of underground services;
  - iv) installation of ground protection;
  - v) main construction;
  - vi) removal of TPB;
  - vii) soft landscaping.

## 9.0 REFERENCES

- Barlow JF & Harrison G. 1999. Shade By Trees, Arboricultural Practice Note 5, AAIS, Farnham, Surrey.
- British Standards Institute. 2012. Trees in Relation to Design, Demolition and Construction - Recommendations BS 5837: 2012 HMSO, London.
- Centre for Ecology & Hydrology. 2006. Tree Roots in the Built Environment, HMSO, London.
- Helliwell R (1980) Provision for New Trees; Landscape Design; July/August issue
- International Society of Arboriculture (ISA). 1994. The Landscape Below Ground. ISA, Champaign, Illinois. USA.
- Lonsdale D 1999. Research for Amenity Trees No.7: Principles of Tree Hazard Assessment and Management, HMSO, London.
- Matheny, N; Clark, J. R.1998. Trees and Development: A Technical Guide to Preservation of Trees during Land Development. ISA, Champaign, Illinois. USA.
- Mattheck C. & Breloer H. 1994. Research for Amenity Trees No.2: The Body Language of Trees, HMSO, London.
- Thomas P, 2000 & 2014. Trees: Their Natural History, Cambridge University Press, Cambridge.
- Trowbridge J & Bassuk N (2004) Trees in the Urban Landscape: Site Assessment, Design, and Installation; J Wiley & Sons inc. NJ USA

### Caveats

This report is primarily an arboricultural report. Whilst comments relating to matters involving built structures or soil data may appear, any opinion thus expressed should be viewed as qualified, and confirmation from an appropriately qualified professional sought. Such points are usually clearly identified within the body of the report. It is not a full safety survey or subsidence risk assessment survey. These services can be provided but a further fee would be payable. Where matters of tree condition with a safety implication are noted during a survey they will of course appear in the report.

A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two - three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter.

Tree works recommendations are found in the Appendices to this report. It is assumed, unless otherwise stated ("ASAP" or "Option to") that all husbandry recommendations will be carried out within 6 months of the report's first issue. Clearly, works required to facilitate development will not be required if the application is shelved or refused. However, necessary husbandry work should not be shelved with the application and should be brought to the attention of the person responsible, by the applicant, if different. Under the Occupiers Liability Act of 1957, the owner (or his agent) of a tree is charged with the due care of protecting persons and property from foreseeable damage and injury.' He is responsible for damage and/or nuisance arising from all parts of the tree, including roots and branches, regardless of the property on which they occur. He also has a duty under The Health and Safety at Work Act 1974 to provide a safe place of work, during construction. Tree works should only be carried out with local authority consent, where applicable.

Inherent in a tree survey is assessment of the risk associated with trees close to people and their property. Most human activities involve a degree of risk, such risks being commonly accepted if the associated benefits are perceived to be commensurate.

Risks associated with trees tend to increase with the age of the trees concerned, but so do many of the benefits. It will be appreciated, and deemed to be accepted by the client, that the formulation of recommendations for all management of trees will be guided by the cost-benefit analysis (in terms of amenity), of tree work that would remove all risk of tree related damage.

Prior to the commencement of any tree works, an ecological assessment of specific trees may be required to ascertain whether protected species (e.g. bats, badgers and invertebrates etc.) may be affected.



## PART 2 – APPENDICES

## APPENDIX 1

### TREE SCHEDULE

#### Botanical Tree Names

Apple	: Malus sp	Indian bean tree	: Catalpa bignonioides
Beech, Copper	: Fagus sylvatica f. purpurea	Magnolia, Saucer	: Magnolia × soulangeana
Cherry	: Prunus spp	Olive	: Olea europaea
Cherry, Japanese	: Prunus spp	Walnut, Black	: Juglans nigra
Chestnut, Pink	: Aesculus x carnea	Willow, Weeping	: Salix × sepulcralis

#### Notes for Guidance:

1. Height describes the approximate height of the tree measured in metres from ground level.
2. The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspect if symmetrical.
3. Ground Clearance is the height in metres of crown clearance above adjacent ground level.
4. Stem Diameter (Dm) is the diameter of the stem measured in millimetres at 1.5m from ground level for single stemmed trees. BS 5837:2012 formula (Section 4.6) used to calculate diameter of multi-stemmed trees. Stem Diameter may be estimated where access is restricted and denoted by '#'.
5. Protection Multiplier is 12 and is the number used to calculate the tree's protection radius and area
6. Protection Radius is a radial distance measured from the trunk centre.
7. Growth Vitality - Normal growth, Moderate (below normal), Poor (sparse/weak), Dead (dead or dying tree).
8. Structural Condition - Good (no or only minor defects), Fair (remediable defects), Poor - Major defects present.
9. Landscape Contribution - High (prominent landscape feature), Medium (visible in landscape), Low (secluded/among other trees).
10. B.S. Cat refers to (British Standard 5837:2012 section 4.5) and refers to tree/group quality and value; 'A' – High, 'B' - Moderate, 'C' - Low, 'U' - Unsuitable for retention. The following colouring has been used on the site plans:
  - █ High Quality (A) (Green),
  - █ Moderate Quality (B) (Blue),
  - █ Low Quality (C) (Grey),
  - █ Unsuitable for Retention (U) (Red)
11. Sub Cat refers to the retention criteria values where 1 is Arboricultural, 2 is Landscape and 3 is Cultural including Conservational, Historic and Commemorative.
12. Useful Life is the tree's estimated remaining contribution in years.



Site: South Lodge

Date: 21/09/2017

## Appendix 1

Landmark Trees Ltd

020 7851 4544

Surveyor(s): Adam Hollis

Ref: GWY\_SLG\_AIA

### BS5837 Tree Constraints Survey Schedule

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Stem Diamete	Age Class	Protection Radius	Growth Vitality	Structural Condition	B.S. Cat	Sub Cat	Useful Life	Comments
1	Magnolia, Saucer	8	5135	1.0	210	Early Mature	2.5	Normal	Fair	C	2	20+	Sprawling habit Split lower branch N 3m
2	Beech, Copper	16	10,11,10,11	1.5	1220	Mature	14.6	Normal	Good	A	1	40+	Entry wounds on stem Long lateral over road
3	Cherry	7	1	5.0	100	Semi-mature	1.2	Poor	Poor	U		<10	
4	Indian Bean Tree	10	3555	1.5	436	Early Mature	5.2	Normal	Poor	U		<10	Split Co-dominant stems
5	Cherry, Japanese	3.5	5232	2.0	150	Early Mature	1.8	Poor	Poor	U			Dead
6	Cherry, Japanese	3	5153	1.5	270	Mature	3.2	Moderate	Fair	C	2	10+	Graft incompatibility Canker Low path clearance



Site: South Lodge

Date: 21/09/2017

## Appendix 1

Landmark Trees Ltd

020 7851 4544

Surveyor(s): Adam Hollis

Ref: GWY\_SLG\_AIA

### BS5837 Tree Constraints Survey Schedule

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Stem Diamete	Age Class	Protection Radius	Growth Vitality	Structural Condition	B.S. Cat	Sub Cat	Useful Life	Comments
7	Olive	6	1.5	0.5	141	Young	1.7	Normal	Fair	C	2	20+	Strangled by support
8	Apple	6	3	1.5	250	Early Mature	3.0	Normal	Fair	B	2	40+	Dense canopy
9	Apple	6	3423	4.0	280	Mature	3.4	Moderate	Poor	U		<10	Decay in stem Storm-damaged tree
10	Chestnut, pink	12	4	1.0	680	Mature	8.2	Moderate	Fair	B	2	20+	Canker Leaf scorch
11	Chestnut, pink	6	3	1.0	200	Semi-mature	2.4	Moderate	Fair	C	2	20+	Leaf scorch Caught base in wire basket
12	Walnut, Black	15	5667	5.0	720	Mature	8.6	Normal	Fair	B	2	20+	Girdling roots Heavily pruned Some wounds not occluded, stip lesions in crown



Site: South Lodge

Date: 21/09/2017

## Appendix 1

Landmark Trees Ltd

020 7851 4544

Surveyor(s): Adam Hollis

Ref: GWY\_SLG\_AIA

### BS5837 Tree Constraints Survey Schedule

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Stem Diamete	Age Class	Protection Radius	Growth Vitality	Structural Condition	B.S. Cat	Sub Cat	Useful Life	Comments
13	Willow, Weeping	7	3322	3.0	750	Mature	9.0	Moderate	Poor	C	2	10+	Major decay in stem Pollarded, remote survey only (RS) Low vigor regrowth





## APPENDIX 2

### RECOMMENDED TREE WORKS

#### Notes for Guidance:

#### **Husbandry 1 - Urgent (ASAP), 2 - Standard (within 6 months), 3 - Non-urgent (2-3 years)**

CB	- Cut Back to boundary/clear from structure.
CL#	- Crown Lift to given height in meters.
CT#%	- Crown Thinning by identified %.
CCL	- Crown Clean (remove deadwood/crossing and hazardous branches and stubs)*.
CR#%	- Crown Reduce by given maximum % (of outermost branch & twig length)
DWD	- Remove deadwood.
Fell	- Fell to ground level.
FInv	- Further Investigation (generally with decay detection equipment).
Pol	- Pollard or re-pollard.
Mon	- Check / monitor progress of defect(s) at next consultant inspection which should be <18 months in frequented areas and <3 years in areas of more occasional use. Where clients retain their own ground staff, we recommend an annual in- house inspection and where practical, in the aftermath of extreme weather events.
Svr Ivy / Clr Bs	- Sever ivy / clear base and re-inspect base / stem for concealed defects.

\*Not generally specified following BS3998:2010



Site: South Lodge

Date: 21/09/2017

Surveyor(s): Adam Hollis

Ref: GWY\_SLG\_AIA

## Appendix 2

### Recommended Tree Works

[Hide irrelevant](#)  
[Show All Trees](#)

Tree No.	English Name	B.S. Cat	Height	Ground Clearance	Crown Spread	Recommended Works	Comments/ Reasons
1	Magnolia, Saucer	C	8	1.0	5135	CB	Sprawling habit Split lower branch N 3m Recommended husbandry 3
2	Beech, Copper	A	16	1.5	10,11,1 0,11	DWD CL	Entry wounds on stem Long lateral over road Recommended husbandry 2
3	Cherry	U	7	5.0	1	Fell	Recommended husbandry 2
5	Cherry, Japanese	U	3.5	2.0	5232	Fell	Dead Recommended husbandry 2
6	Cherry, Japanese	C	3	1.5	5153	Mon	Graft incompatibility Canker Low path clearance Recommended husbandry 3
7	Olive	C	6	0.5	1.5	Remove tie	Strangled by support Recommended husbandry 2



Site: South Lodge

Date: 21/09/2017

Surveyor(s): Adam Hollis

Ref: GWY\_SLG\_AIA

## Appendix 2

### Recommended Tree Works

[Hide irrelevant](#)  
[Show All Trees](#)

Landmark Trees

Tree No.	English Name	B.S. Cat	Height	Ground Clearance	Crown Spread	Recommended Works		Comments/ Reasons
8	Apple	B	6	1.5	3	CR	20%	Dense canopy Recommended husbandry 2
9	Apple	U	6	4.0	3423	Fell	Fell	Decay in stem Storm-damaged tree Recommended husbandry 3
10	Chestnut, pink	B	12	1.0	4	Mon Remove compost heap		Canker Leaf scorch Recommended husbandry 3
11	Chestnut, pink	C	6	1.0	3	Remove basket		Leaf scorch Caught base in wire basket
12	Walnut, Balck	B	15	5.0	5667	Mon		Girdling roots Heavily pruned Some wounds not occluded, stip lesions in crown Recommended husbandry 3






Landmark Trees

---

## PART 3 – PLANS

**PLAN 1**

**TREE CONSTRAINTS PLAN**



**NOTE:**  
 This survey is of a preliminary nature. The trees were inspected from the ground only on the basis of the Visual Tree Assessment method. No samples were taken for analysis. No decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.  
 Branch spread in metres is taken at the four cardinal points to derive an accurate representation of the crown.  
 Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base).

**Landmark Trees**  
 20 Broadwick Street, London, W1F 8HT  
 Tel: 0207 851 4544 Mobile: 07812 989928  
 e-mail: info@landmarktrees.co.uk Web: www.landmarktrees.co.uk

Site: South Lodge  
 Drawing Title: Tree Constraints Plan  
 1:200@ A1  
 October 2017

**Key:**


- Category A High Quality
- Category B Moderate Quality
- Category C Low Quality
- Category U Trees Unsuitable for Retention

Category — Crown Spread  
 Tree Number  
 Species  
 Category  
 Root Protection Area  
 Tree Position Approximate (not shown on original survey)

**PLAN 2**

**ARBORICULTURAL IMPACT ASSESSMENT PLAN (S)**

- i. Ground Floor



**NOTE:**  
 This survey is of a preliminary nature. The trees were inspected from the ground only on the basis of the Visual Tree Assessment method. No samples were taken for analysis. No decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.  
 Branch spread in metres is taken at the four cardinal points to derive an accurate representation of the crown.  
 Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree).

**Landmark Trees**  
 20 Borewallis Street, London, W1P 8HT  
 Tel: 0207 851 4544 Mobile: 07812 99328  
 Email: info@landmarktrees.co.uk Web: www.landmarktrees.co.uk

Site: South Lodge  
 Drawing Title: Arboricultural Impacts Assessment  
 1:200 @ A1  
 March 2018

**Key:**

- Category A High Quality
- Category B Moderate Quality
- Category C Low Quality
- Category U Trees Unsuitable for Retention

**Category Legend:**

- Crown Spread
- Tree Number
- Stems
- Category
- Root Protection Area
- Tree Protection Approximate (not shown on original survey)