



NOTES

- 1.00 THE INTRUDER ALARM SYSTEM SHALL BE WIRED IN MULTICORE SECURITY SYSTEM CABLING BY THE ELECTRICAL CONTRACTOR. TAMPER PROOF PROTECTION IS TO BE PROVIDED TO ALL CIRCUITS & DEVICES.
- 2.00 THE SYSTEM IS TO BE INSTALLED, TESTED & COMMISSIONED & CERTIFIED IN FULL COMPLIANCE WITH BS EN 7958 2015.
- 3.00 THE ELECTRICAL CONTRACTOR SHALL EMPLOY THE SERVICES OF A REGISTERED ALARM INSTALLER.
- 4.00 THE POWER SUPPLY FOR THE INTRUDER ALARM SYSTEM SHALL BE COMPLETELY DEDICATED WITH THE MAIN DISCONNECTION DEVICE SECURED FROM UNAUTHORISED OPERATION.
- 5.00 FOR ASSOCIATED ELECTRICAL SERVICES SPECIFICATIONS REFER TO THE FOLLOWING SECTIONS: • E.00 - GENERAL SPECIFICATIONS
 - E.41 INTRUDER DETECTION & ALARM SYSTEMS
 - E.42 ACCESS CONTROL SYSTEMS E.43 - CCTV
- 6.00 ALL CABLING ASSOCIATED WITH CCTV SYSTEM TO BE CARRIED OUT BY THE ELECTRICAL CONTRACTOR UNDER THE INSTRUCTION OF THE SPECIALIST SECURITY CONTRACTOR.

DOOR INTERCOM / DOOR ACCESS SYSTEM



WALL MOUNTED VIDEO PHONE HANDSET C/W DOOR RELEASE FUNCTION AND INDUCTIVE AUDIO COUPLER.

GREEN BREAK GLASS UNIT FOR EMERGENCY RELEASE.

REX 🔵

TRANSOMAGNETIC DOOR LOCKS C/W INTEGRAL INTRUDER ALARM CONTACTS.

DOOR ACCESS REQUEST TO EXIT BUTTON (STAINLESS STEEL FINISH)

IAP INTRUDER ALARM PANEL.

CCTV - FIXED CCTV CAMERA C/W VANDAL PROOF HOUSING.

S1 ISSUED FOR COORDINATION S2 ISSUED FOR INFORMATION FOR COMPILATION OF IN2 DRAWING. S3 ISSUED FOR INTERNAL REVIEW AND COMMENT ARCHITECTURAL DRAWING REVISION : P1 S4 ISSUED FOR CONSTRUCTION APPROVAL

S3 11.05.2018 PRELIMINARY ISSUE JDT JW BF P1 STATUS DATE DRN ENG APP REV



ENGINEERING DESIGN PARTNERSHIP DUBLIN . ATHLONE . BELFAST . LONDON

BELSIZE PARK FIRESTATION

PLATINUM LAND

DRAWING TITLE ELECTRICAL SERVICES INSTALLATION GROUND FLOOR LEVEL - UNITS 13 & 14 SECURITY & ACCESS CONTROL SERVICES LAYOUT

SCALE SIZE PROJECT REF: DRAWING No.

NOTE: ARCHITECTURAL DRAWING USED

DATE RECEIVED : 12.01.2018