



WALLS:

| | |
|--|---|
| | EXISTING WALLS & COLUMNS |
| | NEW PARTITIONS & WALL LININGS partitions 30min fire rated 150mm above new ceiling level only |
| | NEW PARTITIONS & WALL LININGS partitions 30min fire rated full height to underside of slab |

NOTES:

- 01 NEW SHOPFRONT WINDOWS & DOOR
new timber framed full height glazed shopfront & 1100w entrance door, shopfront frames 100mm side / 10p rails and 50mm dividing frames w/ 583h from internal ffl stall riser all painted dark grey dulux 00NN 13/000. new 1100w 2200h timber frames door with dark grey dulux 00NN 13/000 painted frame, glazing to comply with building regulations. shopfront to be built to structural engineers requirements.
- 02 LEVEL FLOOR W/ NEW STEP UP
existing floor slab retained. existing step up to be retained allow to level out floor with step up to new entrance.
- 03 REPAINT EXISTING ORIGINAL COLUMNS
make good, repair and repaint 2no. existing columns in dark grey dulux 00NN 13/00 apart from top mouldings and detail to central part of column which are to be painted in light grey dulux 00NN 31/000 as shown on drawing.
- 04 RESTORE EXISTING COLUMNS TO REPLICATE ADJACENT ORIGINAL COLUMN DETAIL
replicate all details on original existing columns with new stonework cladding + mouldings and paint in dark grey dulux 00NN 13/00 apart from top mouldings and detail to central part of column which are to be painted in light grey dulux 00NN 31/000 as shown on drawing.

CLIENT
★ PRET ★

PROJECT
FINCHLEY ROAD
219 FINCHLEY ROAD LONDON NW3 6LP

DRAWING No.
TD18-PM93-PL01 .1

TITLE
proposed layout

REVISIONS
A: external pavement added. notes revised.

REVISION DATE SCALE @ A3
A 11.06.18 1:100

All dimensions to be confirmed on site by Contractor.
Structural works to be confirmed by Structural Engineer.
All elements to comply with statutory requirements.

Copyright Tanner Design Limited
2b/4b Gosport Street Lymington Hampshire S041 9BE
tel. 01590 689609 email. studio@tannerdesign.co.uk
www.tannerdesign.co.uk

Tannerdesign