
Key			
	arts to be stripped out. Any brickwork and roof tiles to be Ivaged where possible		
NOTES:		-	
All works to be in a	ccordance with Conservation Specifications.		
All redundant servic	ces to be removed.		
joinery, plasterwork	g fabric, including floor finishes, window joinery, door k, skirting and iron mongery are to be altered or herwise shown on the drawings.		
Operatives: - Appropriately sk - Holding or in trai Site staff responsib the assessment of Dust Control: General: Reduce a with an appropriate clear of mud and d Lead dust: Submit clean-up regimes. Health Hazards: Precautions: Protect associated with vib course of the Work Partly Demolished - General: Leave in a each stage to previ- working hours. Temporary works: I Unauthorised persac Dangerous Openin General: Illuminate Asbestos Containin Discovery: Give nor materials discoverere materials. Methods for safe reformation Site Condition at C- Debris: Clear away Other requirements Recycling	method statement for control, containment and ct site operatives and general public from hazards pration, dangerous fumes and dust arising during the s. Structures: a stable condition, with adequate temporary support at ent risk of uncontrolled collapse. Keep safe outside Prevent debris from overloading. ons: Prevent access. gs: and protect. Keep safe outside working hours. ng Materials: tice immediately of suspected asbestos containing ed during demolition work. Avoid disturbing such emoval. Submit details and statutory risk assessments. Is: tanks, chemicals, etc. discovered during demolition: emoval, filling, etc: Submit details. ompletion: and leave the site in a tidy condition. a: Building occupied at all times and must be kept clear	CHIMNEYS    Existing face brickwork and chimney pots to be cleaned using water based system only; no chemical clean permitted. Brickwork to be repointed; any damaged brickwork to be repaired where possible or replaced with matching brickwork. Damaged chimney pots to be replaced to match existing.    ROOF	
All Materials removed from site are to be recycled offsite where ever possible. This includes existing floor finishes noted for removal (i.e. existing vinyl and carpet), metal framework and concrete/blockwork.		be retained, refurbished and protected throughout the construction programme. Materials and finish to match existing.	
		All gutters to be cleaned and checked. Where damaged to be replaced to match existing.	
		NEW OPENING New opening to be formed in existing wall. Brickwork to be carefully cut-out and/or toothed in as required. Re-use selvaged brickwork where possible.	
		Existing roof and associated structure to be removed. Any fixings/flashing to abutting wall to be carefully removed as to not damage brickwork.	

SIDE EXTENSION Load bearing walls and roof structure to be removed. Where brickwork is toothed in with masonry forming flank wall, this is to be carefully cut-out.

WINDOW Existing window and associated ironmongery to be removed.

EXTERNAL PIPEWORK – Pipework to be removed and re-configured to suit new proposals.

Ground FFL 88.34



SCAL	0 0.5 E - 1:50	1	1.5		2.5 m	
Rev:	Comments:			By:	Date:	Cli
А	Amended rooflight/note			DW	14-06-2018	-

Do not scale this drawing All dimensions must be checked on site All rights reserved. No reproduction in any material form is permitted without consent.

Roofing material to be removed and replaced to suit proposals.

### LEANING CHIMNEY

Chimney stack to be re-built as per Structural Engineer's recommendation. Brickwork to be carefully removed and re-used. Any damaged bricks and chimney pots to be replaced to match existing.

New opening to be formed within existing roof. Roof supporting structure to be adapted to suit new rooflights. Any roof tiles to be salvaged where

Existing rooflight and associated ironmongery to be removed. Roof opening supporting structure to be adapted to suit new proposed rooflight position. All materials to match existing. Salvaged roof tiles to be re-used where

All flashing to be checked and repaired as required. Any damaged flashing to be replaced with matching material.

Existing roof and associated structure to be removed. Any fixings/flashing to -abutting wall to be carefully removed as to not damage brickwork.

### EXTERNAL WALL

Existing face brickwork to be cleaned using water based system only; no chemical clean permitted. Masonry to be re-pointed; any damaged brickwork to be repaired where possible or replaced with matching

Windows and associated ironmongery to be removed. Cill to be lowered forming new door opening. Brickwork to be carefully cut-out and/or toothed in as required. Re-use salvaged brickwork where possible.

Existing roof and associated structure to be removed. Any fixings/flashing to abutting wall to be carefully removed as to not damage brickwork.

Windows and associated ironmongery to be removed. Cill to be lowered forming new door opening. Brickwork to be carefully cut-out and/or toothed in as required. Re-use salvaged brickwork where possible.

### SIDE EXTENSION

Load bearing walls and roof structure to be removed. Where brickwork is toothed in with masonry forming flank wall, this is to be carefully cut-out.

### EXTERNAL PIPEWORK

Pipework to be removed and re-configured to suit new proposals.

# PLANNING

## Client:

Project Title: 24 Heath Drive. London. NW3 7SB

Drawing Title: Strip-Out North-East Elevation Scale: Date:

Drawn: 1:50@A1 JAN 18 ST

## Studio

Checked:

ΗV

28 Scrutton Street London UK EC2A 4RP

T: +44(0) 20 7247 2462 E: enquiries@kyson.co.uk W: www.kyson.co.uk

Project No.: Drawing No.: Revision: 508-16 1603 А

# Kyson