BUROHAPPOLD ENGINEERING

UCL Institute of Education

Interim Sustainability Statement – Phase 1 Wing Levels 4&5

035833

18 April 2018

Revision 01

Revision	Description	Issued by	Date	Checked
00	Sustainability Statement	CVD	16 Apr 18	MD
01	Sustainability Statement	CVD	18 Apr 18	MD

O:\035833 UCL Institute of Education\F42 Sustainability\03 Reports\180412 Phase 1 Levels 4&5 planning report\180413 UCL IOE - Phase 1 Wing Levels 4&5 sustainability statement 00.docx

This report has been prepared for the sole benefit, use and information of Client name for the purposes set out in the report or instructions commissioning it. The liability of Buro Happold in respect of the information contained in the report will not extend to any third party.

author	Chris Van Dronkelaar
date	18 April 2018
approved	Mark Dowson
signature	Monson
date	18 April 2018

...

Contents

1	Executive Summary 7						
2	Plannin	g requirements	8				
	2.1	Camden Planning Guidance – Sustainability CGP3	8				
3	Baselin	e performance	10				
	3.1	Overview	10				
	3.2	Running costs	10				
	3.3	Energy use	10				
	3.4	CO ₂ emissions	11				
	3.5	Fabric performance	11				
4	Energy	strategy	13				
	4.1	Overview	13				
	4.2	BREEAM energy modelling	13				
	4.2.1	Methodology	13				
	4.2.2	Modelling inputs	13				
	4.2.3	Preliminary modelling results	16				
	4.2.4	Summary and recommendations	16				
5	Wider S	Sustainability (BREEAM)	17				
	5.1	Overview	17				
	5.2	BREEAM tracker	17				
	5.3	BREEAM pre-assessment score – Phase 1 Wing Level 4&5	17				
6	Summa	ry and vision	18				
	6.1	Summary	18				
	6.2	Investing in sustainability	18				
	6.3	Wider socio-economic benefits	18				
	6.4	Next steps	19				

Appendix A – BREEAM tracker

1 Executive Summary

This report sets out the interim sustainability statement for planning for Phase 1 of the UCL Institute of Education refurbishment, covering Wing Levels 4&5. Studies contained include a summary of the baseline building performance, the energy strategy, the BREEAM pre-assessment and responses to Camden planning criteria.

The UCL Institute of Education is a Grade II* listed building, however despite this limiting factor significant efforts are being made by the design team to enhance the sustainability of the building. Key measures include:

- Improving the thermal performance of the building fabric in line with heritage constraints, through the addition of secondary glazing, where consented, and internal insulation to cladding panels.
- Upgrading all major MEP systems and lighting. To comply with Building Regulations, all performance values are better or equal to Part L2B 2010 (including 2016 amendments) and Non-Domestic Building Services Compliance Guide 2013.
- Retaining connection to the Bloomsbury Heat and Power network, which includes boiler and combined heat and power plant, enabling up to 80% of the building's electricity to come from low carbon sources.
- BREEAM 'Excellent' strategy this includes a wide variety of sustainability measures including the integration of low flow water fittings, responsible sourcing of construction materials, measures to enhance site ecology, security studies, acoustic measures and stringent sustainability criteria for the Contractor. Currently a BREEAM pre-assessment score of 77.5% (Excellent with a 7.5% buffer) has been identified.

In terms of total CO₂ reduction for the Phase 1 Wing levels 4&5 areas, preliminary modelling following the BREEAM refurbishment and fit out calculation methodology shows up to a 46% reduction in regulated CO₂ emissions compared to the existing building, meeting the BREEAM Excellent minimum requirements (at least 6 credits in Ene01). During RIBA Stage 3-4 onwards, further coordination with the Contractor, Building Control and heritage specialist shall be conducted to develop the final design strategy, adhering to the project sustainability targets.

It is currently estimated that for Phase 1, 19.8% of the project budget will be spent on energy efficiency improvements (including fabric improvement measures, new HVAC plant, lighting, controls and metering. This is in line with the "Camden Council Planning Guidance – Sustainability CGP3" for guidelines existing buildings which requires 10% of project cost to be spent on energy efficiency.

In terms of renewable energy, there is a Camden Planning requirement to target at least a 20% reduction in carbon dioxide emissions through the installation of on-site renewable energy technologies. For UCL IOE, the only applicable on-site form of renewable energy would be solar photovoltaics (which are estimated to save 2.3% of CO₂ across Phases 1-3), however these are potentially contentious according to the heritage consultant. If PV panels are to be considered, these will be brought forward in future refurbishment phases in discussion with Camden and Historic England. It should be noted that the site is served by the Bloomsbury Combined Heat and Power (CHP) district network, which according the Display Energy Certificate allows the UCL IOE building to obtain up to 80% of its electricity from low carbon sources.

In summary, there is good potential to undertake an extensive and sustainable refurbishment for the UCL Institute of Education, which achieves BREEAM Excellent and enhances thermal comfort. The works undertaken in Phase 1 levels 2&3, and now levels 4&5 also have investigated many of the opportunities for the UCL IOE refurbishment applicable to later phases and setting a positive ethos for the project.

2 Planning requirements

2.1 Camden Planning Guidance – Sustainability CGP3

The table below outlines the Camden Council planning requirements in relation to sustainability for existing buildings. Preliminary comments in relation to the UCL IOE Phases 1 Wing levels 4&5 are given.

Table 2-1 - Camden council planning requirements or	n sustainability relevant for IOE.
---	------------------------------------

		Requirement			Commentary
Sustair	nability assessment	tools (BREEAM)			
•	Submission of a pr report should sum of BREEAM and/or credits proposed t Pre-assessment rep of the assessor and report. You are strongly en with Development construction:	The project is targeting a BREEAM Excellent rating with a single assessment across Phases 1-3. The project is currently targeting 75% of the energy credits. 67% of water credits are currently targeted. 61% of materials credits are currently targeted.			
	Time period	Minimum rating	Minimum standard for categories (% of un-weighted credits)		The licenced BREEAM assessor is Adonis
	2010-2012 2013+	'very good' 'excellent'	Energy 60% Water 60% Materials 40%		Charalambous (AC61). The licenced BREEAM AP is Mark Dowson (1000124).
•	 efficiency: existing All buildings, whet their carbon emiss Work involving a c included. As a guid improvements. Where retro-fitting most likely secure way of condition. Development invo m of any floorspace credits in the Energy Special consideration 	Substantial works are planned to improve the energy efficiency of this Grade II* listed building. For L2&3 and ISD L3, based on the interim cost check report, it was estimated that 19.8% of project costs are being spent on energy efficiency for Phase 1. Levels 4&5 would be similar, given the same level of energy efficiency is being applied.			
Renew	All developments a emissions through Special considerati ensure that their h	Solar PV provides up to 2.3% CO_2 savings, however the heritage consultant has confirmed this is potentially contentious. If PV is considered, these will be brought forward in future phases in discussion with Camden & Historic England.			

Decent	alised energy	Levels 4&5 will be connected
•	Where feasible and viable your development will be required to connect to a decentralised energy network or include CHP.	to the Bloomsbury Heat and Power (BHP) district heating network
Water e	fficiency	Low flow fittings will be
•	The Council expects all developments to be designed to be water efficient by minimising water use and maximising the re-use of water. This includes new and existing buildings. The Council will require developments over 1000sq m to include a grey water harvesting system, unless the applicant demonstrates to the Council's satisfaction that this is not feasible.	targeted as part of refurbishment works in line with BREEAM Wat 01. Grey water recycling feasibility to be confirmed by MEP engineer in Phases 2&3.
Sustain	able use of materials	A pre-refurbishment waste
•	All developments should aim for at least 10% of the total value of materials used to be derived from recycled and reused sources. This should relate to the WRAP Quick Wins assessments or equivalent. Special consideration will be given to heritage buildings and features to ensure that their historic and architectural features are preserved. Major developments are anticipated to be able to achieve 15-20% of the total value of materials used to be derived from recycled and reused sources.	audit has been carried out or Wing L2&3 and ISD L3. This identified that 35% of materials can be re-used or recycled. For BREEAM, this study shall will extended to capture Wing L4&5. All materials sourcing will be in line with BREEAM responsible sourcing requirements.
Adaptir	g to climate change	A climate change risk
•	All development is expected to consider the impact of climate change and be designed to cope with the anticipated conditions.	assessment was conducted for BREEAM credit Wst05 covering all of Phase 1. BREEAM thermal comfort modelling has been carried out for L4&5.
Brown	oofs, green roofs and green walls	
•	The Council will expect all developments to incorporate brown roofs, green roofs and green walls unless it is demonstrated this is not possible or appropriate. This includes new and existing buildings. Special consideration will be given to historic buildings to ensure historic and architectural features are preserved.	As the building is listed, the ecologist has recommended that external terrace areas include planters with native species
Floodin	g	The site is located in flood
•	Developments must not increase the risk of flooding, and are required to put in place mitigation measures where there is known to be a risk of flooding. Within the areas shown on Core Strategy Map 5 (Development Policies Map 2) we will expect water infrastructure to be designed to cope with a 1 in 100 year storm event in order to limit the flooding of, and damage to, property.	risk zone 1 (low risk of flooding). The proposed Phase 1-3 refurbishment works will not increase surface water run-off.
Externa	l lighting	BREEAM requirements for
•	Lighting can have particular negative impacts on biodiversity. Unnecessary lighting should be avoided. Where lighting may harm biodiversity timers or specific coloured lighting will be required to minimise any disturbance.	external lighting have been embedded into the project.
Local fo	od growing	Local food growing is not
•	We encourage food to be grown wherever possible and suitable. Rooftops and shared spaces such as gardens and parks provide opportunities.	incorporated into the scheme but shall be raised to the ecologist.
Biodive	rsity	An ecology study has been
•	Proposals should demonstrate how biodiversity considerations have been incorporated into the development; if any mitigation measures will be included; and what positive measures for enhancing biodiversity are planned.	completed, recommending planting of native species on external terrace areas.

3 Baseline performance

3.1 Overview

This section gives an overview of the baseline performance of the UCL Institute of Education, covering running costs, energy use, CO₂ emissions and fabric performance. The study covers the whole IOE building.

3.2 Running costs

The UCL Institute of Education building is an expensive asset to run, spending over half a million pounds on energy every year. This is not sustainable and represents a key area to be considered as part of refurbishment works.

Total annual running costs	£515,000/year
Electricity costs (Aug-14 to Jul-15)	£330,000/year
District heating costs (Aug-14 to Jul-15)	£185,000/year

3.3 Energy use

Based on historic energy surveys, it is estimated that approximately 45% of the buildings energy use is for heating and hot water via a district heat network. The remaining 55% of energy use can be attributed to electricity consumption, with lighting being the main source of electrical energy use. 5% of total building energy use can also be attributed to electric heating, indicating that the building is currently not meeting thermal comfort standards. Measures to improve fabric performance, where appropriate and unregulated electricity consumption should therefore be prioritised.




Figure 3-1 - Energy consumption by end-use for 20 Bedford Way (UCL IOE carbon management plan, 2014)

3.4 CO₂ emissions

In terms of CO₂ emissions, the UCL Institute of Education building actually performs very well. This is because the building is connected to the existing Bloomsbury Heat and Power (BHP) district heating network, which provides low-carbon heat as well as renewable electricity generated simultaneously via a CHP (combined heat and power) engine. According to the building's display energy certificate, 78.8% of the building's electricity is supplied from this renewable source. This gives the building an operational performance rating of a "B". By reducing the initial energy consumption, this can improve the operational performance further.

For Phase 1 Wing levels 4&5, both heating and domestic hot water and heating will be provided from the district heating network. The diagram below illustrates the carbon factor of this network, and the implications of this on the overall in-use carbon emissions of the existing building.




Figure 3-2 - District heating illustration (left) and operational performance rating (middle/right) (DEC number 0650-0313-7079-7509-006)

3.5 Fabric performance

Despite the good CO₂ performance, a key consideration for the UCL IOE refurbishment relates to thermal comfort for users and the building fabric performance. This is because the 1970s building has a significant amount of single glazing, large areas of original cladding panels, as well as un-insulated concrete walls. In addition, according to the facilities manager many users complain periodically about the building being too hot in summer and too cold in winter. A thermal imaging assessment has been undertaken by BuroHappold sustainability to investigate these issues.

The key findings from the study were:

- Heat loss from the IOE is much higher than that of adjacent buildings of older construction.
- Heat losses through the windows and window frames at IOE is significant; the seals on window frames could also be improved throughout the building to avoid air leakage when windows are not closed properly.
- The cladding panels perform marginally better than the glazing. Cladding joints show moderate heat loss.
- The thermal performance of glazing on the wing (by Core A) is poor
- Some windows were open during the survey. This may suggest poor heating/ventilation control.

The main recommendations (which have all now taken place) were:

- Upgrade the thermal performance of the façade, prioritising new glazing.
- Develop internal insulation strategy to treat cladding panels and thermal bridging.
- Façade engineer to be appointed to carry out investigation on improvement options / solutions to treating thermal bridging in consultation with heritage specialist.

A selection of images from the thermal imaging study, the Phase 1 wing are given below. As a result of this exercise, a façade condition survey was carried out giving 3 improvement options in correspondence with the heritage consultant. This has resulted in secondary glazing, where consented and internal insulation being applied to the Wing.




Figure 3-3 - Thermal image showing large sources of heat loss through the curtain walling




Figure 3-4 - Thermal image showing the end of the IOE building compared to adjacent buildings




Figure 3-5 - Thermal image of the Phase 1 wing

4 Energy strategy

4.1 Overview

This section of the report describes the energy strategy for the Phase 1 level 4&5 areas of the UCL IOE refurbishment.

In order to demonstrate compliance with BREEAM, energy modelling is required comparing the existing building performance to the refurbished case. The minimum standard for the 'Excellent' rating under BREEAM credit "Ene01 – reduction of energy use and CO₂ emissions" is 6 credits (out of a possible 15). Preliminary modelling demonstrates that for Wing Levels 4&5, a total of 13 credits are feasible with the current energy strategy.

For Building Regulations Part L2B, note that an "elemental compliance" route is being followed, which does not require modelling. The relevant version of the Building Regulations are Part L2B 2010, incorporating 2016 amendments. Draft proposals and mark-ups for this Building Control submission have been prepared and issued to the Contractor as part of the RIBA stage 2 submission. This includes details of fabric performance levels (currently in development) and system efficiencies.

4.2 BREEAM energy modelling

This section contains the preliminary energy performance calculation in line with BREEAM RFO whole building modelling requirements for Phase 1 Wing levels 4&5. The study has been prepared in accordance with BREEAM credit Ene01 criteria 1 (option 1).

4.2.1 Methodology

IES VE 2017 has been used to calculate the Energy Performance Ratio for Non Domestic Refurbishment (EPRNDR) and assess the wing level 4&5 design performance against Ene 01.

The BREEAM RFO method aims to assess the existing building performance to the proposed refurbishment. At present, many spaces are redundant and largely unoccupied. As it would be unreasonable to compare future energy consumption against this low benchmark the modelling approach has been divided into the 2 following modelling steps;

- Step 1- the existing building performance is modelled (old fabric and old systems) with the proposed model geometry, space use and NCM occupancy profiles. This model is used to generate the Actual (existing) and Reference data for the EPR rating tool.
- Step 2- the proposed building is modelled (new fabric and new systems) with the proposed model geometry, space use and NCM occupancy profiles. This model is used to generate the Actual (proposed) data for the EPR rating tool.

4.2.2 Modelling inputs

The energy modelling conducted covers the Phase 1 Wing level 4&5 (layouts received from Hawkins Brown on 27-02-2018). The model is shown in Figure 4-1.




Figure 4-1 - Wing Level 4&5 IES model

Building fabric

Building fabric input parameters for the existing and proposed building models are summarised below:

 Table 4-1 Modelling inputs tested (building fabric parameters) and Part L2B

			Improved	Part L2B 2013				
		Existing: (assumed based on review of available information)	Improved (Secondary glazing + opaque wall elements and roof upgraded.)	Threshold of retained Element	Value of replacement element	New thermal elements and controlled fittings		
	Solid wall	2.5 (300mm cast dense concrete, membrane)	0.3 for new thermal elements	0.7	0.3	0.28		
Fabric U- values	Roof	2.3 (400mm concrete deck & membrane, concrete tile 100mm)	0.18 (400mm concrete deck, insulation 100mm & membrane, concrete tile 100mm) *	0.35	0.18 flat roof			
(W/m2K)	Internal wall	2.5 (200mm cast concrete medium)	1 (lightweight plaster)	-	-	-		
	Internal floor/ceiling	2.6 (300 reinforced concrete, 20mm screed)	2.6 (300 reinforced concrete, 20mm screed)	-	-	-		
External	U-value	6 (single glazing metal frame	2.1	3.3	1.8 W/m ² K Or heritage constraint doe			
glazing	G-value	0.73	0.4	-	not allow to achieve a centre pane U value of 1.8 W/m2K.			
Air tightness	50 pa (m3/h.m2 @ 50 Pa)	19 (to be tested by contractor)	6.5 (target to be tested by contractor)		-			

* Conservative values taken - Contractor to confirm Part L compliant strategy

Building services

Building services input parameters for the existing and proposed building models are summarised below:


 Table 4-2 System modelling inputs. Figures marked with * are assumed performance levels.

	Existing	Improved	Part L2B limiting efficiencies for new systems
Heating	Central heating using water, radiators		
Description	Existing rads		
Heat source	District heating		
Pump type	Constant speed		
SCOP	0.92	0.92	
Cooling		Water cooled fan coil systems	
SEER / EER		4.5 / 3.6	
Ventilation	Centralised balanced mech vent		
Duct air leakage standard	Not tested	Not tested	
AHU air leakage standard	Class worse than L3 or not tested	L1	
Pump type	Constant speed	Variable speed with differential sensors	Either of B&ES DW/144, BS EN1507:2066, BS EN 12237:2003, BS EN 13403:2003
Heat recovery %	0%	70%	Thermal wheel > 65%
Extract fan SFP (W/(l/s) (e.g. toilet)	0.8 @ 10ACH	0.4 @ 10ACH	AHU to comply as a minimum with Class L2
Metering			
System metering	no	yes	
Metering warn "out of range" values	no	no	
DHW			
Storage volume	600L each	600L each	
Storage losses (kWh/(l.day))	0.0063	0.0063	
Circulation losses (W/m)	30	7	
Pump power	0.2	0.2	
Heating system controls			
Central time control	no	yes	To comply with as a minimum with the Non- Domestic Building Services Compliance Guide
Optimum start and stop	no	yes	
Local temperature control	no	yes	
Local time control	no	yes	
Weather compensation	no	no	
Lighting			
Efficacy Im/W	40	60 to 80	>60 lm/W
Controls	Switch	Dimming/PIR/Time	-
Parasitic power W/m2	0.1 W/m2	0.3 W/m2	-
DH carbon factor (kgCO ₂ /kWh)	0.25	0.25	-

4.2.3 Preliminary modelling results

Energy modelling results are given below. As shown, 13 credits for BREEAM RFO Ene01 are achieved in the preliminary modelling. Total CO_2 savings are estimated at 46% for the measures tested over the baseline.

 Table 4-3 Preliminary Ene01 modelling results for Phase 1 levels 4&5.



4.2.4 Summary and recommendations

Energy modelling for BREEAM Ene 01 shows that 13 credits may be achieved for Wing Levels 4&5. The analysis presented in this section is to be updated by the contractor as the design and underlying assumptions progress. The contractor is to ensure compliance with Part L2B, the Non-Domestic Building Services Compliance Guide recommendations and to ensure a minimum of 13 credits are achieved under BREEAM RFO Ene 01 for Phase 1.

5 Wider Sustainability (BREEAM)

5.1 Overview

BREEAM (which stands for the "Building Research Establishment Environmental Assessment Methodology") sets the standard for best practice in sustainable building design, construction and operation and has become one of the most comprehensive and widely recognised measures of a building's environmental performance.

Phases 1-3 of the UCL IOE refurbishment will be submitted together under one BREEAM 2014 (RFO) refurbishment and fit out assessment 2014. The "UCL Sustainable Building Standard" states that all refurbishment projects with building services <u>or</u> building fabric upgrades must achieve a **BREEAM Excellent** rating.

In order to facilitate this approach in a complex phased project will require careful project management with the Contractor providing design stage and post construction BREEAM evidence for each element of the project as if it were a single assessment in its own right.


Supporting this process, the Contractor has nominated a Sustainability Champion throughout the design and construction process to formally report progress on BREEAM items to the client and BREEAM Assessor. Providing overall leadership to the BREEAM assessment are BuroHappold, who are appointed in a client side role as BREEAM Assessor and BREEAM AP for the project.


5.2 BREEAM tracker

<u>Appendix A</u> sets out a detailed BREEAM tracker for the project scheduling out the BREEAM credits targeted for the Excellent rating, and current pending actions. Actions are separated out in terms of each element of the project, as well as indicating which evidence can be used at a masterplan level covering all elements in Phase 1.

5.3 BREEAM pre-assessment score – Phase 1 Wing Level 4&5

The BREEAM pre-assessment score for Wing Level 4&5 is set out in Figure 5-1. Overall, a low risk score of 77.5% is identified. Note that a 5% buffer above 70% is desired target. As shown, 15.2% of applicable design stage evidence has already been secured from a combination of the RIBA stage 1 and 2 credits being closed out, as well as evidence for a number of masterplan studies being in place.





6 Summary and vision

6.1 Summary

This report has covered an analysis of the baseline performance for the UCL Institute of Education, the Phase 1 Wing Levels 4&5 energy strategy, BREEAM pre-assessment and responses to Camden planning criteria.

In summary, there is good potential to undertake an extensive and sustainable refurbishment for the UCL Institute of Education, which achieves BREEAM Excellent and provides comfortable internal environments. Works undertaken to date for Phase 1 have shown that this will require investment in passive design and fabric improvements, for which an appropriate strategy has been developed in line with the heritage consultant advice.

6.2 Investing in sustainability

The IOE currently spends approximately £515,000/year on energy, which is obviously a very significant amount. Based on energy modelling conducted to date it is estimated that if the proposed fabric renovation works were applied to the whole building, the cost saving over 25 years including expected fuel price rises would be in the order of £2.2 million. Over a 60 year period the cost saving comes to an estimated £5 million, as illustrated below.




Figure 6-1 – Space heating running cost comparison with and without façade upgrade

6.3 Wider socio-economic benefits


Throughout this project, a case has been built to UCL that the investment in the façade should not be considered solely on a CapX vs. OpX model. Instead it should be appreciated that improvements to the façade will improve thermal comfort and noise, as well as light and air quality. This in turn improves health, well-being and productivity for occupants and ultimately provides wide economic savings.

In terms of quantifying this indirect productivity saving, there is a large body of research linking the internal built environment with improvements in health, well-being and productivity.

Example research papers include:

- 3% gain in productivity achieved by improved personal control over workspace temperature (Loftness et al, 2013).
- Better air quality can result in an 8-11% improvement in overall productivity (Loftness et al, 2013).
- Noise reduction in the workplace can increase productivity by up to 28% (Oseland and Burton, 2012)

In terms of quantifying this indirect cost benefit, according to published records on the 'Research Excellence Framework (REF)' portal, from 2008 and 2013 the average research income at the UCL Institute of Education was £15.5 million/year. If it was considered that the fabric refurbishment could improve overall productivity by 2% then over a 25 year period the total economic benefit could be up to £10 million. Over a 60 year period the total economic benefit could be up to £25 million.



Fabric energy saving Value associated with 2% increase in UCL IOE research income

Figure 6-2 – Potential cost benefit from fabric upgrade including additional 2% productivity gain on research income

6.4 Next steps

Moving forward into the detailed design and construction stages for the Phase 1 refurbishment, further work will be undertaken to establish a set of baseline data for the IOE on metric such as thermal comfort, health, well-being and perceived productivity in the building. A user survey to support this process is currently being organised through the IOE, using the industry recognised 'Building Use Studies' (BUS) survey. This will inform the concept design stages for Phases 2 and 3 (and beyond), then also be available for benchmarking during a post occupancy evaluation as part of the client's commitment to long term sustainability.

Despite the constraints of this existing listed building, significant efforts have been made to date to improve the energy performance of the asset. As the design progresses, further work shall be carried out to develop detailed strategies for all IOE phases in line with the BREEAM Excellent requirements, the UCL Sustainable Building Standard, Building Regulations Part L2B and the Camden Planning requirements for existing buildings.

Appendix A – BREEAM tracker

BREEAM Refurbishment and Fit Out 2014 Tracker

В	υ	R	0	н	Α	Ρ	Ρ	0	L	D
Е	Ν	G	Ι	Ν	Е	Е	R	Ι	Ν	G

Scheme: Project: BRE Ref: Stages:	BREEAM RFO 2014 UCL Institute of Education Phase 1 BREEAM-0067-3285 Phase 1 Wing L2&3 and ISD L3 (RIBA Stage 4), and Phase 1 Wing L2&3 (RIBA Stage 2)			Select >> TARG TARGETED LOW R MINIMUM STANDARDS ON ACHIEVED CR ACHIEVED CR	TRACK? YES EDITS (DS) 15.2%		Phase 1 - L4&5 Excelent (70%) 0.005 15255 62356 12376 12 0% 10% 20% 30% 40% 50% 60% 70% 80% 90% 1	100% 110%	ENGINEERING
Date: Rev:	13-Apr-18 17						Achieved - PC Achieved - DS Target - low risk Potential - high r	isk Not Targeted	
Credit Re	Caulii Kowa	tBA Stage	vailable core Value	IOE Masterplan 75.8 90.9 19.0 22.2 0.0 X5 90.9 19.0 22.2 0.0 YS D D C C YS D D C D YS D D C D YS D D D D D	Phase 1 - L2&3 & ISD L3 24.3 87.8 22.1 25.7 0.0 382.8 22.1 25.7 0.0 24.3 87.8 22.1 25.7 0.0 382.8 20.1 25.7 0.0 24.3 87.8 22.1 25.7 0.0 93.9 50.6 1.0 2.0 2.4 9.9 9.6 1.0 2.4 1.0 2.4 1.0	Phase 1 - L4&S 77.5 89.8 19.4 15.2 0.0 77.5 89.8 19.4 15.2 0.0 782 X9 Pase EL 0.0 0 0 782 X9 Pase EL 0.0 0 0 0 99 BE Pase Pase PL 0.0 0	Owner Design stage actions (and risks) (lead JOE Masterplan - Phase 1 support)	Owner Design stage actions (and risks) (laad Phase 1 - L283 & ISD L3 support	Owner Design stage actions (and risks) (lead, support) Phase 1 - 1.48.5
		2	* S	^l argete High Not Achii	Act Act	Act Act	Green = Design stage evidence closed	Green = Design stage evidence closed	Green = Design stage evidence closed
MANAG	EMENT	_							
Man 01	Project Brief and Design								
Man 01	Stakeholder Consultation - Project Delivery (Defining roles and responsibilities)	Stage 2	1 0.65%	1 1	1 1	1	Crit 1a-e, 2, 3a-k - All early stage masterplan evidence covering Arcadis. Phases 1-3 received covering all Crit. HB Crit 4 - See specific phases	Accades. HB Crit 1a-e, 2, 3a-k - See masterplan evidence. Crit 4 - Meeting minutes and updated project execution plan for Phase 1 levels 283 and ISD Level 3 provided.	Arcadic Crit 1a-e, 2, 3a-k See masterplan evidence. LB Crit 4 - Meeting minutes and updated project execution plan for Phase 1 levels 4&S to be provided.
Man 01	Stakeholder Consultation - Third Parties (End users, local community, statutory consultees, etc.)	Stage 2	1 0.65%	1 1	1 1	1	Crit 5 - Consultation evidence from masterplan stages provided. HB Crit 6 - Masterplan phasing strategy evidence provided. Arcadic Crit 2 - See specific phase. Crit 2 - Architect leading consultation independently.	Crit 5 - Consultation evidence provided (UCL, MUM, heritage) HB Crit 6 - Design / phasing strategy presentations provided for phase Arcadis Crit 2 - Phase 1, karge 3 design team presentation provided. Crit 2 - Architect leading consultation independently.	Crit S - Consultation evidence needed (UCL, MLM, heritage) HB Crit 6 - Design / phasing strategy presentations needed Arcadis Crit 2 - Feedback resentations to stateholders needed Crit 8 - Architect leading consultation independently. Image: Crit 8 - Architect leading consultation independently.
Man 01	Sustainability Champion (Design Stage) - Appointment of a BREEAM AP to set BREEAM performance targets	Stage 1	1 0.65%	1	1	1	Crit 9 Mark Dowson (BuroHappold) appointed as BREEAM AP BH sust Crit 10 RREEAM Excellent turget included in UCL Sust Standard Arcadis Crit 11 RREEAM Excellent turget included in UCL Sust Standard Arcadis Crit 11 RREEAM Excellent turget included in UCL Sust Standard Arcadis Crit 11 RREEAM Excellent turget included in UCL Sust Standard Assumed this is low risk currently. Crit 10 Crit 10	n/a n/a	n/a n/a
Man 01	Sustainability Champion (Design Stage) - Involvement of a BREEAM AP to monitor and advise on BREEAM progress	Stage 2 - 4	1 0.65%	1 1	1 1	1	Bit sust Crit 12 - Dependent on securing previous credit Crit 13 - See specific phases	Crit 12 - See masterplan evidence. <u>BH sust</u> Crit 13 - BREEAM AP evidence at RIBA stages 2-4 gathered. BH to write up Stage 4 evidence to close credit.	Crit 12 - See masterplan evidence. BH sust Crit 13 - BREEAM AP evidence at RIBA stages 2-4 to be gathered and written up.
Man 02	Life Cycle Cost and Service Life Planning								
Man 02	Elemental Life Cycle Cost (LCC) analysis to PD156865:2008	Stage 2	2 1.30%	2 2	2 2	2	n/a n/a	AECOM Grit 1-2 - AECOM have provided an LCC study specific to the phase, including a fabric options study.	Crit 1-2 - AECOM will need to update previous report to reflect AECOM addition of the new floors. Action from PM (Ajet) to Su Chia. Note: this is a RIBA Stage 2 study. this is a RIBA Stage 2 study.
	Component Level LCC Plan to PD156865:2008 (Envelope, Services, Finishes and external spaces)	Stage 4	1 0.65%	1	1	1	n/a n/a	AECOM Srit.3 - RIBA Stage 4 LCC report received from AECOM specific to the phase. BH to write up evidence to close credit.	AECOM Crit 3 - As above, AECOM will need to update the RIBA Stage 4 LCC study to reflect the addition of the new floors.
	Capital Cost Reporting (£/m2) to the BRE		1 0.65%	1	1	1	n/a n/a	AECOM Crit 4. RIBA Stage 4 capital cost confirmation needed (Stage 3 confirmation is already in place).	AECOM Crit 4. RIBA Stage 4 capital cost confirmation needed
Man 03	Responsible Construction Practices								
	Pre-Requisite: Responsibly sourced timber		Pre- requisit - e	<u>Y</u> 1	<u>Y</u> 1	<u>Y</u> 1	n/a n/a	Mace Crit 1-2 - Mace have provided a letter of intent for "Phase 1" continuing that all timber will be legally harvested and traded.	Mace Crit 1-2 - Mace have provided a letter of intent for "Phase 1" confirming that all timber will be legally harvested and traded.
	Environmental Management System operated by the Principal Contractor (E.g. ISO14001, BS8555)		1 0.65%	1	1	1	Crit 2-3 - Mace have provided a letter of intent confirming they Mace have an EMS in place and that PPG51 will be followed. EMS certificate needed to close, together with PPG61 examples.	n/a n/a	n/a n/a
	Sustainability Champion (Construction Stage) - BREEAM AP appointed to monitor and advise on progress	Stage 5 Stage 6	1 0.65%	1 1	1 1	1 1	Criticity - Make have confirmed that Conor Storkey is the Contractor's BBERMA No. The Sotialiability Employees Marce requirements also confirm that this is required. Critity - RREEAM Excellent must be achieved to secure credit. Assumed this is low risk currently.	n/a n/a	n/a n/a
	Considerate Construction (CCS or equivalent) (ONE CREDIT NEEDED FOR BREEAM EXCELLENT)		2 1.30%	2 1	2 2	2 1	n/a n/a	Coll 25.8 - Nace have provided a letter of intent confirming that "Phase 1" will be registered for the Considerate Construction Marcs Score of AD with 7 in all sections. Currently 39 achieved 180316) CCS resortation related to be confirmed	CH 7-8 - Mace have provided a letter of intent confirming that "Phase 1" will be registered for the Considerate Construction Scheme, targeting a score of 40 with 7 in all sections. CCS registration details to be confirmed.
	Monitoring of Construction-site impacts (Energy and water consumption: transport movements for delivery of materials and waste transfer)		2 1.30%	2	2	2	n/a n/a	Citl 2 - Mace to confirm who is responsible for site monitoring Citl 10-15. Wace have confirmed in a letter for "Phase 1" that many and water shall be monitored. Mace Citl 16-13 - Mace to confirm transport monitoring shall be in line with BREAM RFO requirements (current wording in letter is slightly different to manual, e.g. MF not mentioned).	Citt.3 - Mace to confirm who is responsible for site monitoring Citt.30-15 Mace have confirmed in a letter for "Phase 1" that merely and water shall be monitored. Citt.15-13 - Mace to confirm transport monitoring shall be in line with BREAM RFO requirements (current wording in letter is slightly different to manual, e.g. MP not mentioned).
Man 04	Commissioning and Handover								· · · · · · · · · · · · · · · · · · ·
	Commissioning and Testing Schedule, including assignment of responsibilities, in line with Building Regulations, CIBSE and BSRIA.		1 0.65%	1	1	1	n/a n/a	Grit 1-4. The BH MEP employers requirements for L2&3 and ISD L3 for Mace made reference to all BREAM requirements. Mace to Mace mode commissioning schedule, the testing programme and BH Mech Confirm who is responsible to monitor and programme pre- commissioning, commissioning, testing and, where necessary, re- commissioning activities on behalf of the client.	Crit 1-4 - Mace to confirm that all BREEAM commissioning Mace requirements are included in the RBA Stage 3-d design, and BH Mech provide all supplementary evidence as per previous levels. Same evidence can apply if same appointments are extended to L4&S.
	Commissioning Building Services - Appointment of a specialist commissioning manager	Stage 4	1 0.65%	1	1	1	n/a n/a	Crit 5 - Criteria 1-4 to be achieved. Grit 5 - The BH MEP employers requirements for L283 and ISD L3 for Mace made reference to all BREEAM requirements. Mace to confirm who is apportate a specialist commissioning manager, as well as their responsibilities.	Mace Crit 14 - Mace to confirm that all BREAM commissioning requirements are included in the RBA Stage 3-d design, and provide all supplementary evidence as per previous levels. Same evidence can apply if same appointments are extended to 1485.

		IOE Masterplan % 75.8 90.9 19.0 22.2 0.0	Phase 1 - L2&3 & ISD L3 74.3 87.8 22.1 25.7 0.0	Phase 1 - L4&5 77.5 89.8 19.4 15.2 0.0			
Credit F	ef: Credit Issue (Mandatory Credits for Excellent shown red)	Available % Score Value Targeted - Low Risk High risk - TBC Not Targeted Achieved - DS Achieved - PC	Targeted - Low Risk High risk - TBC Not Targeted Achieved - DS Achieved - PC	Targeted - Low Risk High risk - TBC Not Targeted Achieved - DS Achieved - PC	Owner (ead: support) Design stage actions (and risks) IOE Masterplan - Phase 1 Green = Design stage evidence closed	Owner (lead support) Design stage actions (and risks) Green = Design stage evidence closed	Owner (lead support) Design stage actions (and risks) Phase 1 - L485 Green = Distign stage evidence closed
	Testing and Inspecting Building Fabric (E.g. Thermographic survey, air tightness)	1 0.65% 1	1 I	1	n/a n/a	Crit 7.4 - The BH sustainability employers requirements confirmed Maca that air rightness testing and thermal imaging is required and that BH Mech jany defects must be remedied. Design stage evidence can be closed.	Mace Cit 2-8 - Mace to confirm that levels 485 will also be air tightness tested and undergo thermal imaging, with any defects rectified.
	Handover - Building User Guide and Training Schedule (Crit 10 NEEDED FOR BREEAM EXCELLENT)	1 0.65% 1	1 1	1	n/a n/a	Grit 3 - Requirements for the BUG were included in the BH MEP Mace. preliminaires for 1283 and 150 13. BH Meth Grit 10 - Requirements for the training schedule were also included in the BH MEP preliminaries.	Crit 9-10. Mace to provide design stage evidence for L485 Confirming that the BUS and training schedule will be completed in line with BREEAM requirements.
Man 0	Aftercare						
	Aftercare Support for building occupants (Aftercare team for 12 months; Energy/water monitoring for 12 months)	1 0.65% 1	1	1	n/a n/a	Mace BH Mech Set 1.2 - The BH sustainability employers requirements included the requirements for aftercare support. Mace has provided letter confirming that all aftercare requirements will be met.	Mace Crit 1-2 - Mace to provide letter confirming that all aftercare requirements will be met.
	Seasonal Commissioning over a 12 month period post- occupation (ONE CREDIT NEEDED FOR EXCELLENT RATING)	1 0.65% 1	1	1	n/a n/a	Mace. Crit 3 - The BH MEP preliminaries for L283 and ISD L3 contain seasonal commissioning requirements. Mace has provided letter confirming that all aftercare requirements will be met.	Mace Crit 3 - Mace to confirm that all seasonal commissioning requirements in BREEAM RFO will also be allowed for in L485.
	Post Occupancy Evaluation (Independent third party POE one year after occupation)	1 0.65% 1	1	1	LCL Crit 4-5 - Letter of intent has been issued to UCL Signed copy to be sent back to close design stage action.	n/a n/a	n/a n/a
	H & WELLBEING						
Hea 01	Visual comfort						
	Glare Control Strategy (E.g. Building integrated measures, brise soleil, blinds)	1 0.77% 1	1 1	1	n/a n/a	HB. Mace required for all windows.	HB, Mace Crit 1.2 - Architectural specs / drawings required to confirm that all windows on L4&S will also have blinds installed.
	Daylighting	3 2.32% 1 2	3	2 1	n/a n/a	Mace Crit 3-5 - RIBA Stage 2 pre-assessment for Phase 1 achieved 19% RES. compliance (i.e. no credits). 30% needed for 1 credit. RES (Appointed BH sust by Mace) to provided RIBA Stage 4 daylight results.	Mace RES, BH sust divight results, 1 credit awarded under method 2.
	View Out	2 1.55% 1 1	1 1	1 1	n/a n/a	Crit 6.2 Criciti s challenging for these areas, however Phase 1 areas still need to be assessed at 53ag 40 for inclusion in wider Marce masterplan assessment. Macc/ Phoenix to provide analysis for Phase market 80% of occursed spaces are within m of wall, window must be 20% of wall area or more depending on room depth check BS 8206	Crit.E.5 - 1.453 areas to be assessed at Stage 4 for inclusion in wider materiplan assessment Mace/Phoenic hit provide analysis for Mace Phase 1 areas.B% of occupied spaces are within 7m of wall window must be 20%-of wall area or more depending on room depth check BS 8206
	Internal and External Lighting Levels to CIBSE codes; Adequate zoning and local occupant control	1 0.77% 1	1	1	n/a n/a	Crit 10-16 The BH MEP specifications included the BREEAM Macce requirements. Macce to ensure strategy complies and provide BH Elec necessary evidence. Macce to provide nesseary evidence (specs, marked up drawings, lighting calcs) with letter signed.	Crit 10-16: Mace to provide design stage evidence for L485 Mace covering internal lighting, external lighting and zoning/occupant control (e.g., specs, marked up drawings, lighting calcs with letter signed).
Hea 02	Indoor air quality						
	Indoor Air Quality Plan	1 0.77% 1 1	1 1	1 1	<u>BH IAO</u> <u>Crit 1</u> - The BH environment team have prepared in the indoor air <u>team</u> Mace to note requirements.	n/a n/a	n/a n/a
	Minimising sources of external air pollution - Ventilation Strategy	1 0.77% 1	1	1	n/a n/a	Crit 2.4 - Venitation standards included in BH MRP specs (p31) Macc Crit 2.4 - Venitation standards up drawing showing distances between intakes and exhausts and sources of external pollution. Crit 5 Venitation schematics provided by BH MRP showing location of CO2 servors in mechanically venitated areas.	Ance Crit 2-5 - Provide design stage evidence to demonstrate compliance in Levels 48:5, allowing for different standards in nat vent vs mechanically ventilated areas.
	Minimising sources of internal air pollution - Specification of Low VOC finishes and fittings	1 0.77% 1	1 1	1	n/a n/a	Crit 5-7 - HB included a table in the architectural specifications <u>HB, Mace</u> listing out all applicable products and VOC standards. Mace to ensure it is implemented and provide evidence.	Mace Crit 6-7 Mace to provide details of VOC standards to be applied for levels 485. HB to provide evidence if they are providing specifications.
	Minimising sources of internal air pollution - Pre-completion indoor air quality testing	1 0.77% 1	1 1	1	n/a n/a	<u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>Mace</u> <u>M</u>	Mace Crit 8-12 - Mace to provide letter confirming that the VOC testing shall also take place 'post construction, but pre-occupancy' on L485.
	Potential for Natural Ventilation	1 0.77% 1	1	1	Credit not achievable. Early modelling showed the need for n/a mechanical cooling. BREEAM credit requires full nat vent everywhere.	n/a n/a	n/a n/a
Hea 03	Safe Containment in Laboratories						
	Laboratory containment devices and containment areas	0 0.00%			n/a Confirmed 19 Jan 2017, that labs are likely to be included in Phase 2 (Phase 1) & 3 scope of works, n/a to Phase 1.	n/a n/a for this phase	n/a n/a for this phase
	Buildings with containment level 2 and 3 laboratory facilities	0 0.00%			n/a Scope for labs on project TBC. If labs are Cat 2 or 3, then these (Phase 1) credits would be required also.	n/a n/a for this phase	n/a n/a for this phase
Hea 04	Thermal Comfort					Cdi 1 C. Di oversioshila oversioshila oversioshila oversioshila	
	Thermal Modelling	1 0.77% 1 1	1 1	1 1	n/a n/a	Crit 1.5. Bit sustainability undertook preliminary modelling at RBA Mace. Stage 3. R55 Sopported by Macel provides RBA Stage 4 modelling R55. results showing compliance with CBSE Guide A writer and summer. Bit sust temperature ranges, as well as report on RVV and RPD indices under current and future climate scenarios.	Maco RES. BH sust BH sust
	Adaptability - For a Projected Climate Change Scenario	1 0.77% 1 1	1 1	1 1	n/a n/a	Macc. Cittle - Deproduct on orbital 3-15 billing achieved. RES. Souge 4: Including PM/VPD reporting BH starts Cittle - De Andrea MM/VPD reporting Cittle - No failing spaces Cittle - No failing spaces	Maco RES. BH sust Ine with BREAM requirements.

				,	IOE Masterplan % 75.8 90.9 19.0 22.2 0.0	Phase 1 - L2&3 & ISD L3 74.3 87.8 22.1 25.7 0.0	Phase 1 - L4&5 77.5 89.8 19.4 15.2 0.0			
	Credit Re		RIBA Stage	Available % Score Value	Targeted - Low Risk High risk - TBC Not Targeted Achieved - PC Achieved - PC	Targeted - Low Risk Hgh risk - TBC Not Targeted Achieved - DS Achieved - DS	Targeted - Low Risk High risk - TBC Not Targeted Achieved - DS Achieved - PC	(lead, support)	(lead Phase 1 - L2&3 & ISD L3 support) Green = Design stage evidence closed	(lead, Phase 1 - L4&5
				1 0.77%	6 1	1	1	n/a n/a	Crit 11 - BH MEP specifications conform to design stage modelling Mace Crit 12 BH MEP HVAC zoning drawings provided as prelimary BH Meh evidence. Mace to provide final zoning drawings. Crit 12be - BH MEP meeting minutes provided confirming that	Mace confirm how modelling has informed the approach. BH Mech Consulted on decisions relating to heating/cooling controls and
	Hea 05	Acoustic performance	_						Color 1, 2, The DH DIRA Char 2 and the second back have see dided	
Number of the statistic set of the stati		(Sound insulation, indoor ambient noise level and		3 2.32%	6 3	3 3	3	n/a n/a	<u>BH</u> confirming that 3 of 3 credits are achievable. Mark-ups are provided acoustics for levels 2&3 and ISD L3. BY to be provided. Mace have also	acoustics Crit 1-3 - Acoustics report and mark-up to be provided for L4&5.
	Hea 06	Safety and security		_						
Image: Second	Hea 06		Stage 2	1 0.77%	6 1	1	1	BH has been provided. BH security provided an SNA for Phase 1 during security RIBA stage 2, and also consulted with the DOCO. The report	Crit 3 - At RIBA Stage 4 the Reach Active security mark up was provided to Peter Smith, the BH security consultant who did not identify any problems. Peter requested that CCTV and access control Reach.	security, Crit 3 - Security drawings for L4&5 to be prepared (e.g. by Reach Active again). BH security to provide similar sign off at RIBA stage 4.
Image: Second	ENERGY	Reduction of CO2 emissions								
		Energy Performance (SIX CREDITS NEEDED FOR BREEAM EXCELLENT UNDER THE RFO ASSESSMENT)		15 9.11%	6 9 2 4 2	9242	13 2 2	consultant undertaken by heritage consultant securing 2 credits (applicable to	Mace, RES, RES, BH sust so a higher score is expected. Provide model, discription of inputs,	RES, be required by the Centractor
	Ene 02	Energy monitoring	_							
		(ONE CREDIT NEEDED FOR BREEAM VERY GOOD OR		1 0.61%	6 1	1	1	n/a n/a	BH Mech, major end use and floor for both electrical and heat/DHW). Mace to	BH Mech, with BREEAM.
Link Link <thlink< th=""> Link Link <thl< th=""><th></th><th></th><th></th><th>1 0.61%</th><th>6 1</th><th>1</th><th>1</th><th>n/a n/a</th><th>BH Mech, major end use and floor for both electrical and heat/DHW). Mace to</th><th>BH Electronic with BREEAM requirements for education buildings. The bar will need to be separately metered (in addition to lecture halls,</th></thl<></thlink<>				1 0.61%	6 1	1	1	n/a n/a	BH Mech, major end use and floor for both electrical and heat/DHW). Mace to	BH Electronic with BREEAM requirements for education buildings. The bar will need to be separately metered (in addition to lecture halls,
Let will be und getres decay refersion I Vest B I </td <td>Ene 03</td> <td>External lighting</td> <th></th> <td></td> <td></td> <th></th> <td></td> <td></td> <td></td> <td></td>	Ene 03	External lighting								
				1 0.61%	6 1	1	1	n/a n/a	requirements. Mace to confirm the scope and external lighting and	Mace to ensure any external lighting meets the BREEAM
	Ene 04	Low Carbon Design								
Interf New Coding Stop 2 I Stop 3 I	Ene 04	Passive Design Analysis	Stage 2	1 0.61%	6 1 1	1 1	1 1	Grit 1 - HeadN to be achieved to fully close credit. <u>BH sust</u> <u>Grit 2-3</u> - RBA Stage 2 passive design analysis was completed covering the IOE masterplan. Can be used for all stages.	n/a n/a	n/a n/a
$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$	Ene 04	Free Cooling	Stage 2	1 0.61%	6 1	1	1		n/a n/a	n/a n/a
Refigeration faregy Concurption 1 0.55 1 0.55 1 0 1 0	Ene 04	Low and Zero Carbon Feasibility Study	Stage 2	1 0.61%	6 1 1	1 1	1 1	BH sust RIBA Stage 2. The study identified the Bloomsbury Heat & Power network as a key strategy, which the building is connecting to. Solar	n/a n/a	n/a n/a
Refigesion fnergy Consumption 1 0.63 1 0.6 1 0.6 1 0.6 1 0.6 1 0.6 </th <th>Ene 05</th> <th>Energy efficient cold storage</th> <th></th> <th></th> <th></th> <th></th> <th></th> <th></th> <th>Crit 1-2 - Mare to ensure that controls and components associated</th> <th>Crit 1-2 - Mace to ensure that controls and components associated</th>	Ene 05	Energy efficient cold storage							Crit 1-2 - Mare to ensure that controls and components associated	Crit 1-2 - Mace to ensure that controls and components associated
Indirect Greenhouse Gist Emissions Image: Series of Seri		Refrigeration Energy Consumption		1 0.61%	6 1	1	1	n/a n/a	with cold storage areas (eg. serving bar) have been designed, installed and commissioned in line with Code of Conduct for carbon reduction and BS EN 378-2. Products to be in line with Enhanced Capital Allowance (EGA) temps Technology Product List (ETPL), or approved equivalent.	with cold storage areas (e.g. serving bar) have been designed, interface and commission cold in line with Code of Conduct for carbon reduction and BS EN 373-2. Products to be in line with Enhanced Capital Allowance (EGA) Energy Technology Product List (ETPL), or approved equivalent.
Energy Consumption (Lift analysis, energy options appraisa) 1 0.65 % 1 <				1 0.61%	6 1	1	1	n/a n/a	Crit 4 - Mace to provide manufacturers evidence confirming the installed refrigeration system demonstrates a saving in indirect greenhouse gas emissions (CO2 eq.) over the course of its	Crit 4 - Mace to provide manufacturers evidence confirming the installed refrigeration system demonstrates a saving in indirect greenhouse gas emissions (CO2 eq.) over the course of its
Energy Crissingtion 1 0.615 1 1 0.615 1	Ene 06	Energy efficient transportation systems								
offer most energy swings: Standby, energy efficient 2 128 2 2 2 2 1				1 0.61%	6 1	1	1	n/a n/a	supplier, compliant study from lift supplier. Regenerative drives to be	Mace, lift compliant with BS EN ISO 25745 and/or request compliant study
Pre-reguisite - Hea 03 criterion 1 (objective risk Pre-		offer most energy savings: Standby, energy efficient		2 1.22%	6 2	2	2	n/a n/a	supplier, efficiency requirements for lifts Mace to provide technical submittal	Mace, lift Crit 2-4 - As per levels 283, Mace to provide technical submittal supplier confirming that all energy efficiency features in lifts will be included.
Pre-requisite - Hea 03 criterion 1 (objective risk	Ene 07	Energy efficient laboratory systems								
assessment) e e (Phase 3) & 3 scope of works, n/a to Phase 1 e e e e e e e e e e e e e e e e e e		Pre-requisite - Hea 03 criterion 1 (objective risk assessment)		requisit -				n/a Confirmed 19 Jan 2017, that labs are likely to be included in Phase 2 (Phase 1) & 3 scope of works, n/a to Phase 1.	n/a n/a for this phase	n/a n/a for this phase

	IOE Masterplan % 75.8 90.9 19.0 22.2 0.0	Phase 1 - L2&3 & ISD L3 Phase 1 - 74.3 87.8 22.1 25.7 0.0 77.5 89.8 19.4	- L4&5		
Credit Ref: Credit Issue (Mandatory Credits for Excellent shown red)	RIBA Sage Available % Score Value Targeted - Low Rikk Helphrink - TPC Not Targeted - Sco Achieved - PC	* *	8 X	Owner Design stage actions (and risks) (lead: support) Phase 1 - L283 & LSD L3 Green = Design stage evidence closed	Owner (lgad) support) Design stage actions (and risks) Phase 1 - U485 Green = Design stage evidence closed
Design specification	0 0.00%		n/a Confirmed 19 Jan 2017, that labs are likely to be included in Phase 2 (Phase 1) & 3 scope of works, n/a to Phase 1.	n/a n/a for this phase	n/a n/a for this phase
Best practice energy efficient measures	0 0.00%		n/a Confirmed 19 Jan 2017; that labs are likely to be included in Phase 2 (Phase 1) & 3 scope of works, n/a to Phase 1.	n/a n/a for this phase	n/a n/a for this phase
Ene 08 Energy efficient equipment				Crit 1-2 - BH sustainability undertook a TM54 at RIBA stage 3 (in	Mace. Crit 1-2 - Consultant leading modelling at RIBA Stage 3 to
Energy Efficient Equipment	2 1.22% 2	2 2	n/a n/a	BH sust Mace, Introl C un sustainability undertook a how a table stage of un unregulated energy. RES, UCL Crit 3 - UCL to provide letter confirming EnergyStar compliance.	RES, BH sust, UCL undertake the TM54 for the new levels. UL <u>Crit 3</u> - If unregulatd load for catering is highest, then the UCL letter will need updating.
TRANSPORT					
Tra 01 Public Transport Accessibility					
Public Transport Accessibility Index (AI)	5 2.94% 5 5	5 5 5	S <u>BH sust</u> <u>Crit 1-2</u> . The transport index has been calculated for the masterplan and achieves maximum score. No further action needed.	n/a n/a	n/a n/a
Tra 02 Proximity to Amenities					
Proximity to Amenities	1 0.59% 1 1	1 1 1	Bit sust <u>Crit 1</u> - Maps have been produced indicating the safe pedestrian UCL routes to amenities. Ben Stubbs has confirmed these are valid.	n/a n/a	n/a n/a
Tra 03 Cyclist Facilities					
Cycle Storage	1 0.59% 1	1 1	Arcadis racks. This has not been included part of Phase 1, but could easily be targeted.	n/a n/a	n/a n/a
Cyclist Facilities	1 0.59% 1	1 1	UCL, <u>HB</u> Arcads addition, compliant showers/lockers/dying space etc would be needed in line with the required occupancy.	n/a n/a	n/a n/a
Tra 05 Travel plan					
Travel plan based on site specific travel survey/assessment	Stage 3 1 0.59% 1	1 1	Image: Crit J. 2b-f. 3 Iceni has prepared a travel plan for IOE. BH suid: UCL UCL crit Ja- Transport survey data for IOE is required for the travel plan. UCL crit Ja- A letter of confirmation will be needed from UCL.	n/a n/a	n/a n/a
WATER					
Wat 01 Water Consumption				Crit 1-3 - Flow rates included in BH MEP spec with requirement to	
Minimising water consumption (ONE CREDIT NEEDED FOR BREEAM VERY GOOD AT EXCELLENT RATING, WHERE APPLICABLE)	ND 5 3.79% 3 2	3 2 3 2	n/a n/a	Mace BH Mech, HB Arbieve 3 credits. Mace to confirm final flow rates (inc. dishwashers) and provide product datasheets. <u>Crit 4-5</u> - Greywater not specified for Phase 1.	Crit 1-3 Mace to confirm final flow rates as per L283, including Mace, HB bar area and dishwashers etc, and provide product datasheets. Crit 4-5 Greywater not specified for Phase 1.
Wat 02 Water Monitoring					
Water Monitoring (Crit 1 NEEDED FOR BREEAM VERY GOOD OR EXCELLENT RATING)	1 0.76% 1	1 I	Crit1- Mains water meter for IOE to meet minimum standards for Arcads. Maca Crit2- Separate water meter for Phase 1 wing. Maca Crit2- Separate water meter for Phase 1 wing. BH PH Relevant or contractor to provide meter schematics and relevant evidence.	n/a IVa	Mace Dinclude in specification and schematic in line with BREEAM requirements.
Wat 03 Water Leak Detection					
Leak Detection System - mains water supply	1 0.76% 1	1 1	Arcadis Crit 1 - Leak detection system will need to be installed on the mains water supply in line with BREEAM requirements. This would de-risk main the supervise of the state of the supervise of the supe	n/a n/a	n/a n/a
Flow control devices to WC areas	1 0.76% 1	1 1	n/a n/a	Mace BH PH Grit 2 - BH MEP specs and PH drawings contain solenoid shut of valves for WC areas. Mace to provide RIBA Stage 4 evidence to close design stage action.	Mace Crit 2 - Mace to provide solenoid shut of valves for WC areas for BH PH levels 4&5. Evidence to be provided.
Wat 04 Water Efficient Equipment					
Water Efficient Equipment	1 0.76% 1		Critic 2- Scope of irrigation for Phase 1 TBC. Where there are soft landscaped areas however on irrigation systems are specified, and Macc UCL, HB, the credit vanable under this assessment issue can be awarded by Arcadis default. Where there are no soft landscaped areas and no other umregulated water demands for the building, this credit is filtered put of the assessment.	n/a iva	n/a n/a
MATERIALS					
Mat 01 Life Cycle Impacts	ļ		ļ		

				IOE Masterplan % 75.8 90.9 19.0 22.2 0.0	Phase 1 - L2&3 & ISD L3 74.3 87.8 22.1 25.7 0.0	Phase 1 - L4&5 77.5 89.8 19.4 15.2 0.0						
Credit Re	f: Credit Issue (Mandatory Credits for Excellent shown red)	RIBA Stage	Available	% Score Value Targeted - Low Risk High risk - TBC Not Targeted Achieved - PC Achieved - PC	Targeted - Low Risk High risk - TBC Not Targeted Achieved - DS Achieved - PC	Targeted - Low Risk High risk - TBC Not Targeted Achieved - PC Achieved - PC	Owner (lead, support)	Design stage actions (and risks) JDE Masterplan - Phase 1 Green = Design stage evidence closed	Owne (lead, suppor	Phase 1 - L2&3 & ISD L3	Owner (<u>lead</u> , support)	Design stage actions (and risks) Phase 1 - 1485 Green = Design stage evidence closed
	Green Guide rating of main building elements		6 6.5	i6% 3 1 2	3 1 2	3 1 2	n/a	n/a	<u>НВ, Ма</u> ВН МЕ	Citil 2-2 - Option 1 compliance must full LCA not taken Citil 2-30 - Option 2 compliance routs taken. In this approach, the green guide rating of all newly specified materials is needed (as per a normal BREEMA assessment) with detailed area calculations not meeded. For all elements, the overall's of elements retained in situ should be estimated (from 0%, <25%, <25%, <25%, <95%), 57%, 95%), In 9 robust environmental information should be estimated (again from 0%, <25%, <25%, <50%, <95%, S9%). Note that the aductation ado requires building services and Fit Out items must also be included in the schedule with robust environmental product information' provided - eg. ISO 14000 compliant suppliers. The output of these results gives the Mat01 score with a maximum of A credits available. Mac/HB to provide relevant information.	HB, Mace	<u>virt 1.7</u> - Option 1 compliance route (full LCA) not taken <u>htt 8.10</u> - Option 2 compliance route taken. Evidence as per Levels 83 to be provided. HB to provide information on materials and fit u.t. Mace to provide information on MEP.
Mat 03	Responsible sourcing of materials											
	Pre-Requisite: Responsible sourced timber (Crit 1 NEEDED FOR BREEAM VERY GOOD OR EXCELLENT RATING)		Pre- requisi te	- <u>x</u> <u>v</u>	¥ Y	¥ Y	n/a	n/a	Mace	Crit J-2 - Mace have provided a letter of intent for "Phase 1" confirming that all timber will be legally harvested and traded.	Mace	kt1.2 - Mace have provided a letter of intent for "Phase 1" onfirming that all timber will be legally harvested and traded.
	Sustainable Procurement Plan		1 1.0	99% 1	1	1	Mace	Crit 3 - Mace to provide a copy of the Sustainable Procurement Plan for the project. Note that this can either be an 'organisational' document' or 'project specific'. It should cover aims, objectives and targets, material tracking procedures, risks & opportunities.	n/a		n/a	/a
	Responsible Sourcing of Materials		3 3.2	28% 1 2	1 2	1 2	n/a	n/a	Mace HB	Criti 34— H8 made reference to FSC/PEFC BIS 5001 standards, with ISO 14001 supply drain and process as a minirum requirement in the spaces. Mace to provide required schedule of materials for design stage evidence. Note that BREAM NFD avancia one credit where at least three of the material types listed in Table 53 "Material attegories" has been responsibly sourced from one of the responsible sourcing schemes recognized by BREEAM as detailed in Guidance Note 18.	Mace	211.3.4 - As per Levels 283, Mace to ensure materials are procured ollowing FSC/PEFC, 855 6001 standards, with ISO 14001 (supply hain and process) as a minimum requirement. Mace to provide equired schedule of materials for design stage evidence.
Mat 04	Insulation											
	Embodied impact of insulation (fabric and building services)		1 1.0	19% 1	1	1	n/a	n/a	Mace HB	Crit 1-2 - BH MEP and HB included requirements for insulations in specifications. Mace to provide schedule of insulation volumes for each element (external valis), GF (Boo), Building services), conductivity and green guide rating (A or A+) with manufacturer EPD where available.	Mace	<u>rit 1-2</u> - As per Levels 283, Mace to provide schedule of insulation olumes for each element (external walls, GF, Roof, Building ervices), conductivity and green guide rating (A or A+) with nanufacturer EPD where available.
Mat 05	Designing for Durability and Resilience Protecting Vulnerable Parts of the Building From Damage (criteria below also needed for credit)		1 1.0	19% 1	1	1	n/a	n/a	Mace HB	Srit1 - Mace / H8 to provide L283 and ISD L3 drawings marking up durability measures e.g. protection to entrance areas, corridoos, lifts stairs, protection in kitchen areas, trolley movement, protection against vehicle collision where vehicle movement and parkin occurs within 1m of building.	Mace, HB	tit 1 - Mace / HB to provide L485 drawings marking up durability neasures e.g. protection to entrance areas, condoors, lifts, stains, rotection in kitchen areas, trolley movement, protection against elide collision where vehicle movement and parkin occurs within an of building.
	Protecting Parts of the Building from Material Degradation (criteria above also needed for credit)						HB, AECOM, Arcadis	Crit 2.3.5 - HB/AECOM to complete the materials degredation schedule for Phase 1 areas (BH sust have template), listing all applicable new and existing elements and protection standards. Crit 4 - AECOM/Arcadis to provide structural survey reports assessing the severity of any degredation effects.	n/a	n/a	n/a	/a
Mat 06	Material Efficiency											
Mat 06	Material Efficiency	Stage 1-5	1 1.0	19% 1	1		n/a	n/a	BH ME HB, AECON	Cith 1-2 - At every RIBA Stage, opportunities have been identified, and appropriate measures investigated and implemented within the scope of refurbibithment of fit-out works, to optimise the use of in materials through building design, procurement, refurbibitment, P, maintenance and end of life. (RIBA Stage 1 - Phase 1 template completed at masterplan stage RIBA Stage 2 - Template updated RIBA Stage 3 - Template updated RIBA Stage 4 - Template updated RIBA Stage 4 - Template updated RIBA Stage 5 - TEC	BH sust BH MEP, HB, AECOM, Mace	ht 1-2 - Team to review Mat06 template at each RIBA Stage produced initially for Viling levels 28.3 and SD 13.3 Ary new omments for LIABS to be added where relevant. BLBA Stage 1 - Phasia 1 template completed at masterplan stage BLBA Stage 2 - Template updated and/or confirmed no changes BLBA Stage 3 - TBC BLBA Stage 5 - TBC
WASTE												
Wst 01	Construction Waste Management											
Wst 01	Pre refurbishment audit	Stage 2	1 0.7	71% 1	1 1	1	n/a	n/a	Mace	Crit 1 - Mace have issued a draft of the pre-refurbishment audit for L283 and ISD L3. Finalised audit report to be issued to allow this element of the credit to be closed. Crit 2-4 - Mace to confirm approach against Wst01 schedule (table	Mace	cit 1 - Pre-refurbishment audit for L4&S to be conducted prior to trip out works.
	Reuse and direct recycling of materials		2 1.4	2	2	2	n/a	n/a	Mace	(f1) at stage 4 to access potential for requiring and reusing in line	Mace	<u>kith 2-4</u> As per L283, Mace to confirm approach against Wst01 chedule (table 61) for L485. Provide written confirmation of routes k tracking procedures for each material ytpe.
	Construction Resource Efficiency		3 2.1	13% 2 1	2 1	2 1	n/a	n/a	Mace	less than 4.5m3/100m2 GIA (less than 1.2 tonnes/100m2 GIA). Mace has provided SWMP. Unclear what level/part of the building this plan extends to. Cett 2.7. Requirements included in tender process were:	Mace	vit 5-6 - Mace to extend SWMP to cover levels 4&5.
	Diversion of Resources from Landfill		1 0.7	71% 1	1	1	n/a	n/a	Mace	- Non-demolition, 85% volume and 90% tonnage	Mace	241 5-6 - Mace to extend SWMP to cover levels 4&5.
Wst 02	Recycled Aggregates			1	1	1 1						

			×	IOE Masterplan 75.8 90.9 19.0 22.2 0.0	Phase 1 - L2&3 & ISD L3 74.3 87.8 22.1 25.7 0.0	Phase 1 - L4&5 77.5 89.8 19.4 15.2 0.0			
Credit Re	f. Credit Issue (Mandatory Credits for Excellent shown red)	RIBA Stage	Available % Score Value	Targeted - Low Risk High risk - TBC Not Targeted Achieved - DS Achieved - PC	Targeted - Low Risk High risk - TBC Not Targeted Achieved - PC Achieved - PC	Targeted - Low Risk High risk - TBC Not Targeted Achieved - PC Achieved - PC	Owner (tead) support() Design stage actions (and risks) I/DE Masterplan - Phase 1 Green - Design stage evidence closed	Owner Design stage actions (and risks) (and support) Phase 1 - 1263 & ISO 13 Green - Design stage evidence closed	Owner lead support) Phase 1 - 1485 Green = Design stage evidence closed
	Recycled Aggregates for high grade use		1 0.71%	1	1	1	AECOM Credit not targeted. Structural engineer to review requirements and confirm if feasible to target for the project.	AECOM Credit not targeted. Structural engineer to review requirements and confirm if feasible to target for the project.	AECOM Credit not targeted. Structural engineer to review requirements and confirm if feasible to target for the project.
Wst 03	Operational waste								
	Operational Waste (ONE CREDIT NEEDED FOR BREEAM EXCELLENT)		1 0.71%	1	1	1	Crit 1-2 - UCL to confirm waste streams and sizing figures for the UCL project. Requirements for waste store to be reviewed in line with BREEAM requirements and operational FM strategy.	n/a n/a	n/a n/a
Wst 05	Adaptation to Climate Change								
Wst 05	Adaptation to Climate Change - Structural and Fabric Resilience	Stage 2	1 0.71%	1 1	1 1	1 1	BH sust: BH MEP, <u>Crit 1</u> - Climate change risk assessment was conducted for the IOE AECOM, masterplan at RIBA Stage 2. Credit closed. HB	n/a n/a	n/a n/a
Wst 06	Functional Adaptability	_						Crit 1 - HB provided the RIBA stage 2 functional adaptability study	
Wst 06	Functional adaptability strategy	Stage 2 Stage 4	1 0.71%	1	1 1	1	n/a n/a	HB. for levels 283 and ISD L3. BH MEP evidence also included. BH MEP, Crit 2 - Mace have provided RIBA stage 4 evidence, including details of fumiture layouts, accessibility routes and confirmation of the MEP strategy and details of carondax ustain.	HB. BH MEP. Macc Macc Macc Macc Macc Macc Macc Mac
LAND U	SE & ECOLOGY								
Le 02	Ecological Value of Site and Protection of Ecological F	eatures	1 2.27%	1 1	1	1	Citi 1-2: An ecology report has been prepared. Requirements include protection of trees with trucks over 100mm diameter in accordance with 553573272. Checks on any works that may disturb nests and eggs in areas such as trees, roof, gutters, soffit constructions buildwently champion deem necessary to check for any block reducts that may be nesting in roof areas and on gravel areas of the roof.	<u>Crt 1.2</u> - Mace sustainability champion to ensure measures are implemented in line with ecologist's report. Mace to provide evidence before work starts on site- that sustainability champion <u>Mace</u> undertook survey: survey report and pictures of protection measures in place required as evidence. Mace to provide program and justification how achieties how been time to avoid megative impact on biodiversity- check ecologist report.	Crit 1-2 - Mace sustainability champion to ensure measures are implemented in line with ecologist's report. Mace to provide evidence before work starts on sile- that sustainability champion index of the start of the start of the start of the start Mace intervent starts are equived as evidence. Mace to provide program and justification how activities have been time to to avoid negative impact on biodiversity- check ecologist report
Le 04	Enhancing Site Ecology								
LE 04	Ecologist's Report and Reccomendations	Stage 1 Stage 2	1 2.27%	1 1	1	1	Ecologist Crit 1-3 - An ecology report was prepared. The report identifed that external terraces should include planters.	Mace. Crit 3 - Mace has provided letter confirming planters will be <u>HB</u> provided on external terraces with native species.	Mace. Crit 3 - Mace has provided letter confirming planters will be provided on external terraces with native species.
Le 05	Long Term Impact on Biodiversity								
	Long Term Impact on Biodiversity (Landscape and habitat management plan; Site management for minimal impact on biodiversity)		2 4.55%	2	2	2	Crit 1-3 - An ecology report was prepared. The SQE confirmed that a <u>Ecologist</u> landscape and habitat management plan is not necessary. Although the contractor will be required to appoint a biodiversity champion and monitor on-site activities.	Crit 3 - Mace to provide finalised letter confirming the scope of the biodiversity champion, and provide evidence of checks undertaken to date.	Crit 3 - Mace to provide finalised letter confirming the scope of the biodiversity champion, and provide evidence of checks undertaken to date.
POLLUTI	ON								
Pol 01	Impact of Refrigerants No Refrigerant Use Pre-Requisite for buildings that use refrigerants		0 0.00% Pre- requisi -	¥	Y	Y	n/a huliding has refrigerants	n/a n/a building has refrigerants Cit12 - Requirements included in BH MEP specs. Mace to provide evidence that all systems will comply with the requirements of BS Cit12 - Requirements of BS evidence that all systems will comply with the requirements of BS and other end of the systems of the system of the systems of the system	n/a building has refrigerants Citit 2 - Mace to provide evidence that all systems will comply with the requirements of BS EN 378 20081 (parts 2 and 3) and where
	(compliance with industry standards and best practice)		te					MMCM containing ammonia are installed, the Institute of Refrigeration Ammonia Refrigeration Systems Code of Practice. <u>Crit 3-4</u> - Not targeted Crit 3-6 - Reprisements (orlyded in RH MER space Mare to provide	of Refrigeration Ammonia Refrigeration Systems Code of Practice. Critt 3-4 - Not targeted
	Impact of Refrigerant (Low DELC C02 refrigerants)		2 1.75%	1 1	1 1	1 1	n/a n/a	Mace. BH Mech BH Mech erdiners for DELCO calculation (or frigherant type, volume of erdingerant charge, cooling capacity etc for each system) plus supporting tech-subs / datasheets.	Mace Crift 5 - Mace to provide evidence for DELC CO2 calculation (refrigerant type, volume of refrigerant charge, cooling capacity etc for each system) plus supporting tech-subs / datasheets.
	Leak detection and containment		1 0.87%	1	1	1	n/a n/a	Mace, BH Mech BH Mech Schematics and manufacturer specs for leak detection on systems with refrigerant charge above 6kg.	Mace Crit 6-7 - Mace to provide schematics and manufacturer specs for leak detection on systems with refrigerant charge above 6kg.
Pol 02	NOx Emissions							Crit 1 - Mace to confirm the heating and hot water loads for Phase	Crit 1 - Mace to confirm the heating and hot water loads for Phase
	Low N0x Emissions plant for space heating and hot water		3 2.62%	3	3	3	BH sust UCI L- BH sustainability requested information about the NOx emissions for the BHP energy centre, but did not receive a reply regarding NOx. Re-request information.	Mace. 1 1283 and ISD L3 served by each item on plant (e.g. DH, heat BH Mech pumps, any new boilers etc). Calculation is then rated to heat output from each system as per BREEAM method.	Mace 11485 served by each item on plant (e.g. DH, heat pumps, any new boilers etc). Calculation is then rated to heat output from each system as per BREEAM method.
Pol 03	Surface Water Run Off								
	Flood Risk Management		2 1.75%	2 2	2 2	2 2	AECOM Crit 1-6 - FRA report confirms that the site is located in flood risk zone 1 (low risk of flooding).	n/a n/a	n/a n/a
	Surface Water Run Off - neutral impact		1 0.87%	1 1	1 1	1 1	AECOM Crit 2-8 - The FRA report confirms the proposed Phase 1-3 refurbishment works will not increase surface water run off.	n/a n/a	n/a n/a
	Surface Water Run Off - 50% reduction		1 0.87%	1	1	1	n/a Credit not targeted as these works are not included in the scope of the refurbishment strategy.	n/a n/a	n/a n/a
	Minimising Watercourse Pollution		1 0.87%	1	1	1	n/a Credit not targeted as these works are not included in the scope of the refurbishment strategy.	n/a n/a	n/a n/a
Pol 04	Reduction of Night Time Light Pollution							<u>_</u>	

				ie e	IOE Masterplan 5.8 90.9 19.0 22.2 0.0 5.8 2 2 2		21 - L2&3 & ISD L3 37.8 22.1 25.7 0.0 22.2 25.7 0.0	Phase 1 - L4&5 77.5 89.8 19.4 15.2							
Credit R	Credit Issue (Mandatory Credits for Excellent shown red)	RIBA Stage	Available	% Score Valu	Largetea - Low High risk - TE Not Targete Achieved - D Achieved - P	Targeted - Low	High risk - Tf Not Targete Achieved - D Achieved - P	Targeted - Low High risk - TE Not Targete Achieved - D	Achieved - P		Design stage actions (and risks) IOE Masterplan - Phase 1 Green = Design stage evidence closed	Owner (<u>lead</u> , support	Design stage actions (and risks) Phase 1 - L2&3 & ISD L3 Green = Design stage evidence closed	Owner (<u>lead</u> suppor	Phase 1 - L48/5
	Reduction of Night Time Light Pollution		1 (.87% 1	ı	1		1	n,	/a i	n/a		Crit 1-3 - BH MEP specifications made referce to BREEAM requirements. Mace to confirm the scope and external lighting and provide drawings, calculations and tech-subs confirming controls and ILP guidance has been followed.	Mace BH Ele	Crit 1-3 - BH MEP specifications made referce to BREAM requirements. Mace to confirm the scope and external lighting and provide drawings, calculations and tech-subs confirming controls and LP guidance has been followed.
Pol 05	Reduction of Noise Pollution														
	Reduction of Noise Pollution		1 (.87% 1	1 1	1	1	1 1	<u>B</u> acou		Crit 2.5 Acoustics study was carried out for Phase 1. To comply with the planning requirements of Canden Council, noise emissions from new plant should be a minimum of 38b below the lowest measured background noise level. Since the requirements of the LA are more stringent, BREEMA criteria can automatically be met when the local planning requirements are satisfied.	Mace	Crit 2-5 - Mace has provided letter of intent confirming that acoustic recommendations will be implemented and that post construction testing shall be carried out to the required standard.	Mace	Crit 2-5 - Mace has provided letter of intent confirming that acoustic recommendations will be implemented and that post construction testing shall be carried out to the required standard.
INNOV	ATION														
Man 03	Exemplary Level Credit: CCS score of 40 or above		1 1	.00% 1	1	1		1	n,	/a i	n/a	<u>Mace</u>	Crit 10 - Mace have provided a letter of intent confirming that "Phase 1" will be registered for the Considerate Construction Scheme, targeting a score of 40 with 7 in all sections.	Mace	Crit 19 - Mace have provided a letter of intent confirming that "Phase 1" will be registered for the Considerate Construction Scheme, targeting a score of 40 with 7 in all sections.
Man 05	Exemplary Level Crit: Building performance review at quarterly intervals over first 3 years of occupation		1 1	.00%	1		1	1	<u>u</u>	a. 1	Crit 4-5 - Letter of intent to be signed by UCL.	n/a	n/a	n/a	n/a
Hea 02	Exemplary Level Crit: - Minimising sources of internal air pollution through specification of exemplary low VOC products		1 1	.00%	1		1	1	n,	/a i	n/a	HB. Mac	Crit 5-2 - HB included a table in the architectural specifications listing out all applicable products and VOC standards. Make to ensure it is implemented and provide evidence. Innovation levels liskly to be challenging to gather all evidence for.	Mace	Crit 6-7 - Mace to provide details of VOC standards to be applied for levels 485. H8 to provide evidence if they are providing specifications.
Wat 01	Exemplary Level Crit: Exemplary water efficiency and rain/water recycling for WC/urinal flushing		1 1	.00%	1		1	1			Credit to be reviewed at masterplan level. Phase 1 areas are not currently targeting this level of performance.	n/a	n/a	n/a	n/a
Mat 01	Exemplary Level Crit Green Guide to Specification (Elemental Approach)		1 1	.00%	1		1	1	Ma H	D D	Very high scoring would be required on the BREEAM RFO Mat01. (option 2) tool to achieve this. The main limitation is providing robust environmental information' for MEP items.	n/a	r/a	n/a	n/a
Mat 01	Exemplary Level Crit Compliant Life Cycle Assessment Software Tools (Whole Building Approach)		2 2	.00%	2		2	2			IES IMPACT software would need to be used to carry out a whole building LCA. This is currently not included in the scope.	n/a	n/a	n/a	n/a
Mat 03	Exemplary Level Crit - At least 70% of the available RSM points are achieved		1 1	.00%	1		1	1	Ma		Very stringent responsible sourcing would be required to achieve this innovation credit.	n/a	n/a	n/a	n/a
Wst 01	Exemplary Level Crit - s 14m3 per 100m2 waste, and 95% diversion from landfill.		1 1	.00%	1		1	1	Ma	ice	Waste generation targets are likely to be too challenging for the project to achieve. (Mace have already flagged that the target of 4.5m3/100m2 is already challenging).	n/a	n/a	n/a	n/a
Wst 05	Exemplary Credit - Responding to Adaptation to Climate Change		1 1	.00%	1		1	1	Ma	<u>om.</u>	A number of requirements have been met. In order to achieve this credit, the key limitation is that 2 credits are needed on "Pol 03 - 50% reduction in surface water run-off which is currently outside of the scope of the project. 8 credits would also be needed on Ene01.	n/a	n/a	n/a	n/a
	BESPOKE BRE Approved Innovations		Varies						LIG BH 3	L i Sust. 1 KCE 1	Identify any possible opportunities for masterplan level bespoke innovation credits UCL sustainability may be able to fund (e.g. wellness facilities, air quality enhancers, innovative PV solutions, window traffic light systems, living lab sensors, phase change materials, productivity surveys, for batteries, outdoor gym etc).	n/a	n/a	n/a	n/a

¹ Note: a maximum of 10 credits can be awarded from the available innovation credits

Chris Van Dronkelaar Buro Happold 17 Newman Street London W1T 1PD UK

T: +44 (0)207 927 9700 F: +44 (0)870 787 4145 Email: Chris.VanDronkelaar@burohappold.com