

Our ref: RJC/72327/R/JAL

9th May 2018

Mr Alastair Darwood
Flat 2, 84 Albert Street
London
NW1 6JJ

By email only to alastairdarwood@hotmail.com
& sb@bbspcuk.com

Dear Alastair,

Re: Flat 2, 84 Albert Street London NW1

Further to our telephone conversation of the 9/5/18, I would like to confirm the following (please refer to enclosed drawing)

- 1) Due to dimensional issues along the elevation facing the patio area, we now propose to install a Delta PT meshed wall membrane, that has an 8mm stud thickness and a thermally welded mesh on the front face, that will accept plasterboard on dabs, this will add approximately an additional 12-15mm onto the system thickness, giving an overall thickness in the region of 25mm
- 2) You informed me that you want to site the sump chamber externally, this is indeed possible but will require your builder to provide an outlet from the bottom of the internal drainage trench to discharge into the sump chamber.
- 3) The recommended inspection ports will predominantly be sited within the stud frame zone and are usually accessed via dummy electric socket or a hatch, the remaining will need to be incorporated within the floor finish or excluded if impractical

Our revised quotation is as follows and supersedes our earlier report/quotation dated 28/3/18

- Apply Polysil TG 500 Lime inhibitor to areas of new concrete
- Supply/install Delta perimeter drainage channels incorporating 4 no Inspection ports
- Supply/Install Delta MS500/PT/MS20 cavity drain membrane to wall/floor areas indicated
- Supply/Only 1 no Delta Dual V3 ground water sump unit (main contractor to concrete unit in and carry out electrical/outlet connections)
- Commission sump unit

For the sum of **£ 5,075.00 plus VAT**

Rates for additional items should they be required are as follows:-

Service entries / pipe seals	@ £ 30.00 + vat per seal
Additional fixing points for dry lining etc	@ £ 4.00 + vat each
Daywork rate	@ £350.00 + vat/day + Materials
Supply Box of Qwik-seal plugs	@ £ 47.20 + vat/Box of 100
Battery backup (if required)	@ £650.00 + vat

We have included within our tender for the supply and installation of the Delta MS Cavity Membrane, the Delta perimeter drainage channels and supply only of the Delta Dual V3 Sumps. The setting back to provide a perimeter recess and the formation of a concrete chamber within the slab to accommodate the drainage channels and sump chamber respectively should be carried out by others in advance of our works to the dimensions provided.

9th May 2018
Flat 2, 84 Albert Street London NW1

RJC/72327/R/JAL

In accordance with the industry standard we provide a 10 year company guarantee for the works and these are backed by our own insurers. However, if you would like additional guarantee protection insurance, this can be provided on request, The GPI quotation is subject to the contracts final account figure and any variations by GPI Ltd

Attendances / Preparation Works

Please see the attached General Attendance Schedule which indicates the attendance's included by us within our submission and those to be provided by the main contractor at no charge to us. Please also refer to the attached preparation checklist for project specific requirements.

We trust our quotation is of interest to you and look forward to speaking with you very soon.

Yours Sincerely

Richard Chamiec CSRT CSSW
Surveyor Mobile 07904 093 715
e-mail: richardc@renlon.com

Encl. General Attendance Schedule
Notice of acceptance
Health & Safety
Terms & Conditions
Technical Information Sheet no's 1 & 8

General Preparation Checklist

for works to be carried out by others at
Flat 2, 84 Albert Street NW1

1. General Requirements

Suspend parking bays/areas outside the front of the building for positioning of plant etc.

Note: All local authority fees for the suspension licence etc should be met by the client.

Provide power, water and background lighting. Provide clear working areas and a space for storing materials. Provide protection to all areas of work, non-working areas and access routes.

Provide skips or other suitable receptacle for the deposit of all debris resulting from our works.

2. Task Specific Requirements

DELTA MS CAVITY DAMP PROOF MEMBRANES

A working temperature of between 5° - 35° centigrade is required with all surfaces being dry and protected from the weather by the main contractor. All concrete or cementitious backgrounds must be shuttered or float finished with undulations not exceeding 3mm and without sharp edges.

In order to ensure continuity of the membrane, the construction of additional internal walls should be delayed. If this is not possible due to structural considerations, the membrane will need to continue around the abutting walls to complete the system at an additional cost. Steels should be encased in concrete or enclosed with masonry to enable continuity of the membrane.

Finishes: Although Cavity Membranes provide a dry surface waterproofing system they are designed to be covered with a finishing product. These provide protection to the membrane and also allow cosmetic decoration to be applied. All finishes should be provided by others.

Make good any areas of defective brickwork /concrete with a render levelling coat

DELTA DRAINAGE & DELTA DUAL V3 SUMP

Form a perimeter recess within the floor slab at dimensions 100mm wide X 75mm deep to accommodate the Delta perimeter drainage channels. Alternatively, this can be formed using a sacrificial screed or closed cell insulation on top of the concrete slab.

Form a concrete chamber at dimensions of 950mm wide X 750mm deep to accommodate the Delta Dual V3 Sump.

Provide a drainage outlet from the bottom of the perimeter drainage trench into the external sump chamber

General Notes

Inspection ports are included to the drainage channels to aid periodic maintenance. These are generally positioned at or close to corners for convenience and subsequent access to these should be considered when designing the final finishes. These to remain accessible after the work is completed .It is the responsibility of the Main Contractor to ensure following trades do not conceal the inspection ports.

Likewise the top of the sump stations will need to be accessed for periodic maintenance to the pumps and this should also be considered when positioning the sumps and designing the final floor finishes.

Note, that the top of the chamber should be level with the top of the structural slab or a maximum of 500MM from the finished floor level.

It is important that all pump equipment and accessories are serviced on a regular basis. A service agreement can be arranged. Both BS 8102 and BS 752 require packaged pump equipment to be serviced in accordance with the manufacturers recommendations

General Preparation Checklist Cont....

Conduct a flood test to ensure the water adequately drains from the basement and no low spots are found where the water can puddle. Should puddling occur, the low spots are to be infilled with a self-levelling compound or made up level with epoxy mortar before the membrane is installed.

Provide a cable duct (diameter 50mm) with draw cord. This must be continuous and run from the chamber to within 500mm of the isolator/spur. Provide a mount for the electrical control / alarm panel within 3m of the chamber. Provide a power supply wired directly to the main fuse board.

Provide a discharge pipe for the ground water and extend this continuously up to ground level for discharge into an open gully. Alternatively it can discharge into an existing manhole chamber or main drainage network provided a non-return valve is incorporated within the discharge pipe (Clients Drainage Engineer to advise)

For further guidance please refer to the enclosed Technical Information Sheets

General Attendance Schedule

GENERAL ATTENDANCES		
CONTRACT: Flat 2 84 Albert Street London NW1		MAIN CONTRACTOR: Mr Alastair Darwood
ATTENDANCE ITEM	PROVIDED F.O.C. BY M/C	PROVIDED F.O.C. BY RENLON
Unloading and distribution of plant and materials		YES
Storage Space	YES	
Protection of Fixed Works	YES	
Protection of surrounding area	YES	
Power 110 Volts	YES	
Mains Pressure Water Supply	YES	
Task Lighting		YES
Shared Welfare Facilities	YES	
Scaffold / Towers for areas over 2.5m high	YES	
Podiums etc. to 2.5m high		YES
Temporary Roof	YES	
Protection from weather	YES	
Passenger Hoists	YES	
Material Hoists	YES	
Cranes	YES	
Setting out level and datum's	YES	
Rubbish Chute	YES	
Clear rubbish to skip.		YES
Skips	YES	
Background Lighting	YES	
Preparation Works	YES	
First Aid Station	YES	
Supervision		YES
No Radios		YES
No Smoking in non designated areas		YES

NOTICE OF ACCEPTANCE

To accept our quotation under the above reference number please complete the details below and return in the prepaid envelope enclosed.

I/We have read and accept the conditions of contract and give you permission to enter the property for the purpose of carrying out the work specified. I/We agree to accept responsibility for the costs incurred.

Signed.....Date.....

Surname.....Title (e.g. Mr. Mrs. Miss, Ms).....Forenames.....

Company (if applicable).....

Tel Home.....Tel .Work.....

Tel Mobile.....Tel Property.....

E-mail address.....

Invoice address.....

.....Postcode.....

Do you own the property? YES/NO If no state interest in space below

.....

Please give details of when you would like the work carried out, access arrangements, and any special requirements you have.....

.....

.....

SUMMARY OF COSTS

Delta membrane works £ 5,075.00 Plus VAT


TOTAL £ 5,075.00 Plus VAT


Independent Insurance Backed Warranty Incl. IPT* Premium available on request

* Insurance Premium Tax.




 DELTA IN SLOPE CAVITY DRAIN MEMBRANE TO FULL HEIGHT OF WALL


 DELTA IN SLOPE CAVITY DRAIN MEMBRANE TO FLOOR

 DELTA PERIMETER DRAINAGE CHANNEL

 DELTA INSPECTION POINT.

DELTA PT MESHED CAVITY DRAIN MEMBRANE TO FULL HEIGHT OF WALL TO RECEIVE PLASTIC DIVIDED ON DUBS OVER BY OTHERS.

 DELTA DRAINAGE CHANNEL AROUND WATER SUMP UNIT.



GROUND FLOOR

RE: FLAT 2,
82, ALBERT STREET
LONDON NW1
KX/72327
28/3/18

0 1m 2m 3m 4m

This document is the property of nea and is not to be used for any other project without the written consent of nea. It is to be used only for the project and site mentioned in the title block. It is to be returned to nea upon completion of the project. nea is not responsible for any errors or omissions in this document. nea is not responsible for any damage or injury caused by the use of this document. nea is not responsible for any loss of profit or business caused by the use of this document. nea is not responsible for any other consequences of the use of this document.

Drawn by: CN
Checked by:

292-002
Rev: D
Date: 03.01.2018
Scale: 1:50 (E A3)

Proposed Floor Plans
Flat 2, 84 Albert Street, London
NW1 7NR

HEALTH AND SAFETY AND PROTECTION OF THE ENVIRONMENT

Renlon are at the forefront in the development of safe methods of remedial treatments to buildings. Treatments are only applied where necessary. Where chemicals are used the products have been thoroughly tested in order to ensure that they are the safest available.

WARNING

Notwithstanding the above, usage of any chemical can result in potential hazards. To minimise the risks to individuals and the environment the following precautions should be observed during our treatment and for at least the next 48 hours.

1. Persons not engaged in the treatment work should stay well clear of the area(s) being treated.
2. No smoking.
3. No naked lights (including pilot lights or blow lamps), fires etc. Any Contractor working in the property should be warned accordingly.
4. Treated areas must be thoroughly ventilated.
5. Do not allow infants, children or pets to come into contact with treated areas. Fish and caged birds should not be re-installed in treated areas.
6. Do not replace food stuffs in treated areas.

IF YOU REQUIRE ANY FURTHER ADVICE OR INFORMATION
PLEASE DO NOT HESITATE TO CONTACT OUR
OPERATIONS DEPARTMENT ON

020 8687 4015/16

TCTRADE

TERMS AND CONDITIONS

1. Our quotation is subject to the following terms and conditions.
2. Our quotation is for a fixed price and is not subject to re-measure, unless otherwise stated.
3. Our quotation is open to acceptance for 3 months and thereafter is subject to review.
4. We reserve the right to ask for either a deposit or full pro-forma payment
5. The payment due date is 7 days from the date of invoice or application and the final payment date is 21 days thereafter. Any notice of withholding must be given 21 days before the final date for payment. Interim applications will be made on a monthly basis. Late payment will accrue interest on a daily basis at a rate of 2.5% per 28 days.
6. Third party recovery costs on outstanding payments will be collectable in full.
7. We reserve the right to suspend works immediately a payment becomes overdue. If this becomes necessary Renlon cannot be held responsible for any resultant delays. Return to site will not be scheduled until outstanding payments have been made.
8. Renlon reserves the right to withdraw this offer at any time prior to acceptance without stating a reason. Our offer is subject to Renlon having sufficient resources to carry out the work without affecting other contracts in progress.
9. Unless stated to the contrary, our price is based on the program giving us continuity of work for the full scope of our quotation. Should the client require the works to be carried out in stages, we reserve the right to receive stage payments and to make a charge for each additional visit.
Should we attend site as agreed with the client and be unable to carry out any works, we reserve the right to make a charge of £75 (plus VAT) per operative for each occurrence.
10. No additional works will be carried out without written instructions and an agreed method of pricing.
11. For works carried out on a day rate basis, labour will be charged at the rate prevailing when the works commence. Materials and plant will be charged at cost plus 25%
12. We must be notified in writing of any problem associated with our works within 7 days of its occurrence.
13. Any proposed contra charges must be submitted in writing and agreed by both parties prior to any monies being withheld.
14. It is the customer's responsibility to ensure that all preparation works are complete prior to our tradesmen arriving, and that clear and safe access is available together with required lighting, power, water and protection to surrounding areas, finishes and goods. Goods and effects should be removed from the areas of our work. We cannot be held liable for damage to any item left in the area. The nature of our work will result in the creation of noise and dust. It is our customer's responsibility to ensure that adequate protection from dust is in place for any goods and effects or to other areas of the property. We cannot be held liable for any claim against dust.
15. All concealed services must be clearly marked. No responsibility can be taken for damage to services not marked. It is the responsibility of our customer to ensure that all electrical circuits and installations within the area of our works are safe and in good order before we commence on site.
16. Where we are called upon to execute works to party walls, it is the responsibility of the customer to inform the owners of the adjoining properties of the works proposed, to ensure that there are no objections and to avoid any possible damage to fixtures or contents. The party wall regulations must be complied with and it is recommended that a chartered surveyor is contacted.
We cannot be held responsible for claims for damage caused by vibration or other causes to adjoining rooms or neighbouring properties.
17. It is possible for odours to permeate into adjacent properties. Where this is at all likely, the occupiers would be informed and advised to take precautions in line with our health and safety warning contained within the report.
18. Where we are required to carry out works, which may be subject to planning consent or Building Regulations Approval, our client must arrange the necessary consents or approvals from the Local Authority including parking bay suspension or skip licence and pay the statutory fees associated therewith prior to the commencement of our works.

19. Our specification is based on the on-site conditions at the time of the survey. Any alteration or change in these conditions may require an upgraded specification in order to accommodate any change in circumstances and may result in additional cost.
20. Where our price includes for forming channels, the extent of channels shown on the drawing is indicative only. The exact extent and layout will be determined on site following a water test.
21. Our Damp Proof Course, Timber and Dry Rot Treatments are guaranteed for ten years from completion date, unless otherwise stated. Plastering, Tanking and Damp Proof Membranes are guaranteed for ten years from completion date. Pump installations are not covered by our guarantees and are subject to manufacturer's warranty period and conditions only. The client is responsible for taking out any maintenance agreement on the pump.
22. The Guarantee Certificates are issued and valid only on receipt of payment of the full amount due including all retention monies.
23. Our Guarantee may be invalidated if works specified in our report are not carried out.
24. If we are requested to revisit under the terms of the guarantee a re-inspection fee will be charged. In the event of a valid claim against the guarantee this fee will be refunded.
25. All chemicals used by the company are cleared under the UK Government's Pesticides Safety precaution Scheme for use as directed. Should our client purchase additives or materials as part of the contract, the client will take full responsibility for the safe handling, storage and use of those supplies and their containers and should refer to manufacturer's data sheets for details.
26. Non-flammable timber preservatives are used unless otherwise stated. However, we advise against the use of naked lights or burning equipment for a period of 8 hours. Do not allow children or animals to come into contact with the treated areas during this period.
27. Where we are instructed to work on structurally weakened timbers, we cannot accept responsibility for any damage which may occur due to their condition.
28. Timbers, which are varnished, painted, or otherwise sealed, cannot be treated successfully unless stripped prior to treatment. Such work is not included within our quotation.
29. We require a minimum of 5 working days' notice prior to each visit. This may vary dependent on the current lead times. 48 hours' notice of cancellation of a visit is required. Failure to comply with this may result in an abortive visit charge of £75 (plus VAT) per man being levied.
30. Whilst all reasonable and due care is exercised by our surveyors our specifications are based on site conditions at the time of survey. We cannot be held responsible for any condition which was not visible at the time of our inspection. Our reports are issued in the context of quotations and are not structural survey reports.
31. Our works will be carried out strictly in accordance with the specified manufacturer's instructions unless otherwise stated. If we are unable to carry out works due to inclement weather, in particular if the temperature falls, or is in danger of falling below 5°C, then we will require additional time in order to carry out works in accordance with the manufacturer's recommendations.
32. No responsibility will be accepted by this company for the standard of works undertaken by others. It is a condition precedent to any order that our client ensures that our recommendations are implemented.
33. All orders accepted and contracts made by the company are contingent upon freedom from all liability for non-fulfilment or delay due to war, strikes, lock-outs, riots, civil commotion, scarcity of materials or labour difficulties or other causes beyond the Company's control.
34. All orders accepted and contracts made by the Company are governed by English Law unless otherwise agreed by the Company
35. The adjudication provisions of the JCT Minor Works Contract will apply to any contract save that the costs of any such adjudication will be reimbursed to this company in any event.

Renlon Limited

Unit 12, Boundary Business Court, Church Road, Mitcham, Surrey, CR4 3TD

Telephone: 0208 687 4000

e-mail: survey@renlon.com

www.renlon.com

TECHNICAL INFORMATION SHEET NO.1 (Including Method Statement)

CHEMICAL DAMP PROOF COURSE

This method statement details our work procedures together with the preparation works and facilities to be provided by others. Our quotations are based upon this sequence of working in one continuous visit for each element. It is important that all preparation works are complete prior to our tradesmen arriving, and clear, safe access is available together with required lighting, power, water, storage space for materials, skips for debris and protection to surrounding areas and finishes.

If our customer wishes to alter the order of the works, this must be agreed prior to scheduling our work and may involve additional costs.

1. USE

The Renlon chemical damp proof course is in accordance with the British Standard Code of Practice BS6576; 2005 and covered by a British Board of Agreement Certificate. The system is designed to control rising dampness in the capillaries of brickwork where:

- a. There is no existing damp proof course.
- b. An existing damp proof course is breaking down or otherwise ineffective.
- c. The existing damp proof course is "bridged" by paths, solid floors etc and it is desirable to form a new damp proof course at a higher level.

The insertion of a chemical damp proof course is only part of a successful system which includes replastering in accordance with our recommendations as covered by our Technical Information Sheet No.4. It is important that the replastering and wall/floor junctions are carried out in accordance with our specifications.

2. CUSTOMER'S RESPONSIBILITIES

- a. Walls must be adequately bonded and stable.
- b. Unrestricted access must be provided to one side of all walls scheduled for damp proof coursing or both sides where walls are in excess of 450mm thick. Where works are planned to party walls, the adjoining owner must be notified in accordance with current regulations.
- c. Any high ground levels must be lowered, wherever possible, to well below internal floor level prior to our arrival on site.
- d. Existing solid floors that do not contain adequate damp proof membranes, or otherwise deteriorated floors should be replaced with new solid floors. The slab must be in place PRIOR to our works. An approved damp proof membrane must be incorporated and dressed up to lap over our damp proof course AFTER our works. The use of polythene membranes should be avoided, due to the difficulties of linking with the damp proof course.
- e. In order to obtain the full benefit of the damp proof course, it is essential that ALL actual and potential sources of moisture ingress be rectified as soon as possible and that thereafter the property be regularly and properly maintained. Our damp proof course must not subsequently be bridged in any way by new paths, gardens, solid floors, etc. External renderings should be stopped short above the level of the damp proof course and terminated in a bell cast mould.
- f. Fungal decay in timber is always related to high moisture content. Timbers bearing into damp walls must be re-supported on metal hangers or brick piers as necessary. Timbers adjacent to damp walls must be isolated with Fungicidal Joinery Lining, (which we can supply upon request) or physical damp proof course material. We can report upon the need for treatment of timbers that may be necessary, if requested.
- g. Walls that have been accumulating dampness for a number of years will not immediately dry out after the insertion of a damp proof course. The residual dampness present within the walling above the level of the damp proof course will take a considerable length of time to disperse to an acceptable level. As a rule of thumb guide, in the British climate, residual dampness disperses at an approximate rate of 25mm (1") thickness of wall per month, dependent upon

temperature, humidity, rainfall, number of air changes and of course, how damp the wall was prior to the insertion of our damp proof course; e.g. 230mm (9") wall = 9-12 months. Walls that are rendered externally will dry more slowly.

- h. The permanent redecoration of newly plastered surfaces should be left as long as possible; at least 12 months. If decorations are contemplated in a shorter period, only water based distemper or non vinyl emulsion should be used, as this will allow the walls to breathe during the drying out period. Any flaking or water markings on the surface can be attended to prior to the final decorations when the walls have returned to normal moisture content. Vinyl wallpapers, gloss paints or other impervious materials must not be used.

3. METHOD AND APPLICATION (by Renlon)

- a. An aqueous silicate fluid is injected into the wall which has the effect of reversing the meniscus in porous masonry. Water rising from the ground in the capillaries is greatly reduced, creating a chemical damp proof course.
- b. The process consists of drilling 10-16mm diameter holes to a depth according to the thickness of the masonry, at pre-determined centres. Where specified, drilling may be carried out from both sides of the wall, but wall thickness of up to 450mm can be injected from one side only. Complementary vertical damp proof courses are injected, where necessary, to isolate treated walls from the effects of rising dampness in adjoining walls.
- c. The course to be injected is chosen so that the position of the horizontal damp proof course is at least 150mm above external ground level or as close as possible to the solid floor surface, taking into consideration the external levels. Where we are injecting above high ground levels the walls beneath will continue to be subject to the lateral penetration of ground water. Please refer to our Tanking (below ground rendering or damp proof membrane) specifications. In the case of thick walls to which access is available from one side only, staggered depth drilling and injection may be undertaken. However, in all cases, the procedure chosen ensures a continuous unbroken band of impregnated material along the length of the wall.
- d. The injection of the silicate solution is carried out under low pressure. Nozzles fitted with pressure-tight seals are inserted into the drilled holes and injection is continuous until saturation is achieved. Holes drilled into external wall surfaces will then be plugged with cement and sand infill unless otherwise specified.
- e. Our system has virtually no odour, no fire risk and there is no potential health hazard as reported with some spirit-based systems.

Should you require any further information, please do not hesitate to contact us.

Renlon Limited

Unit 12, Boundary Business Court, Church Road, Mitcham, Surrey, CR4 3TD

Telephone: 0208 687 4000

e-mail: survey@renlon.com

www.renlon.com

TECHNICAL INFORMATION SHEET NO.8 (Including Method Statement)

VENTED & SEALED CAVITY MEMBRANES

This method statement details our work procedures together with the preparation works and facilities to be provided by others. Our quotations are based upon this sequence of working in one continuous visit for each element. It is important that all preparation works are complete prior to our tradesmen arriving, and clear, safe access is available together with required lighting, power, water, storage space for materials, skips for debris and protection to surrounding areas and finishes.

If our customer wishes to alter the order of the works, this must be agreed prior to scheduling our work and may involve additional costs.

It is important that professional advisers in their design capacity, have complied with the requirements of BS8102 "protection of buildings against water from the ground", for basement construction. Please discuss with our surveyor if required.

1. Cavity Membranes

Renlon are approved installers of a complete range of cavity drainage sheet systems, walls, floor, and curved soffit applications can be tailored to our customers needs and be guaranteed.

The systems are designed to create either a drainage layer or air gap between the structure and the membrane. Depending on the requirement, the system will be either vented or sealed to deal with dampness or running water.

Vented systems do not require sealing at laps or around fixings. They are used above ground level or below ground level where no running water is expected. It is important that our surveyor is informed in writing of any history of flooding or water ingress to the areas.

Where 'Vented Cavity' works are specified the system is based upon the site conditions present at the time of our inspection. Any alteration or change in these conditions, may require an upgraded specification. We recommend that our customer consult with a qualified engineer with regard to groundwater conditions.

Cavity drainage or sealed systems are designed to provide effective wall and floor membranes which allow ground water to pass behind the dimpled sheet to collection points or sumps via falls or drainage channels and hence away from the building, thus allowing no build up of water or water pressure.

Dimpled polythene or polyethylene drainage sheets are fixed to walls and curved soffits using sealed plug fixings. All laps and joints are sealed including service entries. The drainage sheets to the floor structure are lapped and sealed with a linking strip, and held in position by subsequent floor loading. All laps, fixing, service or pipe entries, columns or stanchions are sealed using relevant mastics, sealant or tapes, thus creating a sealed system.

2. Finishes to Membranes.

Recommended finishes vary with different manufacturers. Flooring systems include screeds or flooring grade timber boards. Wall finishes include plasters or renders, where the membrane has to be fixed rigid against the wall and normally require 36 fixings for each square metre.

Dry lining systems are becoming more popular and can be fixed to battens, or independent of the membrane. With drylining, the membrane only requires on average 7 fixings per square metre (as it only needs to support its own weight).

3. General Preparation Works

The following preparation works are to be undertaken by our Customer or their Builder, prior to our arrival on site unless it is clearly stated that Renlon will be carrying out these works.

- a. Remove all furniture, floor coverings etc in the working area and protect all other areas.
- b. Remove skirtings, architraves, plumbing and sanitary fittings and all other obstructions.
- c. Remove any soft plasters or unsound render finishes. All embedded timbers are to be removed and voids bricked and any new concrete lintols set. Any poor bonded or otherwise unsound masonry must be cut out and replaced. The mortar and any other making good must be to a 1:3 cement sand/mix.
- d. All door and window frames/linings must be removed and set aside for possible re-use. Refixing should take place prior to finishes being applied to the membrane.
- e. The client or client's builder is to provide at no extra cost to ourselves:
 - i) Clear access to all working areas, and a secure storage area for materials.
 - ii) Adequate supplies of water, lighting and power in the vicinity of the works.
 - iii) Skip or container to deposit waste and debris.
 - iv) Access scaffold placed in position, if areas of work exceed 2.5 metres high.

4. Preparation of Walls

- a. All substrate surfaces to be thoroughly brushed and washed down to remove loose matter.
- b. In order to ensure continuity of the membrane, abutting walls should be cut back to allow the membrane to continue behind. If this is not possible the membrane will be continued around the abutting walls.
- c. New walls are to be built off a proprietary profile either fixed to the membrane and sealed with mastic or fixed to a flat flexible damp proof membrane with a 300mm lap either side of the profile. The dimpled sheet is then overlapped onto the flat membrane and fixed through all fixings at this junction are sealed with mastic.
- d. Where membranes are to receive plaster direct, it is important that the background is prepared as follows:
 - i) Dubbing out and any straightening of walls should be carried out prior to the fixing of the membrane.
 - ii) All electrical wiring should be sealed in conduit chased into the structure, covered over with a capping or sand and cement render and then clearly marked so as to prevent puncturing when fixing.
 - iii) All chasing out for electrical boxes is to be carried out and the resultant void is to be lined with a suitable damp proof membrane with a lap of 300mm left around the void. The electrical box is screw fixed through the flexible damp proof membrane and the penetrations are mastic sealed. Renlon will overlap the damp proof membrane with the cavity membrane and seal all penetrations.
- e. Where dry lining is used as a finish to the cavity membrane, preparation of the background is not as imperative. The membrane will follow the contours of the wall but any voids should be filled in prior to fixing.

5. Preparation of Floors

If the system is to deal with running water the customer or customer's builder must make provision for dealing with the removal of water.

- a. The substrate must have falls to a drainage outlet and should be laid to prevent ponding in depressions.
- b. Provide drainage channels in existing slabs to falls to drainage outlets. These must be flood tested prior to our works starting.
- c. Where no natural drainage is available, a sump pit should be formed with a suitable sump pump fitted to aid discharge of excess water. An engineer or pump specialist should be consulted and a maintenance agreement arranged.

IMPORTANT NOTES

There may be situations due to adverse conditions when we are unable to offer our normal guarantee. In such circumstances our work will result in considerable improvement upon the conditions existing but may not be wholly watertight. Please note sealed systems are dependent on a working drainage system, so as not to allow the build up water. If this fails for reasons beyond our control, we cannot accept any responsibility for water penetrating the cavity membrane or any subsequent damage to finishes or fixtures. Pump installations are not covered by our 10 year guarantee.

Should you require any further information, please do not hesitate to contact us.

Renlon Limited

Unit 12, Boundary Business Court, Church Road, Mitcham, Surrey, CR4 3TD

Telephone: 0208 687 4000

e-mail: survey@renlon.com

www.renlon.com