

# Report VA2339.180809.NIA

# **45 New Compton Street, London**

Noise Impact Assessment

10 August 2018

Square Feet Architects
95 Bell Street
London
NW1 6TL



01962 461016 0203 8650332 mail@ventaacoustics.com

#### **Contents**

1.	Intr	oduction	1
		ign Criterion and Assessment Methodology	
2	1	Consultation with the Local Authority	
2	2	BS8233:2014	2
3.	Site	Description	2
4.	Env	ironmental Noise Survey	3
4	.1	Survey Procedure & Equipment	3
4	.2	Results	3
4	.3	Plant Noise Emission Limits	4
5.	Pred	dicted Noise Impact	4
5	.1	Proposed plant	4
5	.2	Recommended Mitigation Measures	5
5	.3	Predicted noise levels	5
5	.4	Comparison to NR35 Curve	5
5	.5	Comparison to BS8233:2014 Criteria	5
6.	Con	clusion	6

#### **Attachments**

VA2339/SP1 Indicative Site Plan

VA2339/TH1-TH2 Environmental Noise Time Histories

Appendix A Acoustic Terminology Appendix B Acoustic Calculations

#### 1. Introduction

It is proposed to install twelve new condenser units at 1<sup>st</sup> floor and 5<sup>th</sup> floor roof level at 45 New Compton Street, London as part of the extension of the building.

Venta Acoustics has been commissioned by Square Feet Architects to undertake an assessment of the potential noise impact of these proposals in support of an application for planning permission.

An environmental noise survey has been undertaken to determine the background noise levels at the most affected noise sensitive receptors. These levels are used to undertake an assessment of the likely impact with reference to the planning requirements of Camden Council.

## 2. Design Criterion and Assessment Methodology

## 2.1 Consultation with the Local Authority

Camden Council's Local Plan (adopted June 2017), Appendix 3, provides the following guidance regarding noise from Industrial and Commercial Noise Sources

A relevant standard or guidance document should be referenced when determining values for LOAEL and SOAEL for non-anonymous noise. Where appropriate and within the scope of the document it is expected that British Standard 4142:2014 'Methods for rating and assessing industrial and commercial sound' (BS 4142) will be used. For such cases a 'Rating Level' of 10 dB below background (15dB if tonal components are present) should be considered as the design criterion).

Existing Noise sensitive receiver	Assessment Location	Design Period	LOAEL (Green)	LOAEL to SOAEL (Amber)	SOAL (Red)
Dwellings**	Garden used for main amenity (free field) and Outside living or dining or bedroom window (façade)	Day	'Rating level' 10dB* below background	'Rating level' between 9dB below and 5dB above background	'Rating level' greater than 5dB above background
Dwellings**	Outside bedroom window (façade)	Night	'Rating level' 10dB* below background and no events exceeding 57dBL <sub>Amax</sub>	'Rating level' between 9dB below and 5dB above background or noise events between 57dB and 88dB LAMAA	'Rating level' greater than 5dB above background and/or events exceeding 88dBL <sub>Amax</sub>

\*10dB should be increased to 15dB if the noise contains audible tonal elements. (day and night). However, if it can be demonstrated that there is no significant difference in the character of the residual background noise and the specific noise from the proposed development then this reduction may not be required.

In addition, a frequency analysis (to include, the use of Noise Rating (NR) curves or other criteria curves) for the assessment of tonal or low frequency noise may be required.

\*\*levels given are for dwellings, however, levels are use specific and different levels will apply dependent on the use of the premises.

The periods in Table C correspond to 0700 hours to 2300 hours for the day and 2300 hours to 0700 hours for the night. The Council will take into account the likely times of occupation for types of development and will be amended according to the times of operation of the establishment under consideration.

There are certain smaller pieces of equipment on commercial premises, such as extract ventilation, air conditioning units and condensers, where achievement of the rating levels (ordinarily determined by a BS:4142 assessment) may not afford the necessary protection. In these cases, the Council will generally also require a NR curve specification of NR35 or below, dependant on the room (based upon measured or predicted  $L_{eq,5mins}$  noise levels in octave bands) 1 metre from the façade of affected premises, where the noise sensitive premise is located in a quiet background area.

#### 2.2 BS8233:2014

BS8233 *Guidance on sound insulation and noise reduction for buildings* provides guidance as to suitable internal noise levels for different areas within residential buildings.

The relevant section of the standard is shown below in Table 2.1.

Activity	Location	07:00 to 23:00	23:00 to 07:00
Resting	Living Room	35 dB L <sub>Aeq, 16 hour</sub>	-
Dining	Dining Room	40 dB L <sub>Aeq, 16 hour</sub>	-
Sleeping (daytime resting)	Bedroom	35 dB L <sub>Aeq, 16 hour</sub>	30 dB L <sub>Aeq, 8 hour</sub>

Table 2.1 - Excerpt from BS8233: 2014

[dB ref. 20µPa]

## 3. Site Description

As illustrated on attached site plan VA2339/SP1, the site building is a five storey apartment building located immediately to the east of the St Giles Church grounds. The site is otherwise bounded to the north by dwellings with commercial and public house elements at ground floor level, an apartment building to the south and further mixed use, included residential elements, buildings across New Compton Street to the east.

The background noise levels in the locality are primarily controlled by traffic on St Giles High Street and Shaftsbury Avenue.

It is proposed to install new plant at the roof levels of the new ground floor extension and fifth floor roof extension.

The most affected noise sensitive receivers considered to have the greatest potential to be affected are the existing apartments in the building, specifically the first floor windows on the west facade and the roof lights of the new fifth floor apartments.

Existing building services plant was noted on several of the neighbouring rooftops, including extract plant associated with the pub and cooling plant on the buildings to the east.

## 4. Environmental Noise Survey

#### 4.1 Survey Procedure & Equipment

In order to establish the existing background noise levels at the site, a noise survey was carried out between Wednesday 1<sup>st</sup> and Friday 3<sup>rd</sup> August 2018 at the location shown in site plan VA2339/SP1. This location was chosen to be representative of the background noise level at the most affected noise sensitive receivers.

Continuous 5-minute samples of the  $L_{Aeq}$ ,  $L_{Amax}$ ,  $L_{A10}$  and  $L_{A90}$  sound pressure levels were undertaken at the measurement location.

The weather during the survey period was generally dry with light winds. The background noise data is not considered to have been compromised by these conditions.

Measurements were made generally in accordance with ISO 1996 2:2017 Acoustics - Description, measurement and assessment of environmental noise – Part 2: Determination of sound pressure levels.

The following equipment was used in the course of the survey:

Manufacturer	Model Type	Serial No	Calibration			
ivianulacturei	Model Type	Serial NO	Certificate No.	Date		
NTi Class 1 Integrating SLM	XL2	A2A-12202-E0	42647-A2A-12202-E0	4/10/16		
Larson Davis calibrator	CAL200	13069	UCRT18/1451	26/4/18		

Table 4.1 - Equipment used for the tests

The calibration of the sound level meter was verified before and after use with no significant calibration drift observed.

#### 4.2 Results

The measured sound levels are shown as time-history plots on the attached charts VA2339/TH1-2.

The background noise level is determined by road noise from the surrounding streets.

The typical background noise levels measured were:

Monitoring Period	Typical L <sub>A90,5min</sub>
07:00 – 23:00 hours	52 dB
23:00 – 07:00 hours	48 dB

Table 4.2 - Typical background noise levels

[dB ref. 20 µPa]

#### 4.3 Plant Noise Emission Limits

On the basis of the measured noise levels and the planning requirements of the Local Authority, and considering that it is not expected that tonal noise will be generated by the proposed plant units, the following plant specific sound levels should not be exceeded at the most affected noise sensitive receivers:

Monitoring Period	Design Criterion (L <sub>Aeq</sub> )
07:00 – 23:00 hours	42 dB
23:00 – 07:00 hours	38 dB

Table 4.3 - Specific sound pressure levels not to be exceeded at most affected noise sensitive receivers

## 5. Predicted Noise Impact

### 5.1 Proposed plant

The following plant is indicative of that proposed for installation at roof level.

Plant Item	Quantity	Proposed Model	Notes
Condensers	12	Mitsubishi MXZ-4F72VF	7 units at fifth floor roof level, 4 units at ground floor roof level, 1 unit on the bike store.

Table 5.1 – Indicative plant selections assumed for this assessment.

Consulting the manufacturer's datasheets, sound pressure levels are provided as single number dB(A) values. The heating mode has the higher specified noise level and this shall be assumed. The spectral shape of similar sized units from the manufacture has been used to match the specified overall sound pressure level:

Plant Item	Octave Band Centre Frequency (Hz) Sound Pressure, Lp@1m (dB)								dB(A)
	63	125	250	500	1k	2k	4k	8k	
Mitsubishi MXZ-4F72VF	55	58	57	52	48	44	39	32	54

Table 5.2 - Advised plant noise data used for the assessment.

#### **5.2** Recommended Mitigation Measures

Due to the close proximity of the units to neighbouring windows / skylights, it is recommended that all condenser units are fully enclosed in proprietary enclosures from a manufacturer such as Environ providing the following minimum insertion loss:

	Octave	Band Cen	tre Freque	ency (Hz), /	Acoustic E	nclosure Ir	sertion Lo	oss (dB)
	63	125	250	500	1k	2k	4k	8k
Enclosure for condenser units	12	13	20	29	36	37	39	39

Table 5.3 - Required insertion loss of condenser enclosures.

All plant and ductwork should be fitted with anti-vibration mounts in accordance with the manufacturer guidelines. This is expected to control structureborne noise to the building to acceptable levels.

Please note that the above recommendations relate to acoustic issues only. It is recommended that professional advice confirming the suitability of these measures be sought from others with regards to issues such as airflow, structural stability and visual impact.

#### **5.3** Predicted noise levels

The cumulative noise level at the most affected noise sensitive receivers has been calculated on the basis of the above information and assuming the recommended mitigation measures, with reference to the guidelines set out in ISO 9613-2:1996 Attenuation of sound during propagation outdoors - Part 2: General method of calculation.

A summary of the calculations are shown in Appendix B.

Description	dB(A)
Plant noise criterion	38 dB
L <sub>p</sub> 1m from receiver – 1 <sup>st</sup> Floor	32 dB
L <sub>p</sub> 1m from receiver – 5 <sup>th</sup> Floor	28 dB

Table 5.4 - Predicted noise and level and design criteria at noise sensitive location

#### 5.4 Comparison to NR35 Curve

Frequency (Hz)	63	125	250	500	1k	2k	4k	8k
NR35	63	52	45	39	35	35	30	28
L <sub>p</sub> 1m from receiver – 1 <sup>st</sup> Floor	43	45	37	23	8	0	-7	-14
L <sub>p</sub> 1m from receiver – 5 <sup>th</sup> Floor	39	41	33	19	4	-4	-11	-18

Table 5.5 - Comparison of predicted noise levels against the NR35 criterion

### 5.5 Comparison to BS8233:2014 Criteria

BS8233 assumes a loss of approximately 15dB for a partially open window. The external noise level shown in Table 2.1 would result in internal noise levels that achieve the guidelines shown in Table 2.1.

#### 6. Conclusion


A baseline noise survey has been undertaken by Venta Acoustics to establish the background noise climate in the locality of 45 New Compton Street, London in support of a planning application for the proposed introduction of new building services plant.

This has enabled noise emission limits to be set at the most affected noise sensitive receiver such that the proposed installation meets the requirements of Camden Council.

The cumulative noise emission levels from the proposed plant have been assessed to be compliant with the plant noise emission limits, with necessary mitigation measures specified.

The proposed scheme is not expected to have a significant adverse noise impact and the relevant Planning Conditions have been shown to be met.

#### **Steven Liddell MIOA**



Indicative Site Plan



Figure VA2339/TH1







Figure VA2339/TH2



## **APPENDIX A**

Frequency

dB(A):



Acoustic Terminology & Human Response to Broadband Sound

#### **Acoustic Terminology** 1.1

The human impact of sounds is dependent upon many complex interrelated factors such as 'loudness', its frequency (or pitch) and variation in level. In order to have some objective measure of the annoyance, scales have been derived to allow for these subjective factors.

Vibrations propagating through a medium (air, water, etc.) that are detectable by the auditory Sound system.

Sound that is unwanted by or disturbing to the perceiver. Noise

The rate per second of vibration constituting a wave, measured in Hertz (Hz), where 1Hz = 1 vibration

cycle per second. The human hearing can generally detect sound having frequencies in the range 20Hz to 20kHz. Frequency corresponds to the perception of 'pitch', with low frequencies producing

low 'notes' and higher frequencies producing high 'notes'.

Human hearing is more susceptible to mid-frequency sounds than those at high and low frequencies.

To take account of this in measurements and predictions, the 'A' weighting scale is used so that the level of sound corresponds roughly to the level as it is typically discerned by humans. The measured

or calculated 'A' weighted sound level is designated as dB(A) or LA.

A notional steady sound level which, over a stated period of time, would contain the same amount of acoustical energy as the actual, fluctuating sound measured over that period (e.g. 8 hour, 1 hour,

The concept of Leq (equivalent continuous sound level) has primarily been used in assessing noise L<sub>eq</sub>: from industry, although its use is becoming more widespread in defining many other types of sounds,

such as from amplified music and environmental sources such as aircraft and construction.

Because Leq is effectively a summation of a number of events, it does not in itself limit the magnitude of any individual event, and this is frequently used in conjunction with an absolute sound limit.

Statistical L<sub>n</sub> indices are used to describe the level and the degree of fluctuation of non-steady sound. The term refers to the level exceeded for n% of the time. Hence, L<sub>10</sub> is the level exceeded for 10% of the time and as such can be regarded as a typical maximum level. Similarly, L<sub>90</sub> is the typical minimum

L<sub>10</sub> & L<sub>90</sub>: level and is often used to describe background noise.

It is common practice to use the L<sub>10</sub> index to describe noise from traffic as, being a high average, it

takes into account the increased annoyance that results from the non-steady nature of traffic flow.

The maximum sound pressure level recorded over a given period. L<sub>max</sub> is sometimes used in assessing

environmental noise, where occasional loud events occur which might not be adequately L<sub>max</sub>: represented by a time-averaged Leq value.

#### 1.2 **Octave Band Frequencies**

In order to determine the way in which the energy of sound is distributed across the frequency range, the International Standards Organisation has agreed on "preferred" bands of frequency for sound measurement and analysis. The widest and most commonly used band for frequency measurement and analysis is the Octave Band. In these bands, the upper frequency limit is twice the lower frequency limit, with the band being described by its "centre frequency" which is the average (geometric mean) of the upper and lower limits, e.g. 250 Hz octave band extends from 176 Hz to 353 Hz. The most commonly used octave bands are:

## **APPENDIX A**



Acoustic Terminology & Human Response to Broadband Sound

#### 1.3 Human Perception of Broadband Noise

Because of the logarithmic nature of the decibel scale, it should be borne in mind that sound levels in dB(A) do not have a simple linear relationship. For example, 100dB(A) sound level is not twice as loud as 50dB(A). It has been found experimentally that changes in the average level of fluctuating sound, such as from traffic, need to be of the order of 3dB before becoming definitely perceptible to the human ear. Data from other experiments have indicated that a change in sound level of 10dB is perceived by the average listener as a doubling or halving of loudness. Using this information, a guide to the subjective interpretation of changes in environmental sound level can be given.

Change in Sound Level dB	Subjective Impression	Human Response
0 to 2	Imperceptible change in loudness	Marginal
3 to 5	Perceptible change in loudness	Noticeable
6 to 10	Up to a doubling or halving of loudness	Significant
11 to 15	More than a doubling or halving of loudness	Substantial
16 to 20	Up to a quadrupling or quartering of loudness	Substantial
21 or more	More than a quadrupling or quartering of loudness	Very Substantial

#### 1.4 Earth Bunds and Barriers - Effective Screen Height

When considering the reduction in sound level of a source provided by a barrier, it is necessary to establish the "effective screen height". For example if a tall barrier exists between a sound source and a listener, with the barrier close to the listener, the listener will perceive the sound as being louder if he climbs up a ladder (and is closer to the top of the barrier) than if he were standing at ground level. Equally if he sat on the ground the sound would seem quieter than if he were standing. This is explained by the fact that the "effective screen height" is changing with the three cases above. In general, the greater the effective screen height, the greater the perceived reduction in sound level.

Similarly, the attenuation provided by a barrier will be greater where it is aligned close to either the source or the listener than where the barrier is midway between the two.

## **APPENDIX B**

## VA2339 - 45 New Compton Street, London

## **Noise Impact Assessment**

#### First Floor Reciever

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	55	58	57	52	48	44	39	32	54
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	2	3	3	3	3	3	3	3	3	
Distance Loss	To 2m	-4	-4	-4	-4	-4	-4	-4	-4	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		42	45	37	22	7	-1	-8	-15	32

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	55	58	57	52	48	44	39	32	54
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	1	0	0	0	0	0	0	0	0	
Distance Loss	To 5m	-13	-13	-13	-13	-13	-13	-13	-13	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		30	32	24	10	-5	-13	-20	-27	19

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	55	58	57	52	48	44	39	32	54
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	1	0	0	0	0	0	0	0	0	
Distance Loss	To 6m	-16	-16	-16	-16	-16	-16	-16	-16	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		27	30	22	7	-8	-16	-23	-30	17

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	55	58	57	52	48	44	39	32	54
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	1	0	0	0	0	0	0	0	0	
Screening loss		-18	-18	-18	-18	-18	-18	-18	-18	
Distance Loss	To 21m	-26	-26	-26	-26	-26	-26	-26	-26	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		-1	1	-7	-21	-36	-44	-51	-58	-12

<sup>\*</sup> Screening loss limited to 18dB

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	-12	-13	-20	-29	-36	-37	-39	-39	-24
Enclosure SRI	-p C	-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	2	3	3	3	3	3	3	3	3	
Screening loss		-18	-18	-18	-18	-18	-18	-18	-18	
Distance Loss	To 18m	-25	-25	-25	-25	-25	-25	-25	-25	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		-64	-66	-80	-98	-116	-121	-125	-125	-81

<sup>\*</sup> Screening loss limited to 18dB

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	-12	-13	-20	-29	-36	-37	-39	-39	-24
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	1	0	0	0	0	0	0	0	0	
Screening loss		-18	-18	-18	-18	-18	-18	-18	-18	
Distance Loss	To 17m	-25	-25	-25	-25	-25	-25	-25	-25	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver	·	-67	-68	-82	-101	-119	-124	-128	-128	-83

<sup>\*</sup> Screening loss limited to 18dB

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	-12	-13	-20	-29	-36	-37	-39	-39	-24
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	2	3	3	3	3	3	3	3	3	
Screening loss		-18	-18	-18	-18	-18	-18	-18	-18	
Distance Loss	To 14m	-23	-23	-23	-23	-23	-23	-23	-23	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		-62	-64	-78	-96	-114	-119	-123	-123	-78

<sup>\*</sup> Screening loss limited to 18dB

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	-12	-13	-20	-29	-36	-37	-39	-39	-24
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	2	3	3	3	3	3	3	3	3	
Screening loss		-18	-18	-18	-18	-18	-18	-18	-18	
Distance Loss	To 15m	-24	-24	-24	-24	-24	-24	-24	-24	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		-63	-64	-78	-97	-115	-120	-124	-124	-79

<sup>\*</sup> Screening loss limited to 18dB

Cumulative Level	43	45	37	23	8	0	-7	-14	32



#### Fifth Floor Reciever

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	0	0	0	0	0	0	0	0	7
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	2	3	3	3	3	3	3	3	3	
Distance Loss	To 14m	-23	-23	-23	-23	-23	-23	-23	-23	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		-32	-33	-40	-49	-60	-64	-66	-66	-44

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	0	0	0	0	0	0	0	0	7
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	1	0	0	0	0	0	0	0	0	
Distance Loss	To 16m	-24	-24	-24	-24	-24	-24	-24	-24	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver	·	-36	-37	-44	-53	-64	-68	-70	-70	-49

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	0	0	0	0	0	0	0	0	7
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	1	0	0	0	0	0	0	0	0	
Distance Loss	To 15m	-24	-24	-24	-24	-24	-24	-24	-24	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		-36	-36	-43	-53	-64	-68	-70	-70	-48

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	0	0	0	0	0	0	0	0	7
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	1	0	0	0	0	0	0	0	0	
Screening loss		-18	-18	-18	-18	-18	-18	-18	-18	
Distance Loss	To 25m	-28	-28	-28	-28	-28	-28	-28	-28	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		-58	-59	-66	-75	-86	-90	-92	-92	-70

<sup>\*</sup> Screening loss limited to 18dB

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	55	58	57	52	48	44	39	32	54
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	3	5	5	5	5	5	5	5	5	
Distance Loss	To 3m	-9	-9	-9	-9	-9	-9	-9	-9	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		39	41	33	19	4	-4	-11	-18	28

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	55	58	57	52	48	44	39	32	54
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	2	3	3	3	3	3	3	3	3	
Distance Loss	To 12m	-22	-22	-22	-22	-22	-22	-22	-22	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		24	27	19	4	-11	-19	-26	-33	14

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Mitsubishi MXZ-4F72VF	Lp @ 1m	55	58	57	52	48	44	39	32	54
Enclosure SRI		-12	-13	-20	-29	-36	-37	-39	-39	
Number of Plant	2	3	3	3	3	3	3	3	3	
Distance Loss	To 17m	-25	-25	-25	-25	-25	-25	-25	-25	
Directivity (Hor:90,Vert:0)		0	0	0	0	-4	-7	-7	-7	
Level at receiver		21	24	16	1	-14	-22	-29	-36	11

Cumulative Level	39	41	33	19	4	-4	-11	-18	28