

Notes: Alteration works

- Removal of the stud partition wall to room TF5 creating an open plan office and kitchenette.
- and kitchenette.
  Carefully form an opening to the lateral walls between TF4 and TF5, leaving nib of 500mm as per engineers design with bespoke moulded architraves fitted all round to protect edges of existing lath and plaster walls.
  Additional W/C will be created as shown to room TF3.
  New stud partition will be at this level approx 140mm width, timber framed incorporating insulation. Finished with plywood and plasterboard over, with the initiate order deviation and existing and an environment.
- the joints scrimmed and skimmed.
- Removal of the existing drop ceilings to restore original ceiling height. Fireplaces to be retained to room numbers TF4 and TF5. •
- •
- Fire doors (FD) Supply and fit new Georgian style 6 panel oak veneered doors to be 30 minute resistant. Complete with intumescent strips. Smoke seals routed into door edges, complete with new ironmongery and over head closer's.
- Existing doors (Ex) retain existing doors.

500 1000 3000 0.5 2 3 1

Scale

4000

4

5000 (mm)

5 (m)

## Note:

1. This drawing is copyright.

- 2. Contractors must check all dimensions on site.
- 3. Figured dimensions are to be used in preference to scaled dimensions
- 4. Discrepancies must be reported immediately.

62
DG
FAP
I.A
D.B
(SD)
<u> </u>
(700.5)
Ш
-
Fire Door
Existing Door
Door

REVISION	DATE	DESCRIPTIO	N		BY
M		Chartered :	& SO Surveyors	-	-
PROJECT	87 GO		STREE /C1E 6,		
	ropose ayout	ed Thi	rd Floo	or	
DATE	20/03/2018		DRAWN BY CHECKED BY	HAB	
SCALE	1:50 @ A3		CHECKED BY		
	5 NUMBER 8002	/3/10	)4	REVISION	