



1 GROUND FLOOR PLAN - PROPOSED



2 FIRST FLOOR PLAN - PROPOSED



3 ROOF PLAN - PROPOSED

DO NOT SCALE FROM THIS DRAWING

Figured dimensions only are to be taken from this drawing. All dimensions are to be checked on site before any work is put in hand. If in doubt, ask.

All SHH drawings to be read in conjunction with relevant SHH Finishes, Sanitaryware, Lighting & Ironmongery schedules.

Any discrepancies to be highlighted to SHH prior to procurement and in good time.

Copyright © Spence Harris Hogan Limited 2018
Registered in England & Wales. Registered No. 261 0615
SHH is the trading name of Spence Harris Hogan Limited

0 1 2 3m

Legends & Notes: GENERAL NOTES

1. Allow for some pointing repairs and brickwork replacement as necessary - to be assessed post clean.
2. Existing brick reclaimed from demolition process to be used for all New Brick, where there is insufficient reclaimed brick to match existing other approved brick is to be used - samples required.
3. Existing Clay Tiles to be replaced with new to match existing including decorative tiles to ground floor bay window roof - samples required.
4. Refer to SE for specification for crack repairs and any other repairs to masonry, with any holes left after removal of elements to be made good.
5. Repair or replacement of any existing decorative roof timbers to match existing.
6. Chimneys to be retained and to be unblocked for use as fireplaces as required - New decorative clay pots to be installed - Design TBC
7. All rainwater goods to be replaced with new - Refer to NBS: R10
8. Refer to Security Specialist for specification of CCTV and other Security Elements

PL03	28.08.18	Planning Issue	JD
PL02	17.11.17	Planning Amendments - Issue for Comments	ZS
PL01	16.06.16	Planning Issue	JH
Rev	Date	Descriptor	Athr.

shh
SHHARCHITECTS|INTERIORDESIGNERS
RIBA **MEMBER**
Chartered Practice

1 Vencourt Place, Ravenscourt Park
Hammersmith, London W6 9NU
Phone +44 (0) 20 8600 4171 Email info@shh.co.uk
shh.co.uk

Project:
Athlone House - Gate House
Hampstead Lane
London
Client:
Private Client
Drawing Title:
040 General Arrangements

Floor Plans

(Project number)DWG number_Revision:	Checked:
(817)GH-040_PL03	SM