## 2.4 Option 4 - Proposed Changes - Reinstate spine wall at high level


## 2.4 Option 4 - Proposed changes Cupboard removed & door relocated Spine Wall Relocated at High Level

- 2.4.1 Removal Work
  Remove existing partition wall at higher level above kitchen units. See section BB.
- 2.4.2 Structural Alterations
  No structural alterations required.
- 2.4.3 Windows

  No windows are affected.
- 2.4.4 Internal Walls

  To be made good after removing
  units for partition removal at higher
  level.
- 2.4.5 Floor Finishes

  New timber floor within cupboard area
- 2.4.6 Staircase Staircase not affected.
- 2.4.7 Ceiling
  Extent of newly exposed ceiling to be made good and finished to match existing.
  New cornice to be reinstated to match original ceiling proportions.
- 2.4.8 Internal Doors
  Existing lounge door relocated within spine wall as shown.
- 2.4.9 Fixtures & fittings
  Kitchen units amended and refitted as required.



## 2.4 Option 4 - Proposed Changes - Reinstate spine wall at high level

