02

FORM NEW OPENING -TO ACCESS STAIRS



ALL LAYOUTS SUBJECT TO THE FOLLOWING APPROVALS:- CLIENT, LANDLORD, FIRE, BUILDING CONTROL, MECHANICAL AND STRUCTURAL.

LAYOUTS & DETAILS TO BE USED IN CONJUNCTION WITH FIRE **REVIEW & STRATEGY.**

BUILDING OUTLINES SUPPLIED

FULL ARCHITECTURAL SURVEY

EXISTING DISABLED REFUGES TO ALL STAIRS TO BE CHECKED. NEIGHBOURING PROPERTIES ESCAPE THROUGH THIS BUILDING - HOARE

LEA FIRE TO CONFIRM DISABLED WC'S TBC - BUILDING CONTROL MAY REQUIRE MORE

DUE TO TRAVEL DISTANCES. ALL NEW RISERS TO BE 90 MIN.

FIRE RATING.

SOME COLUMNS MAY BE EXPOSED - TBC BY WEWORK

Floor Area m2	Floor Area ft2		
2019 m ²	21,733 \$	SF	
Square foot shown is based on supplied building shell and includes all columns - suject to site survey			
GENERAL CEILING HEIGHT = TBC mm unless other noted - Refer to survey details			
FLOOR VOID = TBC mm unless other noted - Refer to survey details			
CEILING VOID = TBC mm unless other noted - Refer to survey details			
ACCOMMODATION SCHEDULE			
FACILITY	/	QTY	
BRAINSTORM ROOM		1	
CONFERENCE ROOM		6	
FEMALE WC		2	
IT		2	
JC		1	
LOUNGE		1	
MALE WC		2	
NOOK		5	
PANTRY		1	
PHONE BOOTH		9	
PRINTER		2	
PRIVATE OFFICE		49	
STORE		1	

FACILITY		QTY
Name	Occupancy	QII

TOTAL HEAD COUNT 394

KEY

NEW WORKSTATIONS 1220 x 610mm WITH 'T' BAR LEGS

JOINERY ITEM



Minimal Works or No Works proposed to these areas. Notes shown in red. — FIRE CURTAIN LINE



NOTES: SEE CONTRACTORS DRAWINGS FOR A/V, SECURITY ETC. FIRE BARRIERS ON P-SET & LLS DRAWINGS.

LTB TO SUPPLY AND FIT ALL WHITEBOARDS

Н	North Symbol & Scale Bar added	TK	19.09.18		
G	Layout change to South Wing for Custom Deal	TK	13.09.18		
F	Minor Amendments, Including Tile Setting Out	TK	14.09.18		
E	Updated to WW comments 23.07.18	GM	01.08.18		
D	Amended to match updated EC. Updated Floor Grid & Grommet Locations	тк	25.07.18		
С	General updates to detail design	TK	16.07.18		
В	General updates to detail design	CE	22.06.18		
A	Revisions following design meeting & site visit	TK	15.06.18		
-	Drawing First Issue	CE	08.06.18		
Rev	Descriptive Amendments	Drawn By	Date		
	Pre-Design - Construction - As Built				
Construction					

Client

WeWork

Client Contact Project Name

125 Kingsway

Drawing Title 2nd Floor - General Arrangement

1128

Account Manager

Designer / Senior Tech. Designer / Project Manager Rebekah Webber / Tim Kirkman / Jordan Reay Scale @ A0 Drawn B First Drawing Date 16/05/18 1:100 ΔΝ Contract Number Floor

02

GA