



01 Existing plan

1:200

KEYS - item demolition

- ① Remove metal disks set in ground inc. kerbs
- ② Remove existing raised timber planters
- ③ Remove existing tree
- ④ Remove existing play structure - slide and tower
- ⑤ Remove existing play structure - timber log net bridge
- ⑥ Remove existing play structure - timber balancing logs
- ⑦ Remove existing play structure - adventure play timber structure
- ⑧ Trees to be relocated

KEYS - surface demolition

- (A) Remove existing grass mound - retain soil & fill for reuse
- (B) Remove existing boulder mound - retain for reuse
- (C) Remove existing crazy paving
- (D) Remove existing grass and prepare for tarmac surface
- (E) Remove existing sand pit and prepare for new surfacing
- (F) Remove existing tarmac and prepare substrate for new wetpour/ rubber mulch surface
- (G) Remove existing timber steps set in ground
- (H) Remove existing tarmac path and prepare for safety surfacing
- (I) Remove existing grass mat

LEGEND

- Existing fence: Refer to plan for height
- Remove existing timber gate
 - Remove existing timber hoarding
 - Remove existing timber low retaining wall
 - Remove existing timber post and rail fence/palisade

LEGEND

- Levels
- +40.00 Existing level to remain as is
 - +40.00 Existing level to be changed
 - +40.00 Proposed level
 - Existing mounding
 - Existing mounding to be reshaped

LEGEND

- Trees / plants
- Existing sapling trees relocated
 - Root Protection Area
 - Existing trees

P	27.09.18	Issued for Planning
SK	07.09.18	Issued for Costing rev02
SK	04.09.18	Issued for Costing rev01
SK	31.08.18	Issued for Costing

erectarchitecture.
22b Regent Studios, 8 Andrews Rd, London E8 4QN, t.020 72546336

client **LBC**
project **Kilburn Grange Park**
title **Demolition Plan**
scale/date **1:200 at A3/ 23.08.18**
drwg no **344-KGP-DEM01**