

Key Plan Mary Ward (neighbour) Existing party wall Proposed courtyard extension For structural openings, see door schedule 1615-ST-Q1-ZZ-SH-A-8301-8303 Final Measurements to be taken by manufacturer on site prior to manufacture. Door handles to be 1050mm AFFL unless otherwise stated. Door closers to be concealed. Ironmongery - Refer to schedule for all types Refer to 5370-5372 for Typical Louvre Screen Details. Specification Reference 25-55-45/170 Please note that a generic louvre system has been drawn to be read in conjunction with Alps proposals Openings for ductwork/service routes to be co-ordinated with MEP engineers prior to manufacturing For fire escape gate to Gage Street, refer to drawing 5654 Maximum heights have been noted which have been granted from Camden. This also screens the plant within the compound to meet the acoustic requirements. Any discrepancy should be identified and

highlighted to the architect.

Rev	Date	Details/ Amended by	Sign
P1	10.01.18	Draft Stage 4 Issue / JB	LM
A7	07.02.18	STAGE 4 SUBMISSION/ LM	AML
A12	25.06.18	REVISED STAGE 4 ISSUE / LM / MJF	LM
C1	19.09.18	First Construction Issue - Louvres -MJF	LM

sonnemanntoon

architects

Quality House 6-9 Quality Court Chancery Lane London WC2A 1HP

United Kingdom

tel: +44 (0)20 7580 8881 email: info@st-arch.co.uk web: www.st-arch.co.uk © This drawing is copyright

Do not scale this drawing. Architect to be informed of all discrepancies in dimensions. Contractor to check all dimensions on site.

Project title

ITALIAN HOSPITAL Drawing title

DETAILS: FIXED LOUVRES Louvres - Type LR-01

CONSTR.

1: 2 @A1

Drawing number

1615-ST-Q1-ZZ-DR-A-5372