

APPENDIX 4

SPECIFICATION FOR MOVEMENT MONITORING



1 SPENCER RISE LONDON NW5 1AR MOVEMENT MONITORING

INTRODUCTION

- Movement monitoring will be carried out by special contractor.
- Recommendations of BRE Digest 343 Part 2 'Simple Measuring and monitoring of movement to low rise buildings' shall be followed.
- Movements in three planes (left to right, front to back and verticality) will be measured relative to remote and stable control stations.

EQUIPMENT

• All measurements will be made with suitable EDM equipment.

ACCURACY

The accuracy (stated standard deviation to ISO 17123-4) in both level and plan position shall be +/- 1mm but this
is dependent upon site conditions / weather at the time of survey.

MONITORING STATIONS

Monitoring points shall be agreed between the party wall surveyors and consulting engineer. The targets to be
monitored will be retro reflective targets fixed to the walls with resin adhesive See attached plans / photos for
proposed positions.

SURVEY CONTROL

Minimum of 3 reference points remote from the site. (At least 5.0m away from the site boundary)

PROCEDURE

- Survey equipment shall be set up on firm a base.
- Each location will be measured in turn and readings of distance and angle, and Northing, Easting and height will be recorded.
- Readings will be repeated on both faces of the instrument.

FREQUENCY

- Two sets of baseline readings will be taken before any excavation work commences, with an interval of no less than 5 days between the two sets of readings.
- Frequency of readings during the basement excavation works will be weekly.
- One final reading will be taken 4 weeks after basement works are complete.

TRIGGER VALUES

Amber Level = 5mm

At Amber level basement construction work will cease and procedures reviewed by the project Structural
Engineer to determine additional safeguards or working practices need to be implemented. Work will not restart
until approval of project Engineer. The building owner's surveyor and adjoining owner's surveyor informed of
level being reached, monitoring will become more frequent at weekly intervals.

Red Level = 8mm

- Construction works shall cease on site until a thorough review of working practice has been carried out by project Structural Engineer. Any additional temporary works shall be implemented by Contractor
- Works will not recommence until approval has been given by the Project Engineer and both the owner and adjoining owner surveyors.

RESULTS

- The recorded results shall be tabulated and graphically presents in report form and issued to all relative parties
- Monitoring results shall be presented within 24 hours of measuring.
- The contractor will identify trends in movement from the results before amber level is reached and assess the best course of action to take.

0203

Sort Code


Drawing No. Revision

1:100 @ A3

A/1SR

0204

Subject: Existing Rear Elevation Project: 1 Spencer Rise 45 Notling Hill Gate, London, W11 3LQ E. mall@edwardwilliamsarchitects.com EDWARD WILLIAMS ARCHITECTS



NOTES:

G15 Refer to Abox/9100 for T Street references, and to Abox/9110 to 9167 for Architectural Specifications. G14 Setting Out Points shown thus: G13 Finishes are shown thus:

G12 T Sheet Reference shown thus G11 Clear height is shown thus (finished floor to finished soff!) GENERAL NOTES:

G6 Refer to Engineers drawings for all structural and services Information. G5 Use figured dimensions only; Do not scale from drawings. If IN DOUBT, ASK,

OB For destruction of works unabject to Continuation's Dunlight, this drawing is indicating of the sideaud for performances to condementate only. The Continuation is magnostable to the statistical or sideaud redsign and co-certification of the statistical relation to the continuation of the statistical relation to the continuation of the contin

G7 For tolerances see the Design Drawings and Specifications

