



New internal metal stud partition walls, British Gypsum 70mm Gyframe 70 S 50 'C' studs at 600 c/c, Isover 25mm APR1200 acoustic insulation between studs.
Metal studs indicated, timber may have to be used subject to feedback from conservation officer.
Allow for CP backerboard to wet areas with tiling, MR plasterboard in areas with potential condensation eg. kitchens, bathrooms.
All dry lining works to NBS K10.

Indicates existing building fabric, exact build up to be confirmed in areas where works are taking place when opening up commences. Method of construction to be agreed with conservation officer.

1 Existing Long Section 2
Scale 1:50

P2	Amendments to GA information	02.11.18	LS	LH
P1	Tender Issue	20.09.18	LS	LH
Rev	Description	Date	Chk	Appr
Project No:	Scale @ A1:	As Indicated	Drawn By:	LH
811618				

Ingleton Wood Property and Construction Consultants
Issuing office: London
T: 020 7680 4400
www.ingletonwood.co.uk

Vision, form and function
Project:
1, Taviton Street Refurbishment
Euston
London
WC1H 0BT
Client:
University of London

Title:
Proposed Long Section 2

Drawing Number:
TAV - IW - XX - XX - DR - A - 2546

Status:	Purpose of Issue:	Revision:
D2	TENDER	P2