



T: 0845 463 6303 E: info@itechroofworks.co.uk

Pine Ridge, Roundwood, Kings Langley. WD4 8BE

Nathaniel Mosley Architects

JS030816-1R1

12-Oct-16

Quotation
REVISED*

3 Leverton Place, London NW5 2PL

Supply & Fit Bauder Total Green Roof System per Drawings, Specification & Info Provided:

	<u>Qty</u>	<u>Unit</u>
J41 Built Up Bituminous Felt Warm Deck Roof- Ground Floor Extension - Green Elements Below		
Bauder SA Primer, to plywood deck by others	15	m2
BauderTherm KSD Mica Vapour Control Layer	15	m2
Bauder PIR FA-TE Flatboard Insulation, 120mm thickness (U-value 0.17)	15	m2
BauderTEC KSA DUO Underlayer	15	m2
Bauder Plant-E root resistant capping sheet	15	m2
Perimeter Upstand Flashings, max girth 150mm	16	lm
GRP Drip Edge	16	lm
Rainwater Outlets	3	Ea

<i>Subtotal</i>	£2,772.50
-----------------	------------------

Green Roof Elements

	<u>Qty</u>	<u>Unit</u>
Bauder SDF Mat	11	m2
* Bauder Xero Flor XF118 Wildflower Blanket	11	m2
Delivery Charges	1	Item
AL40 Edge Trims	13	lm
20/40 Washed River Pebbles, 250mm width	15	lm
Bauder ALU 250 Inspection Chamber (To outlet)	3	Ea

<i>Subtotal</i>	£2,044.00
-----------------	------------------

Scaffolding

<i>Subtotal</i>	£1,050.00
-----------------	------------------

Bauder 20 Year Guarantee

Included

Total	£5,866.50
--------------	------------------

VAT Chargeable at Current Rate

Note:

* Dedicated 110 Volt 10 KVA Supply Required, Vertical Hoist, Site Skips Required.

Extra Over / Add Items You May Require:

Abortive / Return Trip Charge	£295.00	Ea
Service Cable Bends	£140.00	Ea
Hardedge to Box Gutter	£16.00	lm
Code 4 Lead Cover Flashings < 150mm Girth & Lead Caulk	£32.00	lm
Mansafe Post Flashings (Excludes Mansafe)	£65.00	Ea
Walkway Membrane	£27.00	Ea
SVP / Extract Flashings 110mm Dia.	£65.00	Ea

Itech Roofworks Ltd trading as P&R Roofing Contractors (Watford)

Reg. Office. 8th Floor, Elizabeth House, 54-58 High Street, Edgware, Middlesex, HA8 7RJ

Directors. K. Reynolds.

Company No.7915629

Vat. No. 133 5746 15

