

Notes

					L
					L
NO DIMENSIONS ARE TO BE SCALED FROM THIS DRAWING. THE CONTRACTOR/MANUFACTURER IS RESPONSIBLE FOR CHECKING AL COPYRIGHT IS RESERVED BY THEM AND THE DRAWING IS ISSUED ON CONDITION THAT IT IS NOT COPIED, REPRODUCED, RETAINED					

Schedule of items to be protected at all times:

1.	Staircase - treads and hand rail - to be adequately protected at all times throughout the works and for the duration of the main construction works. The contractor is to advise on how this will be achieved.
2.	All existing windows unless specifically identified on drawings
3.	All doors unless specifically identified on the drawings for removal within or on the access routes to the project scope area - including frames, architraves, stops, ironmongery. Removed doors to be set aside for reuse.
4.	All stonework including wall cladding and floor tiles at ground floor.
5.	All ironwork including railings, ballusters, SVPs', rainwater goods, hoppers
6.	Lift doors and interior of lift car if being utilised for materials delivery.

Key		Notes
	Removal of fixtures	Generally spaces are to be stripped back to the existing substrates removing all finishes fixtures and redundant services. Additional notes on drawings do not necessary capture entire set of strip out each space and are intended to provide additional helpful informat only. No laibility is accepted for information not included within this drawing.
	Demolition of lightweight partitions	ст, , , , , , , , , , , , , , , , , , ,
		Floors Existing floor finishes to be removed back to screed except where noted on the drawing
	Demolition of masonry walls	Contractor to carry out a spot level survey following strip out to confirm tolerances.
		Walls
	Demolition of lowered ceilings	Walls are a mixture of masonry and light weight partitions.
	Demolition of floor	Fixtures & Fittings With the exception of those noted on the drawings all fixtures and fittings (including sanitaryware) are to be removed.
_	Project Scope Area	Decorative Items All decorative items are to be retained in place as noted on the drawings. Any items discovered during the strip out works are to be notified to the Project Manager.
*	Boxed out services shown as demolished and re-located. Services Consultant to advise if this is acceptable	Services Refer to M&E Engineers specification for details of the services strip out.
*	Boxed out services shown as	Windows No works to windows are currently proposed.

Client Project Drawing	UCL Rockefeller Refurbishment Demolitions Fifth			Burwell Deakins		
Scale 1:100@ A1 Date August 2018		Drawn CG				
Project Nº 789	Drawing N° 789_PL_026		Revision A	Unit 0.01 California Building London SE13 7SF +44 (0) 2083 056010	First Floor 6 Southernhay West Exeter EX1 1JG +44 (0) 1392 423981	