



GROUND FLOOR PLAN



NOTE:
 This survey is of a preliminary nature. The trees were inspected from the ground only on the basis of the Visual Tree Assessment method. No samples were taken for analysis. No decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.
 Branch spread in metres is taken at the four cardinal points to derive an accurate representation of the crown.
 Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base).

Landmark Trees
 20 Broadwick Street, London, W1F 8HT
 Tel: 0207 851 4544 Mobile: 07812 988928
 e-mail: info@landmarktrees.co.uk Web: www.landmarktrees.co.uk

Site: 52 Reddington Road
 Drawing Title: Tree Constraints Plan
 August 2018

Key:

● High Quality	○ Crown Spread
● Category B	○ Tree Number
● Moderate Quality	○ Species
● Category C	○ Protection Area
● Low Quality	○ Category
● Category U	○ Tree Position Approximate (not shown on original survey)
● Trees Unsuitable for Retention	