

SCHEDULE OF PROPOSED WORKS

- Re-constructed and new brick piers with new double-pitched coping stones to match no. 104 Chetwynd Road
- 2. New wrought iron gate with finials to match no. 104 Chetwynd Road.
- Re-constructed front boundary wall comprising new brick dwarf wall and railing over. Existing bricks to be re-used with new bricks, where required, to

match existing. Brickwork to have flush lime mortar pointing. Existing brick pier and coping stone retained.4. New wrought iron gates with finials to match no. 104 Chetwynd Road.

- 5. New double-pitched coping stone to existing brick pier.

2

5m

The use of this data by the recipient acts as an agreement of the following statements. Do not use this data if you do not agree with any of the following statements:-

All drawings are based upon site information supplied by third parties and as such their accuracy cannot be guaranteed. All features are approximate and subject to clarification by a detailed topographical survey, statutory service enquiries and confirmation of the legal boundaries.

Do not scale except for planning purposes.

Report any discrepancies in writing to Palmer Lunn Architects before proceeding.

P01 Rev	Plann	•	03.12.2018 Date	B APa Drn	MLu Chk
Rev Description Date Drn Chk Status PLANNING					
Client Mitzi Mina & Greg Rubinstein					
Project 100 Chetwynd Road London NW5					
Drawing Landscape Plan as Proposed					
Project 1800	rt No. B		g No. PL-10	Revis P01	ion
Scale 1:100	@ A3	Drawn APa	Ву		
palmer lunn architects					
www.palmerlunn.com					

10m