






BUILDING DESIGN PARTNERSHIP LTD SHALL HAVE NO RESPONSIBILITY FOR ANY USE MADE OF THIS DOCUMENT OTHER THAN FOR THAT WHICH IT WAS PREPARED AND ISSUED.
 ALL DIMENSIONS SHOULD BE CHECKED ON SITE.
 DO NOT SCALE FROM THIS DRAWING.
 ANY DRAWING ERRORS OR DIVERGENCES SHOULD BE BROUGHT TO THE ATTENTION OF BUILDING DESIGN PARTNERSHIP LTD AT THE ADDRESS SHOWN BELOW.

NOTES

- A - SCOPE OF WATER-PROOFING REQUIREMENTS AND THE PROPOSED DETAILS HAVE BEEN PROVIDED ON THESE DRAWINGS HAVE BEEN TAKEN FROM HEYWOOD'S DAMP REPORT ON THE 01.06.18.
- B - ALL WORK TO BE DESIGNED AND COMPLETED IN ACCORDANCE WITH THE RECOMMENDATIONS SET OUT BY HEYWOODS AND APPROVED TRITON DETAILS AS RECOMMENDED BY HEYWOODS.
- C - INSURANCE-BACKED GUARANTEES TO BE PROVIDED BY HEYWOODS FOR ALL RELEVANT WORKS.
- D - COMPLETION OF DESIGN AND EXECUTION OF ALL DAMP PROOFING WORKS TO BE CARRIED OUT IN ACCORDANCE WITH BS 8102-2009.

-  Remedial damp proofing as detailed in Heywood report
-  Cavity drainage membrane system (CDM)
-  Cementitious tanking system localised repairs as detailed in Heywood's email on 10/10/18
-  Vertical chemical DPC injection
-  Proposed drainage route from CDM system to land drain



Boiler flue and ducts penetration into the above vault.
 P8 membrane to run up to the top floor opening.
 Ref. to details (50)AD012, (50)AD013, (50)AD014.

REVISION/DESCRIPTION	DRAWN	CHECKED	DATE
C - For Planning and Listed Building Consent Application	NA	AC	17/12/18
B - For Planning and Listed Building Consent Application	MF	AC	29/10/18
A - For Planning and Listed Building Consent Application	MF	AC	01/06/18
FIRST ISSUE	MF	AC	30/05/18

