



PTAL output for Base Year 5

NW3 7AD
Finchley Rd, London NW3 7AD, UK
Easting: 525475, Northing: 185547

Grid Cell: 106971

Report generated: 06/12/2018

Calculation Parameters

Day of Week	M-F
Time Period	AM Peak
Walk Speed	4.8 kph
Bus Node Max. Walk Access Time (mins)	8
Bus Reliability Factor	2.0
LU Station Max. Walk Access Time (mins)	12
LU Reliability Factor	0.75
National Rail Station Max. Walk Access Time (mins)	12
National Rail Reliability Factor	0.75

Map key - PTAL

0 (Worst)	1a
1b	2
3	4
5	6a
6b (Best)	

Map layers

- PTAL (cell size: 100m)

Calculation data

Mode	Stop	Route	Distance (metres)	Frequency(vph)	Walk Time (mins)	SWT (mins)	TAT (mins)	EDF	Weight	AI
Bus	FINCHLEY RD HEATH DRIVE	113	32.45	7	0.41	6.29	6.69	4.48	0.5	2.24
Bus	FINCHLEY RD HEATH DRIVE	82	32.45	8.75	0.41	5.43	5.83	5.14	1	5.14
Bus	FINCHLEY RD HEATH DRIVE	13	32.45	8	0.41	5.75	6.16	4.87	0.5	2.44
Bus	WEST END GREEN	C11	452.99	7.5	5.66	6	11.66	2.57	0.5	1.29
Bus	WEST END GREEN	139	452.99	7.5	5.66	6	11.66	2.57	0.5	1.29
Bus	FORTUNE GN R HILLFIELD R	328	308.79	9	3.86	5.33	9.19	3.26	0.5	1.63
Rail	Finchley Road & Frognal	'CLPHMJ2-STFD 2L50'	850.77	3.67	10.63	8.92	19.56	1.53	1	1.53
Rail	Finchley Road & Frognal	'STFD-CLPHMJ2 2Y11'	850.77	3.67	10.63	8.92	19.56	1.53	0.5	0.77
Rail	West Hampstead	'BEDFDM-SUTTON 10I13'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'STALBCY-SVNOAKS 2E11'	650.48	1	8.13	30.75	38.88	0.77	0.5	0.39
Rail	West Hampstead	'BEDFDM-SVNOAKS 2E19'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'LUTON-SVNOAKS 2E21'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'STALBCY-SVNOAKS 2E95'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'SUTTON-LUTON 2000'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'SUTTON-BEDFDM 2004'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'SUTTON-STALBCY 2006'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'SUTTON-LUTON 2010'	650.48	1	8.13	30.75	38.88	0.77	0.5	0.39
Rail	West Hampstead	'LUTON-SUTTON 2017'	650.48	0.67	8.13	45.53	53.66	0.56	0.5	0.28
Rail	West Hampstead	'STALBCY-SUTTON 2021'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'STALBCY-SUTTON 2029'	650.48	0.67	8.13	45.53	53.66	0.56	0.5	0.28
Rail	West Hampstead	'LUTON-BCKNHMJ 2S91'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'STALBCY-BROMLYS 2S93'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'BRGHTN-BEDFDM 2T02'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'BRGHTN-BEDFDM 2T04'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'SUTTON-STALBCY 2V02'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'SUTTON-STALBCY 2V08'	650.48	0.67	8.13	45.53	53.66	0.56	0.5	0.28
Rail	West Hampstead	'BEDFDM-SUTTON 2V15'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'SUTTON-BEDFDM 2V16'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'LUTON-SUTTON 2V19'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'STALBCY-SUTTON 2V27'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'LUTON-SUTTON 2V31'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'ORPNGTN-STALBCY 2D93'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'ORPNGTN-LUTON 2D95'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'SVNOAKS-STALBCY 2E59'	650.48	0.67	8.13	45.53	53.66	0.56	0.5	0.28
Rail	West Hampstead	'SVNOAKS-LUTON 2E61'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'SVNOAKS-WHMPSTM 2E63'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15
Rail	West Hampstead	'BROMLYS-LUTON 2E93'	650.48	0.33	8.13	91.66	99.79	0.3	0.5	0.15

Total Grid Cell AI: 21.67