

Statement of Intent for

# KITCHEN VENTILATION SYSTEM ODOUR MANAGEMENT PLAN

serving

Lore Of The Land,

The Fat Boy Pub Co., 4 Conway Street, London, W1T 6BB

PLANNING APPLICATION 2018/2004/P Pre-Commencement Condition No. 1

**Ref: B3349 rev 2** (04/01/19)

Building Management Technology Ltd Unit 2 Forest Business Park, Oswin Road, Leicester LE3 1HR

Tel: 0116 244 0331

Email: alan.logan@bmt-ltd.co.uk

DAILY CLEANING	
Kitchen Canopy 1	
Stainless Steel Kitchen extract canopy external surfaces open to the kitchen are to be kept clean by the onsite operator.	
Kitchen Extract Water Mist within Canopy 1	
Kitchen extract canopy has and integral water mist system providing a filter and spark arrestor. The site operator shall ensure the system is operational prior to lighting the wood burning appliance.	
Kitchen Canopy 2	
Stainless Steel Kitchen extract canopy external surfaces open to the kitchen are to be kept clean by the onsite operator.	
Kitchen Canopy 2 Primary Filters	
Kitchen canopy mounted primary baffle filters are to be cleaned daily by the onsite operator, using the onsite Dishwashing/Cleaning Facilities.	

WEEKLY CLEANING	
Kitchen Canopy 1 Primary Filters	
Kitchen canopy incorporates a solid filter with low level slot as part of the water mist canopy. The front panels are to be cleaned weekly by the onsite operator, using the onsite Dishwashing/Cleaning Facilities.  At the same time the internal elements including the water mist nozzles exposed by removal of the solid fiter are to be cleaned by the onsite operatives.	

kitchen canopy are to be cleaned by a specialist cleaning contractor with a minimum of three minor/ observational cleans one per quarter year. The ductwork has been installed with	Date Completed  Next Scheduled Date  Date Completed	
Kitchen extract ductwork, extract fan and internal surfaces of kitchen canopy are to be cleaned by a specialist cleaning contractor with a minimum of three minor/ observational cleans one per quarter year. The ductwork has been installed with accessible hatches along its route. with hatches in building fabric	Next Scheduled Date	
one per quarter year. The ductwork has been installed with accessible hatches along its route. with hatches in building fabric		
accessible hatches along its route. with hatches in building fabric	Date Completed	
void via a third floor ceiling hatch. It is anticipated the ductwork can be cleaned using conventional methods of scrape and clean,	Next Scheduled Date	
and all sections both internally and at roof void level, would be cleaned in this manner.	Date Completed	
Cleaned in this manner.	Next Scheduled Date	
Kitchen Extract Pre Filter Section from Canopy 1		
Kitchen extract filters that are installed in a filter housing located in the third floor roof void. The filters are accessed via a fabric access hatch in the ceiling above the third floor corridor and then the filter housing access door.	Date Completed	
	Next Scheduled Date	
	Date Completed	
The panel filters are a G4 Grade.	Next Scheduled Date	
The bag filters are sized 333 x 333 x 237 W	Date Completed	
The bag filters are a G7 Grade. There are 2No. bag filters in the housing.	Next Scheduled Date	
All the filters will be changed at the same time	Date Completed	
	Next Scheduled Date	
Kitchen Extract Carbon Filter Section from Canopy 1		
Kitchen extract filters that are installed in a filter housing located in the third floor roof void. The filters are accessed via a fabric access hatch in the ceiling above the third floor corridor and then the filter housing access door.	Date Completed	
	Next Scheduled Date	
The filters are sized 595 x 195 x 595 W providing a residency time of 0.12 seconds.	Date Completed	
There are 6 No. number filters in the housing All the filters will be changed at the same time.	Next Scheduled Date	
	Date Completed	
	Next Scheduled Date	
	Date Completed	
	Next Scheduled Date	

QUARTERLY PLANNED PREVENTATIVE MANTENANCE		
Kitchen Extract Ductwork from Canopy 2		
Kitchen extract ductwork, extract fan and internal surfaces of kitchen canopy are to be cleaned by a specialist cleaning	Date Completed	
contractor with a minimum of three minor/ observational cleans one per quarter year. The ductwork has been installed with accessible hatches along its route and externally. It is anticipated	Next Scheduled Date	
the ductwork can be cleaned using conventional methods of scrape and clean, and all sections both internally and externally, would be cleaned in this manner.	Date Completed	
	Next Scheduled Date	
	Date Completed	
	Next Scheduled Date	

ANNUAL PLANNED PREVENTATIVE MANTENA	NCE	
Kitchen Extract Ductwork from Canopy 1		
Kitchen extract ductwork, extract fan and internal surfaces of kitchen canopy are to be cleaned by a specialist cleaning contractor with a minimum of 1 annual full clean. The ductwork has been installed with accessible hatches along its route. It is anticipated the ductwork can be cleaned using conventional methods of scrape and clean, and all sections both internally and at roof void level, would be cleaned in this manner.	Date Completed	
	Next Scheduled Date	
Kitchen Supply to Canopy 1		
Kitchen supply system has a supply fan with inlet filter. The fresh air filter is to be changed once per year. The panel filter is 600 x 450 x 95 size The panel filter is a G4 Grade There is 1No. filters in the housing. All the filters will be changed at the same time	Date Completed	
	Next Scheduled Date	
Kitchen Extract Ductwork from Canopy 2		
Kitchen extract ductwork, extract fan and internal surfaces of kitchen canopy are to be cleaned by a specialist cleaning contractor with a minimum of 1 annual full clean. The ductwork has been installed with accessible hatches along its route and externally. It is anticipated the ductwork can be cleaned using conventional methods of scrape and clean, and all sections both internally and externally, would be cleaned in this manner.	Date Completed	
	Next Scheduled Date	