



- General Notes**
1. Drawings shall be referred to for structural work only unless otherwise stated and read in conjunction with Architect's, Service Engineer's and Sub-Contractor's drawings.
 2. The Contractor shall check all levels and dimensions, any errors or omissions are to be reported at once to the Engineer.
 3. Existing layouts and levels based upon Murphy's surveys information received to date (February 2016)
 4. For Key and Member Schedules refer to drawing no. 9100-DRG-99YY-GN010.
 5. For General Notes refer to drawing no. 9100-DRG-99YY-GN002.
 6. Indicates cast-in pipe 100Ø unless noted otherwise.

NOTE
FOR BUILDERSWORK HOLES ASSOCIATED WITH NEW SERVICES REFER TO M & E DRAWINGS.

NOTE
ALL SERVICES SIZES AND POSITIONS ARE TO BE CONFIRMED BY THE ARCHITECT/M&E CONSULTANT PRIOR TO CONSTRUCTION.

NOTE
INTERNAL FINISHED FLOOR LEVELS ARE TO BE LOWERED 100mm. IT IS NOT ENVISAGED UNDERPINNING WILL BE REQUIRED AS A RESULT OF THIS. INTERNAL TRIAL PITS ARE NECESSARY TO CONFIRM THIS.

NOTE
REFER TO DRG No. 9100-DRG-00KH-LG001 FOR GROUND FLOOR DETAILS.

NOTE
REFER TO DRG No. 9100-DRG-00YY-DE007 FOR GROUND BEARING SLAB REINFORCEMENT PRINCIPLES.

NOTE
REFER TO SOILTECHNICS GROUND INVESTIGATION REPORT FOR EXISTING TRIAL PIT RECORDS.

NOTE
WATERPROOFING AND GAS PROTECTION MEASURES TO DESIGN AND DETAIL BY OTHERS.

NOTE
EXTENT OF MAKING GOOD OF BRICKWORK TO FORM NEW OPENINGS INDICATIVE TBC ON SITE.

NOTE
NEW SERVICES TO CONSIDER ROUTE TO AVOID UNDERPINNING EXISTING FOOTINGS IN PERMANENT CONDITION AND DURING INSTALLATION.

REV	DATE	DESCRIPTION	BY	CHKD
C3	19.12.18	Stairs repositioned as clouded and partition wall removed	BL	DRS
C2	17.12.18	Swimming pool introduced & wall removed at LG & steel beam inserted. Opening infilled as clouded	BL	DS
C1	11.11.16	Updated to Architects new T2 layouts	HM	TP
E	09.09.16	Issued for Construction. SVP locations revised to A & G current T1 drawing. Note 6 added.	DA	TP
D	03.08.16	Generic repair & generic detail references added. Updated to Architects latest G.A's & co-ordination discussions.	DA	TP
C	14.07.16	Updated for Tender	DA	TP
B	15.06.16	Key and lintel schedules removed. General notes revised	DA	AT
A	28.04.16	Notes revised. Lintel and Beam schedules added. General notes key revised.	DA	TP
-	08.03.16	First Issue	DA	TP

FOR APPROVAL



TITLE:
Level LG Proposed Floor Plan

PROJECT:
**Project No. 11581
Kidderpore Avenue**

SCALE: A1@ 1:50 DATE: March '16 DRAWN: DA CHKD: TP

DRG NO. REV.
9100-DRG-03KH-LG001 C3

Tully De'Ath consultants
Engineering at its Best

T: 01342 828 000
E: info@tullydeath.com
W: www.tullydeath.com