



Legend Flow & return Heat interface unit Underfloor heating manifold Primary Heating pipework Secondary Heating pipework

Refrigerant Pipework

Pipework at high level

Pipework at low level Pipework within floor void

Thermostat / controller

Underfloor heating manifold

Electric underfloor heating

'Wet' underfloor heating

Timber joist direction

Pipework within ceiling void

Mechanical and Electrical drawings, Schedules and Specification. 2. Contractor to allow for on site co-ordination with the structure and other services and the production of fully

Notes

dimensioned working drawings prior to installation. 3. All equipment to be installed in accordance with the

1. This drawing shall be read in conjunction with all

manufacturers instructions. 4. All notched joists will be wrapped with hair felt lagging

and the top of the notch to be mechanically protected

6. Drain off's to be fitted at low points.

7. Air vents to be fitted on all high points.

5. All pipework penetrations to be sleeved.

8. Commissioning set to be fitted on the return from each underfloor heating manifold.

9. Primary Heating flow and return temperatures

71/31°C.

10. All Plant to be commissioned by manufacturer or

approved installer. 11. For futher pipework details & valve arrangements

12. All pipework penetrations through any structure to be sleeved with oversized tube of same material.

13. All radiators to be fitted with adjustable TRV's.

14. All pipework and valves to be insulated.

refer to schematic drawing.

15. Access panels to be installed by main contractor to allow access to all valves.

16. All steel pipework to be stainless steel grade 304.

17. All pipework to be earth bonded.

draining & venting.

18. All gaps between pipework & sleeves to be fitted with fire resistant sealant.

19. All pressure gauges to be connected by pigtails.

20. All temperature gauges to be installed in a stainless steel pocket with heat conducting compound.

21. All pipework to run to fall to from bends & vents to aid

22.Commissioning set to be fitted on the return from each manifold.

23. Screed underfloor heating flow and return temperatures 45/37.5°C. (Pumped manifold)


24. Joisted underfloor heating flow and return to be

55/47.5°C (Pumped manifold) 25.Radiator circuit flow and return temperatures 65/45°C

26.All equipment to be commissioned by manufacturer or approved installer.

27. Thermostat / controller to be mounted at 1200mm above FFL

Typical Radiator



15Ø HTG FROM BELOW SPLIT 15Ø TO ABOVE

FOR PLANNING



Integrated Mechanical, Electrical & Plumbing Services

Watkins House, Leigh Road Haine Business Park Ramsgate, Kent, CT12 5EU TEL: 01843 852 277

info@watkins.co.uk, watkins.co.uk

the express permission of C Watkins Plumbing Ltd.

WARNING

COPYRIGHT ©

RELATED DOCUMENTS This drawing should be read with the appropriate Specification (s) and Schedule (s) and all other standard documentation.

Do Not Scale from this drawing. Verify all dimensions, levels and structural details on site.

This drawing is copyright and may not be altered, reproduced, copied, lent borrowed or sold without

REFRIGERANT PIPEWORK RISE UP FROM FLOOR -

REVISIONS 13/12/18 pdated to Architects comments. Background updated. Issued for planning submission.

Mount Anvil 140 Aldersgate Street London

CLIENT

C Watkins

CONSULTING ENGINEER

Kidderpore Hall Kidderpore Avenue London NW3

CONTRACT

Level 01 Heating & Cooling Layout

DRAWING TITLE

DRAWN 29/10/18 SCALE CW 1:50 @ A1

6003-DRG-38KH-0101