

DRAINAGE AND PLUMBING: All new drainage to comply with \$\mathcal{LP}\$ 30 \ 1979, and new plumbing to comply with 8.5 5572 1978 and both to be agreed on site. New drains to be 102 mm (4") dia. Hepsleve flexibly jointed, vitreous, clay pipes in 150 mm (6") pea shingle surround, to fall minimum 1 in 40. Any existing drains underneath proposed extension, to be exposed and encased in 150 mm (6") concrete if not already so encased. Drains passing through foundations to have approved R.C. lintels over. Any new inspection chambers to be constructed in 225 mm (9") class 'B' semi engineering brickwork, with air tight covers. Any internal risspection chambers or guillies to have double seal, bolt down and tight covers with access provided in floor. Provide min. 450 mm concrete base to 1.C.

All new guillies to be back inlet type and be roddable. New waste pipes to be polypropathane or similar approved type and have rodding access provided at all bends (rodding eyes). All sanitary units to have min 75 mm (3") deep seal traps (not bottle traps). All wastes connected to a common S.V.P. to have anti-syphonage systems where necessary, to maintain traps under working conditions (single stack system). Sink and bath and shower wastes to be 38 mm (1\frac{1}{2}") dia. and hand basins 32 mm (1\frac{1}{2}") dia. unless specified otherwise on plan. Soil and vent pipes to be 100 mm (4") dia. and where passing through any roof to have adequate Code 4 lead flashing around. Provide wire balloon to vent min. 1 metre (3" 3") above top of highest window. All plumbing air tested on completion. New guttering to be 100 mm (4") H.R. type discharging via 63 mm (2\frac{1}{2}") dia. R.W.P. to surface water drainage system.

All wastes discharging to existing guillies, to do so below grating level and above water level. FOUNDATIONS: Unless shown otherwise on plan. Trench-fill foundations to within 200 mm (8")

10年本种工具

FOUNDATIONS: Unless shown otherwise on plan, Trench-fill foundations to within 200 mm (8") of ground level, min 450 mm (18") wide x 1.1 metre (3' 6") deep. Where any tree roots present, continue foundations down to 1 metre (3' 3") below the roots visible or to L.A. approval. All foundations to be continued down to below the invert of any adjacent drains, to Reg. N 14(2). Use 1:2:4 mix using sulphate resisting cement.

BRICKING UP: Existing openings, provide new foundations as above where none presently existing, or provide approved R.C. lintels under new d.p.c., to be lapped to existing, and brickwork to be bonded to existing. Use sulphate resisting cement.

DAMP PROOF COURSE: Use approved lead lined or P.V.C. Type to B.S. 743, min 150 mm (6") above adjacent ground level and lapped to existing d.p.c. Use sulphate resisting cement on all works below d.p.c. level.

HALF HOUR FIRE RESISTANT: 75 mm x 50 mm (3" x 2") stud partitions with noggins and 75 mm x 50 mm sole and head plates, faced both sides 13 mm ($\frac{1}{2}$ ") plasterboard.

ONE HOUR FIRE RESISTANT: Use 13 mm (‡") plasterboard and 9.5 mm (‡") vermiculite/gypsu-plaster on both sides, or 19 mm plasterboard on both sides. Double-up floor joists under all new partitions, where parallel to partitions.

HALF HOUR FIRE RESISTANT: To existing fleors consisting of lathe and plaster on 7" x 2" joiste with close boarding over, overlay and fix down 5 mm (\frac{1}{2}") dense hardboard to provide full \frac{1}{2} hour

ONE HOUR FIRE RESISTANT: As half hour fire resistant floor above, but provide additional 9.5 mm (§") plaster to provide full 1 hour fire resistance, where existing lathe and plaster ceiling sound. If ceiling to be renewed then overlay flooring as described above and provide new 9.5 mm (§") plasterboard with 12.5 mm

ONE HOUR FIRE RESISTANT: Underline all stairs with 12.5 mm (‡") Asbestolux based sheeting

STRUCTURAL STEELWORK & TIMBER: All twin universal beams (R.S.Js.) to be boiled together with M.S. separator (a. \frac{1}{2} spaces. All structural members, both steelwork and S.W. beams/trimmers to be encased in 9.5 mm (\frac{2}{3}) plasterboard and 9.5 mm vermiculite/gypsum plaster to provide minimum of \frac{1}{2} hour fire resistance. Use 1.6 mm binding wire at 100 mm crs. All structural timbers to be stress graded to 8.S. 4973. Where steel beams are exposed to external weathering encase beams in concrete with min 75 mm (\frac{3}{3}) cover all round. (Use 0.49 wrapping fabric on steelwork.)

VENTILATION: All rooms to have a minimum of 1/20th of floor area in opening lights. Any internal bathrooms and w.c.s to have mechanical ventilation, ducted to outside, providing min 3 volume changes per hour and 20 minute over run – operated by light switch. — Additional openable vent equal in area to 10,000 mm² (16 in²) where ventilation is by external

Any pipes passing through compartment walls/floors, to be encased 9.5 mm (**) plasterboard and 9.5 mm vermiculite/gypsum plaster to provide min \(\frac{1}{2} \) hour fire resistance, all to Reg. E.12.

Provide meter cupboard in common hallway, to be min. I hour fire resistant. + kept locked

Provide 3 kW electric immersion heaters for H.W. supply to kitchen and bathroom(s)

ELECTRICAL WORKS: To be in accordance with I.E.E. Regulations and position of socket outlets and lighting points to be agreed with owners.


EXTERNAL WOODWORK: Knot, prime and stop, paint with 1 undercoat and 2 coats gloss finish.

denotes stud partitions as NOTES - zhv. f.v., except stud partitions

Double up joists wider partitions where parallel.

The Contractors are to check all dimensions, levels, drain runs and conditions on site before works commence. The Chartered Surveyors, Stuart Henley & Partners to be notified immediately upon discovery of any enough omissions or discrepancies. Figured dimensions to be used in preference to

The contents of this plan including the printed notes are COPYRIGHT and reproduction in whole or part is not permitted without the prior consent in writing of Stuart Henley & Partners.



COMVERSION TO THREE S/CONTAINED

42 ENGLANDS LAHE LONDON YW3

REV. DRG. No. 390/3. DATE Sep 83

