

Monarch House 1-7 Smyth Road Bedminster Bristol BS3 2BX

Southwest: 0117 244 0012 Southeast: 0207 871 3003 Midlands: 0121 647 7021

info@treeworks.co.uk www.treeworks.co.uk

Graeme Shimmin
Green Space Project Officer
Graeme.Shimmin@camden.gov.uk

26<sup>th</sup> October 2018

Dear Graeme,

### College Gardens, London, NW1 9NB

Further to our recent instruction of October 23<sup>rd</sup>, we carried out a tree survey at College Gardens on October 25<sup>th</sup>. The survey was carried out in accordance with BS5837:2012 Trees in Relation to Design, Demolition and Construction – Recommendations.

The results of the survey, provided in the attached documents are intended to provide the design team with sufficient information to make balanced judgements and informed decisions about conflicts between the proposed design and the above and below tree constraints on site including those outside of the site boundary (where applicable) which may extend into the site above or below ground. This process ensures that the sustainability of the resulting landscape, in relation to existing trees, has been properly considered.

The following information and attached tree schedules and plans, have been undertaken with no reference to previous surveys and have been intended to record as much detail as possible in regard to the tree features recorded.

The following documents are attached:

- 1. Tree Schedule (181026-1-CGL-TS-MW)
- 2. Tree Constraints Plan (181026-1.0-CGL-TCP-MM, in .dwg and .pdf)
- 3. Decision process in relation to design near to trees (TEP-Designing Near Trees-Decision Flowchart.pdf)

Above-ground constraints consist of tree stems and canopies, for which a range of measurements are provided to aid any proposed design. Canopies are shown on the TCP as green outlines. The below-ground constraints are tree roots, shown on the Tree Constraints Plan (TCP) as Root Protection Areas (RPAs). RPAs are a layout design tool, indicating the minimum area around a tree deemed to contain sufficient roots and soil volume to maintain the tree's viability. RPAs should be treated as a precautionary area within which activities such as ground compaction, excavation, storing of

#### Services

**Design Planning and Construction** 

Tree Risk Surveys and Management

Comprehensive Tree Management

Veteran Tree Surveys/Management

**Expert Witness** 

**TPO Advice** 

Static Load Test

Tree Work Contract Administration

MyTrees Tree Management Software

Tree Planting Plans

**Tree Planting Audits** 

Tree Health Assessments

Tree Policies and Strategies

Home-buyers Reports

Structural Damage Reports

Soil Health Assessments

Grounds Maintenance Mapping

### **Registered Office**

Monarch House 1-7 Smyth Road Bedminster Bristol BS3 2BX

Registered in England No 1621606



materials, ground stripping, raising of levels and building are likely to cause damage to trees and should therefore be avoided.

Please note that the Phase 1 information provided above is <u>not</u> normally sufficient to accompany and validate a planning application. Normally an Arboricultural Impact Assessment and Tree Protection Plan (Phase 2, RIBA Stages 3-4) are required. These documents will need to reference the emerging design and the juxtaposition of trees, and can be provided once the design has been finalised prior to submission of a planning application.

### **Summary of Phase 1 Material Tree Constraints**

14 individual trees have been assessed during the survey that are located within the site boundary or located outside of the site boundary, but are close enough to potentially influence or be influenced by the proposal.

These trees, tree groups and hedges have been assigned the following quality and value categories, according to the BS5837 categorisation process:

- 1 tree (T9) has been assessed as **Category A** 'trees of high quality'.
- 10 (T2-T4, T6, T7, T10-T14) trees have been assessed as **Category B** 'trees of moderate quality', and as such are likely to be considered by the local planning authority as posing a significant material constraint.
- 3 (T1, T5 and T8) trees have been assessed as **Category C** 'trees of low quality', and whilst still a 'material consideration' are likely to be considered by the local planning authority as posing a minimal constraint.
- None of the trees have been assessed as Category U 'those in such a condition that they
  cannot realistically be retained' regardless of land use and as such pose no constraint on
  development.

RPAs, shown as red circles around each tree on the Tree Constraints Plan are a layout design tool, indicating the minimum area around a tree deemed to contain sufficient roots and soil volume to maintain the tree's viability. Where the surveyor has assessed that tree roots are likely to have grown in a non-uniform pattern, for example, where roots have been obstructed by underground structures, topography, drainage or soil type and structure, the RPA has been modified. This modification is delineated on the Tree Constraints Plan and noted in the Tree Schedule.

It should be noted that this survey is not a tree safety inspection. It is carried out in order to inform the planning process. Where clear and obvious hazards have been observed, these have been addressed in the preliminary recommendations in the attached Tree Schedule.

We have made enquires with Camden London Borough Council Tree Officers regarding Tree Preservation Orders (TPO) and Conservation Areas (CA) at the site. Nick bell, Tree and Landscape Officer has confirmed that none of the trees are covered by a TPO; however, they are considered to be of sufficient value. The site is within Jeffery's Street Conservation Area which affords the same protection.



#### **General Advice**

Retained trees are an important factor on development sites and indeed a material consideration in the UK planning system. Treework Environmental Practice will support you to best achieve your objectives including delivering a sustainable outcome. Part of this includes the avoidance of unnecessary tree damage. If trees are damaged by the works on the site (e.g., demolition, construction, landscaping), they may decline, die or become unstable.

The attached **Decision Process for Tree Retention Removal and Protection** document provides broad information on how trees can be damaged and what measures can be taken to protect them.

Where trees are retained, or new planting proposed, the objective should also be to achieve a harmonious relationship between trees and structures that can be sustained in the long term. When this relationship is not achieved (e.g., excessive shade and low hanging limbs), conflict can occur that can lead to post completion pressure to remove trees.

Planning officers will normally require a clear rationale for the removal, retention and protection of trees that meets the requirements of national and local policy. Treework Environmental Practice will support this by providing an Arboricultural Impact Assessment report and Tree Protection Plan for submission with the planning application.

If you require clarification or further information at this stage, please do contact me.

Yours sincerely,

### Mike Wood

Senior Arboricultural Consultant M. 07966 648 482 E. mike@treeworks.co.uk

## College Gardens, London, NW1 9NB Tree Survey BS5837-2012



Tree/Group Reference	Tree Count	Species	Height (m)	Stem Count	Stem Diameter (cm)	Crown R	adius	(m)	Crown Clearance Height (m)	Lowest Branch Height (m)	Life Stage	Physiological Condition	Observations and Recommendations	RPA (m²)	RPR (m)	Remaining Contribution (Years)	Retention Category	Retention Sub-category
T1	1	Tilia x vulgaris Common Lime	8.0	1	21	N E 1.0 1.0	S 1.0	W 1.0	2.0	2.0	Semi Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut.	20.0	2.5	40+	С	1
T2	1	Tilia x vulgaris Common Lime	11.0	1	55	N E 2.0 2.0	S 2.5	W 2.0	2.0	5.0	Early Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut. Raised surface roots.	136.8	6.6	40+	В	1
Т3	1	Tilia x vulgaris Common Lime	10.0	1	32	N E 1.5 1.5	S 1.5	W 1.5	2.0	6.0	Early Mature	Good	Altered ground level - Suspected. Bark wound - Major. Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut.	46.3	3.8	40+	В	1
T4	1	Tilia x vulgaris Common Lime	10.0	1	46	N E 2.0 2.0	S 2.0	W 1.5	2.0	6.0	Early Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut. Structural impact - Footpath / highway / drive disturbance.	95.7	5.5	40+	В	1
T5	1	Tilia sp. Lime sp.	10.0	1	37	NW NE 2.0 2.0	SE 2.5	SW 1.0	2.5	3.0	Early Mature	Fair	Bark wound - Major. Decay / structural defect in crown limb / limbs - Localised. Decay / structural defect - Localised. Epicormic growth - Base. Epicormic growth - Crown. Pollard - Recently cut. Appears to be lower vitality than adjacent limes with less epicormic growth.	61.9	4.4	10-20	С	1
Т6	1	Tilia x vulgaris Common Lime	10.0	1	51	N E 2.0 2.0	S 1.5	W 2.0	2.0	6.0	Early Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut.	117.7	6.1	40+	В	1
T7	1	Tilia x vulgaris Common Lime	10.0	1	38	N E 2.0 1.5	S 1.5	W 1.5	2.0	6.5	Early Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut.	65.3	4.6	40+	В	1

## College Gardens, London, NW1 9NB Tree Survey BS5837-2012



Tree/Group Reference	Tree Count	Species	Height (m)	Stem Count	Stem Diameter (cm)	Crown Radius (m)	Crown Clearance Height (m)	Lowest Branch Height (m)	Life Stage	Physiological Condition	Observations and Recommendations	RPA (m²)	RPR (m)	Remaining Contribution (Years)	Retention Category	Retention Sub-category
Т8	1	Tilia x vulgaris Common Lime	8.0	1	28	N E S W 1.0 1.0 1.0 1.0	2.0	6.5	Semi Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut.	35.5	3.4	40+	С	1
Т9	1	Platanus x hispanica London Plane	25.0	1	118	N E S W 13.0 10.0 12.0 12.5	3.5	9.0	Mature	Good	Arboricultural work - Historic. Epicormic growth - Base.	629.9	14.2	40+	А	1
T10	1	Tilia x vulgaris Common Lime	10.0	1	51	N E S W 2.0 2.0 2.0 2.0	2.0	3.5	Early Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut. Raised surface roots.	117.7	6.1	40+	В	1
T11	1	Tilia x vulgaris Common Lime	10.0	1	49	N E S W 2.0 2.0 2.0 2.0	2.0	6.0	Early Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut.	108.6	5.9	40+	В	1
T12	1	Tilia x vulgaris Common Lime	10.0	1	51	N E S W 2.0 2.0 2.0 2.0	2.0	2.5	Early Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut.	117.7	6.1	40+	В	1
T13	1	Tilia x vulgaris Common Lime	10.0	1	47	N E S W 1.5 1.5 1.0 2.5	2.0	3.0	Early Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut.	99.9	5.6	40+	В	1
T14	1	Tilia x vulgaris Common Lime	10.0	1	47	N E S W 3.0 1.5 2.0 2.0	2.0	4.5	Early Mature	Good	Epicormic growth - Crown. Epicormic growth - Base / bole / principal stems. Pollard - Recently cut. Structural impact - Footpath / highway / drive disturbance.	99.9	5.6	40+	В	1

### Tree Schedule Key



Tree/Group Reference Reference number for individual trees or groups of trees, prefixed by T (Tree), G (Group), W (Woodland), H (Hedge) or S (Shrub) to indicate the type of feature.

Tree Count Number of trees of a particular species recorded within a group feature, with the default value of 1 for single trees.

Species Scientific name followed by common name (where available).

Height (m)

Tree height to the nearest metre, either measured with a device or estimated. Tree height for group records refers to the estimated average height of trees within the group

(unrepresentative trees may be excluded from this estimate).

Stem Count Number of stems. Stem count indicates whether the tree is single-stemmed or multi-stemmed and informs the RPA calculation.

Stem Diameter (cm) Stem diameter, measured at 1.5m above ground level in accordance with Annex C of BS5837:2012. Diameters of multi-stemmed trees are presented as a combined stem diameter

calculated in accordance with the formulae in Section 4.6.1 of BS5837:2012. Stem diameter for group records refers to the estimated average stem diameter of trees within the group

(unrepresentative trees may be excluded from this estimate).

Crown Radius (m) Distance from stem position to crown periphery in either the four cardinal or four ordinal directions, estimated to the nearest half metre. Crown spreads for group records refer to the

estimated average spreads of trees within the group (unrepresentative trees may be excluded from this estimate).

Crown Clearance Height (m) Distance between the ground and the lowest point of the crown periphery, estimated to the nearest half metre.

Lowest Branch Height (m) Height of the lowest branch, the removal of which is considered likely to have a significant negative effect on the tree in terms of physiology or in terms of the size of wound created.

Life Stage Young, Semi-mature, Early Mature, Mature, Late Mature, Ancient or Veteran.

Physiological Condition Good, Fair, Poor, Dead.

Observations General description of the tree or tree group, including basic features and morphology, structural and physiological condition, growing conditions and surroundings.

Recommendations Management recommendations for tree works to address immediate unacceptable risks, or to facilitate development proposals.

RPA (m²) Minimum area around a tree deemed to contain sufficient roots and rooting soil volume to maintain the tree's viability, in which the protection of roots and soil structure is treated as a

priority. Calculated from the stem diameter according to the formulae in BS5837:2012. RPA for group records is based on the estimated average stem diameter of trees within the

group (unrepresentative trees may be excluded from this estimate).

RPR (m) Radius of the RPA, in metres, when this is plotted as a circle around the tree stem.

Remaining Contribution (years) Estimated number of years for which the tree will continue to make a positive contribution to the site, banded as < 10, 10-20, 20-40, 40 +.


Retention Category Quality and value category (A, B, C or U) as defined in Table 1 of BS5837: 2012 (reproduced below), where A = high quality and value; B = moderate quality and value; C = low


quality and value and U = tree identified for removal due to poor condition regardless of development proposals.

Retention Sub-category One or more sub-categories (1-3) as defined in Table 1 of BS5837: 2012 (reproduced below), assigned for Categories A. B or C where 1 = arboricultural gualities, 2 = landscape

qualities and 3 = conservation and cultural value.









Treework Environmental Practice Monarch House 1-7 Smyth Road Bedminster Bristol

Tel: 0117 244 0012 Web: www.treeworks.co.uk BS3 2BX Email: info@treeworks.co.uk

# Decision Process for Tree Retention, Removal & Protection



### Tree Constraints Plan **Design or Required Construction Area Design & Required Construction Area is Breaches Root Protection Area Outside Root Protection Area** Can design be revised out-**Retain Tree** side of the RPA? • Erect appropriately specified tree protection fencing **Retain Tree** Fell Tree • This is a strategic decision depending on the value of the tree (Category A-• BS5837:2012 warns against inappropriate retention of trees in current or future conflict with proposed buildings. • Further methodology to assess likely root damage and to mitigate for this If approved, felled trees are likely to require replacements. will be assessed and provided by an Arboricultural Consultant. **Roots Not Expected To Be Present** Roots Expected To Be Present **Assess Actual Extent & Location of Roots Demonstrate No Roots Present** • Excavate by hand / use Airknife to remove soil in selected locations Method Statement to investigate whether roots are present provided by an (e.g.: in the location of a proposed retaining wall). Arboricultural Consultant. • This methodology will normally be subject to approval by the LPA Tree • Map location of roots with a Radar. • Remove apparent obstructions to roots (e.g.: curb stones) to assess whether roots pass under them. Roots Found To Be Present Roots Not Found To Be Present Can design be revised outside of the RPA? Manage Extent of Root Damage Minimise or Prevent Root Damage RPA Breach Assessed to be Insignificant Special engineering Pile and beam or radial strip foundations. Where a breach of a RPA is minor (e.g. 1-2m) and within a large RPA, no special measures are required. Bridge across area of RPA. Low compaction / permeable surfacing. Measures to ensure that raised ground level doesn't reduce roots' access Hand Dig and Move or Sever Roots to water and gaseous exchange. Provision within design should be made to allow access for water to root

A methodology may be considered whereby roots are exposed by hand

(air-spade or similar), moved into the proposed Construction Exclusion Zone or severed by an Arboricultural Consultant, in accordance with an appropriate and approved Method Statement.