

amendments

A Forum updated. Tree T9 omitted & public realm planting added 09.04.18 JP

B. Below ground drainage and lighting added 19.4.18 SN

C. Areas of public realm added 4.5.18 SN

D. Public Realm temporary works shown. DSDHA dwg no. 146-500-22RevD school proposal updated to reflect client comments. 4.7.18 JP

E. Public realm drainage references added. Spec references and temporary levels noted. 22.10.18 JP

F. Levels at main entrance amended. 07.02.19 JP

Note:
Please refer to drawing no:
3597-C-110 & 3597-C-111
for Indicative SUDS Plan in
the public realm.

Drainage Services Legend:

- Private Manhole 1050 dia
- Inspection chamber 450dia/600dia
- Floor Gully

External Lighting Legend:

- Column Luminaire (Singular & Twin)
- Pendant Luminaires
- Linear Luminaire
- Wall-mounted Luminaire

Note: Please read this drawing in reference with
'Below ground drainage layout'
drawing no. 668831-MLM-04-XX-DR-C-0100
and 'External lighting layout', drawing no.
V(41)001/B

drawing status: Information

project:
Central Somers Town
Plot 4 Edith Neville Primary School

job number:
LP2119
drawing title:
Landscape General Arrangement

drawing number:
5859-LP2119-FIR-PT4-MP-0001

revision	scale	date
F	1:200@A1	25.01.2108
for information	drawn GL	auth JP
for construction		date 25.01.18

- Limit of Plot 4 Works
- Self Binding Gravel Q23/110
- Buff Coloured Macadam Q22/175
- Bark Chipping Safety Surface Q26/310
- Porous Black Macadam Q22/180
- Line Markings Q10/395
- Composite Decking Q55/110
- Artificial Grass Q26/350
- C Insitu Concrete Q21/120
- Concrete Slab Paving Q25/315
- Rubber Crumb Safety Surface Q26/360
- Circular Concrete Stepping-stones Q25/335
- External Mat Wells. Q26/365
- Ground level planting bed. Kerb Q10/110
- Raised Planter Block F10/225
- Linear Drain Q10/180
- Sport Fence Q40/140
- Stainless steel cables (Q40/355)
- Steel Colonnade (Q40/350)
- Webnet Mesh Fence (Q40/125)
- Brick Paving Q25/140
- New Trees (See separate schedule)
- Existing Trees (to be retained)
- Proposed levels
- 450mm Topsoil for Shrub Planting Q28/325
- Timber Posts (Q50/550)
- Tree Climbing Frame Q52/360
- Timber Sleeper Structure Q40/330
- Tactile Paving Q25/310
- Wattle Hurdle Fence Q40/328
- Amenity Grassworks in Public Realm (Q30)
- H2 Concrete Thresholds (Set to finished levels). Macadam will be ramped locally along edging line for DDA compliant access. Concrete finish: Back of broom drawn over towelled concrete with bullnose edging.
- Proposed Tree (Public Realm)
- T1 (Porous) To base course only (25mm Below Final FL) for Bound Gravel Park Path by other. (Q22/175).
- T2 Temporary Soft Surface (DSDHA specification)
- T3 Temporary Hard Surface (DSDHA specification)
- Public Realm Lights
- Temporary Edge Treatment
- Camden Highway Dept

