



General Notes

20 x 320wp LG
Monocrystalline
6.4Kwp
PV array installed on
aluminum aframe and
held in position with
ballast.
total weight 1396Kg
PV Array 34.26m²
at 40.75Kg/M²

PV inverter & distribution
board installed in top
floor electrical riser
cupboard

see backboard drawing
DC cable will require 50
mm hockey stick hole
through roofing area
below top floor electrical
riser cupboard and
weathered by main
roofing contractor

Drawing Title
PV Roofing Layout

Issue No	Drawing By	Checked By	Date
1	Paul O'Mara		07/02/19
No.	Revision/Issue		Date



Project Name and Address
Client: Ambassador Group
Project: 16 Rochester Mews

Drawing No
PV2502/3-RD
Date
12/01/18
Scale
NTS

Sheet
1