



Notes
Do not scale from this drawing.
All dimensions are drawn in millimetres.
Drawing & design copyright LUC.
Reproduction of this drawing in whole or in part is prohibited without prior permission.

Key

- Site Boundary
- Existing trees
- Proposed Trees
- Existing planting
- Proposed planting
- Play Fall Zones
- S01 - Tigermulch
- S02 - Textured Concrete
- S03 - Play Sand
- S04 - Timber Decking
- S05 - Stone Setts
- S06 - Permeable Resin Bound Gravel
- S07 - Non-permeable Resin Bound Gravel
- S08 - Play Bark
- S09 - Matta Safety Surface
- E01 - Timber Edging
- E02a - Granite Sett Edging
- E02b - Granite Sett Edging
- E03 - Timber Wall to sand pit
- E04 - Metal Edging
- F01 - Timber Bench Seating
- F02 - Gabion Seating
- F03 - Timber Seating Cubes
- F04 - Picnic Bench
- F05 - Sky Seats
- F06 - Play boulders, cobbles and pebbles
- G01 - Revetment Gabion Walls
- BR1 - Bridge to Waterplay area
- BT01 - Post & Strained Wire Fence
- BT02 - Salvaged Railing
- BT03 - Self-Closing Gate
- BT04 - Salvaged Double Leaf Maintenance Gate
- W02 - Low willow fence to planting

Bespoke Play Equipment

- P01 - Timber Logs with Nets and Traverse Ropes
- P02 - Timber Log Steps
- P03 - Timber Sleeping Stumps
- P04 - Climbing ropes
- P05 - Timber trunk steps
- P06 - The Revetment - Bridge/Earthwork Structure
- P07 - Timber stepping stones
- P08 - Timber standing posts
- W01 - Willow Den
- W02 - Low Willow Fence
- W03 - Willow Tunnel

Catalogue Play Equipment

- C01 - Large Gated Cableway
- C02 - Oro Oak
- C03 - Inclusive Roundabout
- C04 - Quad Swing
- C05 - Cradle Nest Swing
- C06 - Tunnel Slide
- C07 - Wide Slide
- C08 - See-Saw

Catalogue Water Play Equipment

- D01 - Playground Pump
- D02 - Channel With Two Way Seal
- D03 - Channel with Wedge Seal
- D04 - Triangular Channel
- D05 - Mill Wheel of Wood
- D06 - Multisport Spring
- D07 - Triangular Channel
- D08 - Big Bucket Wheel
- D09 - Rectangular Flap
- D10 - Bar Gate
- D11 - Rotating Gate

Sheet Notes:

Please read the adjacent plan in conjunction with the below:
10335-LD-PLN-015 Tree Protection and Removal Plan
10335-LD-PLN-120 Demolition Plan
10335-LD-PLN-221-223 : Detail Plans

- Making Good:** the contractor is to make allowance to ensure all edges and joints with adjacent surfaces are made good, married into to existing levels, and with the appropriate surface/edging material, (e.g. timber edging to marry into existing edge type).
- General Items:** Please refer to ALL necessary landscape construction details as indicated and required. Where not referenced, the contractor is responsible for the identification of relevant details (and specification clauses) to ALL work items across the site, and/or to notify the CA prior to commencement on-site.

Relocation/new proposed setting out: ALL setting out is the responsibility of the contractor and is to be marked out on-site for sign off by the CA prior to commencement of works, unless stated otherwise. Allowance is to be made for ALL relocated items to have new footings/surface pads (if required), installation under CA direction.

Contractor is responsible for ALL necessary protection of existing trees and vegetation to be retained, (in line with BS: 5837 2012).

All construction works are to be carried out in accordance with the latest statutory guidance, building regulations and national building specification standards.

Contractor is to follow standard practices and provide method/access statements for the excavation of all watercourse items in accordance with the Engineers' drawings and details.

The contractor is to make allowance for appropriate surveying (e.g. CAT scan etc.) to areas where break out is required - in accordance with HSE regulations. Where existing services are discovered and not previously surveyed, the contractor is to down tools and notify the client and CA for further instruction.

- Ecology:** ALL relevant ecological protection laws are to be observed (e.g. bird nesting season), and recommendations noted in 10335-LD-REP-602 (Ecological Appraisal, July 2018).

Hedgehogs: Special notice is to be given to existing Hedgehog population, and the contractor is to undertake ALL actions stated in support document: 10335-LD-REP-603 (Hedgehog Guidance Note, Feb 2019). The contractor is to liaise with The Royal Parks ecology team to ensure protection and safe passage of Hedgehog movement around (not through) the site.

Rev	Date	Description	Drn	CHK
T2	15.03.19	Revised tender issue	JL	AM
T1	18.02.19	Final issue	JL	AM

0 2 4 6m

LUC LUC London
43 Chalton Street, London, NW1 1JD
+44 (0)20 7383 5784
london@lucanduse.co.uk
www.lucanduse.co.uk

Project
Gloucester Gate Playground
The Regent's Park

Client
The Royal Parks

Scale @A1
1:100

Status
TENDER

Drawing Title
Detail Area:
Hard Landscape - Sheet 3 of 3

Job Nr
10335

Drawing Nr
10335-LD-PLN-223

Issue
T2

REFER TO 10335-LD-PLN-223 FOR FURTHER DETAIL