



REFER TO THE PHASE 1A DRAWINGS FOR CONTINUITY OF THE PAVEMENT WORKS

REFER TO PBA DRAWING NO T14011-PBA-DR-C-1B-FGH-00-PA-003 FOR THE PROPOSED PAVING WORKS WITHIN ADOPTED HIGHWAY

REFER TO THE LANDSCAPE ARCHITECT DRAWINGS FOR THE SPECIFICATION OF THE SOFT AND HARD LANDSCAPING MATERIALS AND FOR THE PATTERN AND ORIENTATION OF THE PAVING

REFER TO PBA DRAWING NO. T14011-PBA-DR-C-1B-FGH-00-GA-060 T14011-PBA-DR-C-1B-FGH-00-GA-061 T14011-PBA-DR-C-1B-FGH-00-GA-062 T14011-PBA-DR-C-1B-FGH-00-SD-064 T14011-PBA-DR-C-1B-FGH-00-SD-065 T14011-PBA-DR-C-1B-FGH-00-SD-066 FOR LAYOUT AND CONSTRUCTION DETAILS OF THE TEMPORARY TURNING HEADS NW AND SW OF LULWORTH BLOCK AND EAST OF WROTHAM ROAD

SITE CBR TEST LOCATIONS			
CBR REFERENCE	EASTING	NORTHING	
CBR01	52942.213	184245.913	
CBR02	529516.994	184270.811	
CBR03	529528.798	184262.496	
CBR04	529594.108	184238.513	
CBR05	529507.747	184205.592	
CBR06	529474.214	184198.097	
CBR07	529477.142	184238.086	

- NOTES
1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT DESIGN DRAWINGS, SPECIFICATIONS AND DOCUMENTATION.
  2. CONSTRUCTION TO BE IN ACCORDANCE WITH ALL BRITISH AND EUROPEAN STANDARDS, BIDDING REGULATIONS AND SPECIFICATION FOR HIGHWAY WORKS.
  3. ALL DIMENSIONS ARE IN MILLIMETRES AND LEVELS IN METRES ABOVE LOCAL DATUM, UNLESS NOTED OTHERWISE.
  4. ECO TRENCH PROFILES: THE CONTRACTOR SHALL HAVE ALLOWANCE TO UNDERPINE EQUAL GRAIN AND SITE CBR TESTS (INSERTION OF 50MM PLYMER AT EACH OF THE LOCATIONS SHOWN IN THIS DRAWING, AT THE FORMATION LEVEL, THE CBR TESTS SHALL BE CARRIED OUT, RECORDED AND PRESENTED IN LINE WITH ITEM ADVISE NOTE 7006 (REV. 01 - 2009) AND BS 1377 PART 9 AND IN THE FOLLOWING ORDER:
    5. THE CONTRACTOR WILL BE RESPONSIBLE FOR LOCATING ALL EXISTING SERVICES WITHIN THE PROPOSED CONSTRUCTION AREAS AND FOR MARKING THEM PRIOR TO COMMENCEMENT OF THE WORKS.
    6. THE CONTRACTOR MUST ENSURE ALL WORKING AREAS ARE FULLY SECURE, ENCLOSED OR WHEN LEFT UNATTENDED, OPEN EXCAVATIONS MUST NOT BE LEFT UNGUARDED OR UNATTENDED WITHOUT SURFACE PROTECTION.

**LEGEND**

- SITE BOUNDARY (EXTENT TO BE CONFIRMED BY HPJ)
- NS1 - SETT PAVING
- NS1/F - 300 x 200 MARSHALLS GRANITESTONE KERB FLUSH
- NS3 - 300 x 200 MARSHALLS GRANITESTONE KERB WITH 100mm UPSHAND
- NS3-G - 300 x 200 MARSHALLS GRANITESTONE KERB WITH 100mm UPSHAND AND 25mm GAP BETWEEN UNITS
- OK1 - 255 x 125 CHARCON ECO KERB FLUSH
- PK3 - 150 x 50 CHARCON ECO KERB EDGING FLUSH
- SC - STRETCHER COURSE RESTRAINT LAID FLUSH
- C1 - SACRIFICIAL 125 x 255 x 94mm FLAT TOP ECO CHANNEL KERB
- PLANTER WALL WITH MANUAL STONE COPING
- MASONRY WALL TO ARCHITECT'S DETAILS
- SEATING TO LANDSCAPE ARCHITECT'S DETAILS
- REMAINING CONCRETE WALL
- DROP KERB TO MATCH THAT ADJACENT
- GABION WALL/RETAIN TO SWALE
- STANDARD CONCRETE BLOCK PAVING (80mm THICK) WITH ASPHALT BASE COURSE 90 DEG. HERRINGBONE PATTERN
- PERMEABLE CONCRETE BLOCK PAVING (80mm THICK), STRETCHER COURSE PATTERN
- STANDARD CONCRETE BLOCK PAVING (80mm THICK), STRETCHER COURSE PATTERN
- PROPRIETARY POROUS EDPM RUBBER GRUMB PLAY SURFACING
- POROUS MACDAM SURFACING TO MUGA
- SOFT LANDSCAPE BY OTHERS
- TIMBER DECKING NEXT TO MUGA BY OTHERS
- TEMPORARY ASPHALT SURFACE
- PROPOSED CERAMIC TILES TO ARCHITECT'S DETAILS
- PROPOSED CBR TEST LOCATION (REFER TO NOTE A1 TO G1)
- EXTENT OF THE ROOT PROTECTION ZONES AFTER THE REMOVAL OF THE EXISTING TREE ROOTS AS SHOWN IN HANOVERS ARBORICULTURAL REPORT AND DRAWINGS

Mark/ Revision

Mark	Revision	Date	Drawn	Chkd	Appd
C3	R02 ADDED CONSTRUCTION ISSUE	04.05.18	IK	BH	PPS
C2	PRE CONSTRUCTION ISSUE	19.01.18	IK	ET	PPS
C1	DRAFT CONSTRUCTION ISSUE	14.07.17	IK	ET	PPS
-	DRAFT ISSUE	31.03.17	OO	IK	PPS

SCALING NOTE: DO NOT SCALE FROM THIS DRAWING. IF IN DOUBT, ASK UTILITIES NOTE: THE POSITION OF ANY EXISTING PUBLIC OR PRIVATE SEWER, UTILITY SERVICES, PLANT OR EQUIPMENT SHOWN ON THIS DRAWING IS FOR INFORMATION ONLY. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF ALL SERVICES PRIOR TO COMMENCEMENT OF THE WORKS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING SERVICES, PLANT OR EQUIPMENT. ANY DAMAGE TO ANY EXISTING SERVICES, PLANT OR EQUIPMENT MUST BE REPAIRED AT THE CONTRACTOR'S COST.

Drawing Issue Status

**CONSTRUCTION**

REFER TO PBA DRAWING NO T14011-PBA-DR-C-1B-FGH-00-PA-003 FOR THE PROPOSED PAVING WORKS WITHIN ADOPTED HIGHWAY

**AGAR GROVE ESTATE REGENERATION PHASE 1B - BLOCK F, G & H PROPOSED PAVEMENT PLAN**

Client **Hill**

Architect **ARCHITYPE**

Date of this Issue 15.03.17

Art Scale 1:200

Drawing Number T14011-PBA-DR-C-1B-FGH-00-PA-01

Revision **C3**

Checked ET

Approved PPS

Drawn OO

Design IK

Design Date 15.03.17

Office through-out the UK and Europe

**peterbrett**

www.peterbrett.com

Peter Brett Associates LLP

020 7596 8600