

1. Stair cores from third floor terraces above to be demolished. Retention of structural columns
2. Original fabric removed to create open office space
3. Non-original fabric removed to create office space
4. WCs stripped out
5. Section of lightwell façade to be removed to provide access into lightwell.
6. Existing lift cars stripped out, cores retained.
7. Builders work openings for services risers - refer to services engineers drawings for sizes of holes. Note: as existing structural layout is unknown, additional fabric may need to be removed to facilitate structural reinforcement.
8. Overhead downstand retained to delineate existing walls positions.
9. Existing single glazed windows to upstands of roof lanterns to be removed and replacement with sliding replacements to closely match existing but to facilitate safe access and maintenance of council chamber rooflight.
10. Openings for reinstatement of windows following demolition of link-bridge during Crosstree development

Notes:

Drawings are based on survey data and may not accurately represent what is physically present.

All dimensions are to be verified on site before proceeding with the work.

All dimensions are in millimeters unless noted otherwise.

Purcell shall be notified in writing of any discrepancies.

Demolitions & Alterations Key

Original fabric defined as that documented in Archive Drawings. Where date of fabric is unknown, it is assumed as original.


- Original Fabric: Section of Wall/Slab to be Demolished
- Original Fabric: Item to be Demolished
- Overhead - 300mm wide opening to ceiling for high level concealed cable distribution - make good after installation
- Overhead: Whole bay of vaulted ceiling to be removed for cabling distribution and reinstated
- Original Fabric: High level opening in wall for services distribution
- Floor trenches in slab for cable distribution
- Manhole: Opening in slab
- Non-Original Fabric: Section of Wall to be Demolished
- Non-Original Fabric: Item to be Demolished

- Window Number
- Door Number
- Annotation Item

Drawings to be read in conjunction with:

Internal Repairs & Builder's Works drawing series (93)000 for key spaces
Conservation Strategy Report: CTH-PUR-MP-00-SP-A-00005

1:200 Scale



S5 P00 18 Apr 2019 OB NS

ISSUE	DATE	DRAWN	CHECKED	DESCRIPTION
DRAWING TITLE	GA PROPOSED DEMOLITIONS AND STRIP OUT SECOND FLOOR LEVEL PLAN			
DRAWING NO.	CTH-PUR-MP-02-DR-A-91004			
REVISION	S5 P00			
SIZE & SCALE	A1L 1:200			
DRAWING STATUS	S5 SUITABLE FOR PLANNING			

CLIENT	Lendlease	
PROJECT	Camden Town Hall	
JOB NUMBER	238664	

15 Bermondsey Square, Tower Bridge Road, London, SE1 3UN . T: +44(0)20 7397 7171, E: london@purcelluk.com
© PURCELL 2012. PURCELL ® IS THE TRADING NAME OF PURCELL MILLER TRITTON LLP

I 91004 SECOND FLOOR LEVEL PLAN PROPOSED DEMOLITIONS AND STRIP OUT 1:200 @ A1