27 Randolph Street - Window Schedule

Existing Windows		Proposed Works								Replace			Other works		Comments
Reference	**Existing Window**	Refubish Window or Door	Remove Casement	Strip Paint	Replace Defective Ironmongery	Replace Broken Glass	Windowc are Repairs	Renew Cill	Redecorate	Remove existing and dispose	Renew window in like for like timber	Double glazing unit thickness 14mm	Secondary glazing	Fit window restrictors	
W-01	Timber sash		✓		✓					✓	✓		✓		
W-02	Timber sash		✓		✓					✓	✓		✓		
W-03	Timber sash		✓		✓					✓	✓		✓		
W-04	Timber sash		✓		✓					✓	✓		✓		
W-05	Timber sash		✓		✓					✓	✓		✓		
W-06	Timber sash		✓		✓					✓	✓		✓		
W-07	Timber sash		✓		✓					✓	✓		✓		
W-08	Timber sash		✓		✓					✓	✓		✓		
W-09	Timber sash		✓		✓					✓	✓		✓		
W-10	Timber sash		✓		✓					✓	✓		✓		
W-11	Timber sash		✓		✓					✓	✓		✓		
W-12	Casement		✓		✓					✓	✓		✓		
W-13	Timber sash		✓		✓					✓	✓		✓		
W-14	Timber sash		✓		✓					✓	✓		✓		
W-15	Timber sash		✓		✓					✓	✓		✓		