

Proposed Clean Corridor Sections

GOSH Decontamination Unit

Boiler House & East Link

Notes:

1. Drawing to be read in conjunction with manufacturer's details and specification
2. Drawing to be read in conjunction with all other architectural drawings.
3. Drawing to be read in conjunction with Structural and Civil Engineers' and MEP drawings and specification.
4. For RWP dmensions, refer to Roof manufacturer's details and specification.

New roof structure to create covered link

Refer to Structural Engineer's details for lintel information

New 1:12 ramp up to existing level - extent TBC following survey

Proposed Handrail
Spec ref: 35-05-50/150
Hand railing - type B

Movement joint between new and existing slabs

Existing BH FFL

19740

Ext BH SSL

19490

Access to be advised by M&E

Condition of existing wall to be reviewed - with some surface materials and brickwork to be removed

Refer to Structural Engineer's detail for lintel information

Existing pipe work to be traced/resolved and subsequently removed

Movement joint between new and existing slabs

New levelling screed to existing corridor

External Envelope - Section A

1 : 50

New roof structure with 1:40 fall to create covered link

Refer to Structural Engineer's details for lintel information

Door removed - existing opening to be made good

New light guage steel/brick wall

Ramp up to existing internal level

Existing BH FFL

19740

Ext BH SSL

19490

Existing beam

Light guage steel frame built up in front of existing overhang

External Envelope - Section B

1 : 50

External Envelope - Section C

1 : 50

New doorset - existing opening to be widened to create required structural opening.
- Refer to Door Types drawing 32010 and Door Schedule 06010

NOTE:

All levels and dimensions TBC following completion of survey.

Internal space to be hospital corridor quality.

Revision Schedule

* WIP issue for comment	04/12/17
P1 Tender Issue (note: tender not submitted)	12/01/18
P2 Issued for information	20/02/18
P3 Updated to reflect design development to clean corridor	26/02/18
P4 Existing opening to Scan Room to be infilled	12/03/18
P5 Updated for review	10/04/18
P6 Issue for Planning	07/03/19

DO NOT SCALE OFF DRAWINGS
REPORT ALL DISCREPANCIES
CHECK ALL DIMENSIONS ON SITE



1:50

© Copyright Murphy Philipps 2018
Prepared using Revit 2016

Planning

Proposed Clean Corridor Sections
at
GOSH Decontamination Unit
for
NHS Foundations Trust

MURPHYPHILIPPS

3068 - MPA - 01 - B1 - DR - AR - 21001
REV: P6 - 07/03/19
Scale: 1 : 50 @ A3

16 Wenlock Road
London, N1 7TA
Tel: 020 7490 8008
Fax: 020 7490 8778