



### DEMOLITION SPECIFICATION

1. AGREE REQUIREMENTS FOR RETAINING SHRUBS AND PLANTING WITH CLIENT PRIOR TO COMMENCING WORKS
2. SET ASIDE ANY MATERIALS FROM DEMOLITIONS IF SUITABLE FOR RE-USE
3. CAREFULLY REMOVE ALL COPINGS
4. CAREFULLY TAKE DOWN TOP SECTION OF HIGH WALL AS INDICATED
5. RAKE OUT AND REPOINT JOINTS TO ALL SECTIONS OF WALL WHICH ARE NOT TO BE RE-BUILT, ALLOW FOR REMOVAL OF ANY PREVIOUSLY INSTALLED CORRODING METAL FIXINGS

### RE-BUILD SPECIFICATION

1. TO INCLUDE BUTTRESSES AND PIERS TO MATCH EXISTING AS NOTED USING SALVAGED BRICKS FROM DEMOLITION WHERE POSSIBLE
2. RAKE OUT AND RE-POINT ALL RETAINED BRICKWORK
3. ALLOW FOR ENGINEERING BRICKS TO BE USED BELOW GROUND LEVEL AND SECOND HAND STOCKS TO MATCH EXISTING ABOVE GROUND LEVEL
4. FOUNDATION TO BE MASS CONCRETE TRENCH FOUNDATION
5. JOINTS TO BE FLUSH POINTED STRUCK AS WORK PROCEEDS
6. ALLOW FOR BACKFILL AND TOPSOIL TO GARDENS BOTH SIDES OF NEW SECTIONS OF WALL
7. SUPPLY AND LAY NEW BRICK ON EDGE COPINGS IN STOCK BRICKS
8. SUPPLY AND LAY NEW/ RE-USED STONE COPINGS TO WEST SECTION OF WALL UP TO AND INCLUDING PIER 1. ALLOW FOR REMOVAL AND RE-BEDDING OF TOP THREE BRICK COURSES OF PIER 1 AND PART OF PANEL TO WEST AS INDICATED

CLIENT:  
MR AND MRS C HARRISON,  
26 GROVE TERRACE,  
LONDON NW5 1PL

PROJECT:  
NORTH GARDEN WALL  
CONSERVATION

DRAWING NR:  
26-GT-04

DRAWING TITLE:  
PROPOSED WALL DETAILS  
(WEST)

SCALE:  
1:100@A4

DATE:  
03-04-2019

REV:

ARCHITECT:  
HUGHES CONSULTANTS,  
96 HARBERTON ROAD,  
LONDON N19 3JP