





Existing gantry floor level

Existing beams to be trimmed out to give clear opening of 2000x1500 clear opening for plant access.

Basement

21.04

20.46

Sub-Basement

Survey Information not available

Wall construction and complete transformer enclosure to achieve 4hr fire rating throughout.

chamber at basement level

4no 125 diameter pipes to link cabling to mains. Outlet louvre.

Reinforced concrete slab - to Structural Engineer's specification. To be 4hr fire rated.

Lightwell to be drained to a gully.

Door construction to be 2hr fire rated.

50mm screed and Earth rod mesh.

NOTE

to be read in conjunction with information from UKPN and cube_design ltd drawings P3002-P3005.

Sources: Surveyed plans received from Maltby Surveys Ltd October 2018. Update received March 2019. Substation information received from UKPN January 2019.

0 0.5 1 1.5 2m

 scale
 1:50 @ A3 date drawn
 11/04/2019 JLS
 1289 - P3005 - A

 www.cube-designltd.co.uk
 T: 01425 481 999
 cube_design ©