




The planting shall be carried out in the first planting (seeding) season following completion of the development (between December and March inclusive).

All plant stock, plant handling and planting to be undertaken in accordance with the following British Standard Specifications and Code of Practice:

- BS 3936:1992 Part 1 Nursery Stock - Specification for trees and shrubs;
- BS 3936:1998 Part 10 Nursery Stock - Specification for ground cover plants;
- BS 4428:1989 - Code of Practice for General Landscaping Operations (excluding hard surfaces);
- BS 8545:2014 Trees from Nursery to Independence in the Landscape;
- The Code of Practice for Plant Handling 2002 (Horticultural Trades Association).

LEGEND (SOFT WORKS)

-  Retained tree
-  Extra heavy standard to semi mature tree, rootballed
-  Multistemmed tree
-  Grasses, ferns and herbaceous mix
-  Hedging
-  Climber
-  Species Rich Lawn - Wildflower Turf Spec or equal approved - pre grown turf
-  Activity Lawn - Tillers Arena Turf available from Tillers Turf Ltd or equal approved - pre grown turf
-  Log pile refugia - site won timber as hibernacular
-  Temporary works area for turning head for refuse and emergency vehicles

Notes
Plan to be read in conjunction with the engineer and landscape drawings.

Based on drawings and specification produced by Grant Associates May 2014, as approved by the LPA.

No measurements to be scaled off drawing. Worked from figured dimensions only.

All dimensions shown on drawing are shown in millimetres unless otherwise stated.

All dimensions and levels to be checked on site. Landscape Architect to be notified immediately of any discrepancies prior to the commencement of works.

JO WILD LANDSCAPES

Landscape Architect
Tel: 07867 336 117
Email: jmwilld@btinternet.com

Client
Hill Partnership Ltd

Project:
Agri Grow, Phase 1B (Phase 2)

Drawing Title:
Soft works CONSTRUCTION

Scale:
1:200 @ A2

Drawing Number:
10425-15

Date:
Sept. 2018

Revision Number:
-