Report VA2484.190618.NIA1.2

22 Bedford Square, London

Noise Impact Assessment

19 June 2019

Taylor Project Services No 1 Cornhill London EC3V 3ND

Venta Acoustic

01962 461016 0203 8650332 mail@ventaacoustics.com

registered company no. 10139494

Contents

1.	Intr	oduction	1
2.	Des	ign Criterion and Assessment Methodology	1
2	.1	Camden Council Requirements	1
2	.2	BS8233:2014	2
3.	Site	Description	2
4.	Envi	ironmental Noise Survey	3
4	.1	Survey Procedure & Equipment	3
4	.2	Results	3
4	.3	Plant Noise Emission Limits	4
5.	Prec	dicted Noise Impact	4
5	.1	Proposed plant	4
5	.2	Recommended Mitigation Measures	4
5	.3	Predicted noise levels	5
5	.4	Comparison to NR35 Curve	5
5	.5	Comparison to BS8233:2014 Criteria	5
6.	Con	clusion	6

Attachments

VA2484/SP1	Indicative Site Plan
VA2484/TH1-TH2	Environmental Noise Time Histories
Appendix A	Acoustic Terminology
Appendix B	Acoustic Calculations
nppenan b	

1. Introduction

It is proposed to install 10 new condenser units in the rear lightwell at 22 Bedford Square, London to service the office in the premises.

Venta Acoustics has been commissioned by Taylor Project Services to undertake an assessment of the potential noise impact of these proposals in support of an application for planning permission.

An environmental noise survey has been undertaken to determine the background noise levels at the most affected noise sensitive receptors. These levels are used to undertake an assessment of the likely impact with reference to the planning requirements of Camden Council.

2. Design Criterion and Assessment Methodology

2.1 Camden Council Requirements

Camden Council's Local Plan (adopted June 2017), Appendix 3, provides the following guidance regarding noise from Industrial and Commercial Noise Sources

A relevant standard or guidance document should be referenced when determining values for LOAEL and SOAEL for non-anonymous noise. Where appropriate and within the scope of the document it is expected that British Standard 4142:2014 'Methods for rating and assessing industrial and commercial sound' (BS 4142) will be used. For such cases a 'Rating Level' of 10 dB below background (15dB if tonal components are present) should be considered as the design criterion).

Existing Noise sensitive receiver	Assessment Location	Design Period	LOAEL (Green)	LOAEL to SOAEL (Amber)	SOAL (Red)
Dwellings**	Garden used for main amenity (free field) and Outside living or dining or bedroom window (façade)	Day	'Rating level' 10dB* below background	'Rating level' between 9dB below and 5dB above background	'Rating level' greater than 5dB above background
Dwellings**	Outside bedroom window (façade)	Night	'Rating level' 10dB* below background and no events exceeding 57dBLAmax	'Rating level' between 9dB below and 5dB above background or noise events between 57dB and 88dB LAmax	'Rating level' greater than 5dB above background and/or events exceeding 88dBLAmax

*10dB should be increased to 15dB if the noise contains audible tonal elements. (day and night). However, if it can be demonstrated that there is no significant difference in the character of the residual background noise and the specific noise from the proposed development then this reduction may not be required.

In addition, a frequency analysis (to include, the use of Noise Rating (NR) curves or other criteria curves) for the assessment of tonal or low frequency noise may be required.

**levels given are for dwellings, however, levels are use specific and different levels will apply dependent on the use of the premises.

The periods in Table C correspond to 0700 hours to 2300 hours for the day and 2300 hours to 0700 hours for the night. The Council will take into account the likely times of occupation for types of development and will be amended according to the times of operation of the establishment under consideration.

There are certain smaller pieces of equipment on commercial premises, such as extract ventilation, air conditioning units and condensers, where achievement of the rating levels (ordinarily determined by a BS:4142 assessment) may not afford the necessary protection. In these cases, the Council will generally also require a NR curve specification of NR35 or below, dependant on the room (based upon measured or predicted L_{eq,5mins} noise levels in octave bands) 1 metre from the façade of affected premises, where the noise sensitive premise is located in a quiet background area.

2.2 BS8233:2014

BS8233 *Guidance on sound insulation and noise reduction for buildings* provides guidance as to suitable internal noise levels for different areas within residential buildings.

Activity	Location	07:00 to 23:00	23:00 to 07:00
Resting	Living Room	35 dB L _{Aeq, 16 hour}	-
Dining	Dining Room	40 dB LAeq, 16 hour	-
Sleeping (daytime resting)	Bedroom	35 dB L _{Aeq, 16 hour}	30 dB LAeq, 8 hour

The relevant section of the standard is shown below in Table 2.1.

Table 2.1 - Excerpt from BS8233: 2014

[dB ref. 20µPa]

3. Site Description

As illustrated on attached site plan VA2484/SP1, the site building is located on Bedford Square, with Gower Mews to the north.

The most affected noise sensitive receivers are expected to be to the rear of the adjacent property on Gower Mews.

4. Environmental Noise Survey

4.1 Survey Procedure & Equipment

In order to establish the existing background noise levels at the site, a noise survey was carried out between Monday 19th and Wednesday 21st November 2018 at the location shown in site plan VA2484/SP1. This location was chosen to be representative of the background noise level at the most affected noise sensitive receivers.

Continuous 5-minute samples of the L_{Aeq}, L_{Amax}, L_{A10} and L_{A90} sound pressure levels were undertaken at the measurement location.

The weather during the survey period was generally dry with light winds. The background noise data is not considered to have been compromised by these conditions.

Measurements were made generally in accordance with ISO 1996 2:2017 Acoustics - Description, measurement and assessment of environmental noise – Part 2: Determination of sound pressure levels.

The following equipment was used in the course of the survey:

Manufacturer		Serial No	Calibration			
Manufacturer	Model Type	Seliai NO	Certificate No.	Date		
NTi Class 1 Integrating SLM	XL2	A2A-11586-E0	UCRT18/1582	7/6/18		
Larson Davis calibrator	CAL200	13049	UCRT18/1431	20/4/18		

Table 4.1 – Equipment used for the tests

The calibration of the sound level meter was verified before and after use with no significant calibration drift observed.

4.2 Results

The measured sound levels are shown as time-history plots on the attached charts VA2484/TH1-2.

The background noise level is determined by road traffic in the surrounding roads.

The minimum background noise levels measured were:

Monitoring Period	Minimum L _{A90,5min}
07:00 22:00 hours	42 dB
07:00 – 23:00 hours	07:00 - 07:05, 21/11/18
22.00 07.00 hours	40 dB
23:00 – 07:00 hours	03:35 - 03:40, 21/11/18
Table 4.2 Minimum heateneus durates levels	

Table 4.2 – Minimum background noise levels

[dB ref. 20 μPa]

4.3 Plant Noise Emission Limits

On the basis of the measured noise levels and the planning requirements of the Local Authority, and considering that it is not expected that tonal noise will be generated by the proposed plant units, the following plant specific sound levels should not be exceeded at the most affected noise sensitive receivers:

Monitoring Period	Design Criterion (L _{Aeq})
07:00 – 23:00 hours	32 dB
23:00 – 07:00 hours	30 dB

 Table 4.3 – Specific sound pressure levels not to be exceeded at most affected noise sensitive receivers

5. Predicted Noise Impact

5.1 Proposed plant

The following plant is proposed for installation in the rear lightwell at the location indicated on site plan VA2484/SP1.

This location benefits from line of sight screening, provided by the roof edge, from all noise sensitive receptors.

Plant Item	Quantity	Proposed Model
Condensers	6	Daikin RXYSCQ5TV1
Condensers	4	Daikin RXYSQ8TY1
AHU	1	M&Y Q 10427-01-00

Table 5.1 – Indicative plant selections assumed for this assessment.

Consulting the manufacturer's datasheets, the following noise emissions levels are attributed to the proposed plant items:

Plant Item	Octave Band Centre Frequency (Hz) Sound Pressure, Lp@1m (dB)								dB(A)
	63	125	250	500	1k	2k	4k	8k	
Daikin RXYSCQ5TV1	51	53	52	53	47	41	34	27	53
Daikin RXYSQ8TY1	60	63	55	52	49	48	42	34	56
M&Y Q 10427-01-00 – supply	76	69	72	67	66	60	51	54	70
M&Y Q 10427-01-00 – return	77	71	65	64	65	56	54	60	68
M&Y Q 10427-01-00 – breakout	60	54	55	50	48	42	39	45	53

Table 5.2 – Advised plant noise data used for the assessment.

5.2 Recommended Mitigation Measures

The air handling unit will need to be fitted with attenuators to provide the minimum insertion losses shown in Table 5.3.

Attenuation Component	Octave Band Centre Frequency (Hz) Acoustic Louvre Insertion Loss (dB)								
	63	125	250	500	1k	2k	4k	8k	
Supply and Exhaust Attenuator	4	9	17	28	34	32	21	14	

Table 5.3 – Recommended attenuation to ventilation openings.

Should the above insertion loss by achieved using multiple silencers, these should be separated from each other by a distance of minimum 3-4 x D, where D is the largest internal dimension of the duct work (e.g. D is 0.5m, so a minimum of 1.5-2m apart).

Please note that the above recommendations relate to acoustic issues only. It is recommended that professional advice confirming the suitability of these measures be sought from others with regards to issues such as airflow, structural stability and visual impact.

All plant and ductwork should be fitted with anti-vibration mounts in accordance with the manufacturer guidelines. This is expected to control structureborne noise to the building to acceptable levels.

5.3 **Predicted noise levels**

The cumulative noise level at the most affected noise sensitive receiver on the upper floor to the rear of Gower Mews, some 8 meters away, has been calculated on the basis of the above information with reference to the guidelines set out in ISO 9613-2:1996 Attenuation of sound during propagation outdoors - Part 2: General method of calculation.

A summary of the calculations are shown in Appendix B.

Description	dB(A)
Plant noise criterion	30 dB
L _p 1m from receiver	30 dB

 Table 5.4 – Predicted noise and level and design criteria at noise sensitive location

5.4 Comparison to NR35 Curve

Frequency (Hz)	63	125	250	500	1k	2k	4k	8k
NR35	63	52	45	39	35	35	30	28
L _p 1m from receiver	48	40	31	26	22	20	14	14

 Table 5.5 - Comparison of predicted noise levels against the NR35 criterion

5.5 Comparison to BS8233:2014 Criteria

BS8233 assumes a loss of approximately 15dB for a partially open window. The external noise level shown in Table 5.4 would result in internal noise levels that achieve the guidelines shown in Table 2.1.

6. Conclusion

A baseline noise survey has been undertaken by Venta Acoustics to establish the background noise climate in the locality of 22 Bedford Square, London in support of a planning application for the proposed introduction of new building services plant.


This has enabled noise emission limits to be set at the most affected noise sensitive receiver such that the proposed installation meets the requirements of Camden Council.


The cumulative noise emission levels from the proposed plant have been assessed to be compliant with the plant noise emission limits.


The proposed scheme is not expected to have a significant adverse noise impact and the relevant planning requirements have been shown to be met.

Jamie Duncan MIOA

Venta Acoustics







APPENDIX A

Venta Acoustics

Acoustic Terminology & Human Response to Broadband Sound

1.1 Acoustic Terminology

The human impact of sounds is dependent upon many complex interrelated factors such as 'loudness', its frequency (or pitch) and variation in level. In order to have some objective measure of the annoyance, scales have been derived to allow for these subjective factors.

Sound	Vibrations propagating through a medium (air, water, etc.) that are detectable by the auditory system.
Noise	Sound that is unwanted by or disturbing to the perceiver.
Frequency	The rate per second of vibration constituting a wave, measured in Hertz (Hz), where 1Hz = 1 vibration cycle per second. The human hearing can generally detect sound having frequencies in the range 20Hz to 20kHz. Frequency corresponds to the perception of 'pitch', with low frequencies producing low 'notes' and higher frequencies producing high 'notes'.
dB(A):	Human hearing is more susceptible to mid-frequency sounds than those at high and low frequencies. To take account of this in measurements and predictions, the 'A' weighting scale is used so that the level of sound corresponds roughly to the level as it is typically discerned by humans. The measured or calculated 'A' weighted sound level is designated as dB(A) or L _A .
L _{eq} :	A notional steady sound level which, over a stated period of time, would contain the same amount of acoustical energy as the actual, fluctuating sound measured over that period (e.g. 8 hour, 1 hour, etc). The concept of L _{eq} (equivalent continuous sound level) has primarily been used in assessing noise from industry, although its use is becoming more widespread in defining many other types of sounds, such as from amplified music and environmental sources such as aircraft and construction. Because L _{eq} is effectively a summation of a number of events, it does not in itself limit the magnitude of any individual event, and this is frequently used in conjunction with an absolute sound limit.
L10 & L90 :	 Statistical Ln indices are used to describe the level and the degree of fluctuation of non-steady sound. The term refers to the level exceeded for n% of the time. Hence, L10 is the level exceeded for 10% of the time and as such can be regarded as a typical maximum level. Similarly, L90 is the typical minimum level and is often used to describe background noise. It is common practice to use the L10 index to describe noise from traffic as, being a high average, it takes into account the increased annoyance that results from the non-steady nature of traffic flow. The maximum sound pressure level recorded over a given period. Lmax is sometimes used in
L _{max} :	assessing environmental noise, where occasional loud events occur which might not be adequately represented by a time-averaged Leg value.

1.2 Octave Band Frequencies

In order to determine the way in which the energy of sound is distributed across the frequency range, the International Standards Organisation has agreed on "preferred" bands of frequency for sound measurement and analysis. The widest and most commonly used band for frequency measurement and analysis is the Octave Band. In these bands, the upper frequency limit is twice the lower frequency limit, with the band being described by its "centre frequency" which is the average (geometric mean) of the upper and lower limits, e.g. 250 Hz octave band extends from 176 Hz to 353 Hz. The most commonly used octave bands are:

 Octave Band Centre Frequency Hz
 63
 125
 250
 500
 1000
 2000
 4000
 8000

APPENDIX A

Venta Acoustics

Acoustic Terminology & Human Response to Broadband Sound

1.3 Human Perception of Broadband Noise

Because of the logarithmic nature of the decibel scale, it should be borne in mind that sound levels in dB(A) do not have a simple linear relationship. For example, 100dB(A) sound level is not twice as loud as 50dB(A). It has been found experimentally that changes in the average level of fluctuating sound, such as from traffic, need to be of the order of 3dB before becoming definitely perceptible to the human ear. Data from other experiments have indicated that a change in sound level of 10dB is perceived by the average listener as a doubling or halving of loudness. Using this information, a guide to the subjective interpretation of changes in environmental sound level can be given.

Change in Sound Level dB	Subjective Impression	Human Response
0 to 2	Imperceptible change in loudness	Marginal
3 to 5	Perceptible change in loudness	Noticeable
6 to 10	Up to a doubling or halving of loudness	Significant
11 to 15	More than a doubling or halving of loudness	Substantial
16 to 20	Up to a quadrupling or quartering of loudness	Substantial
21 or more	More than a quadrupling or quartering of loudness	Very Substantial

1.4 Earth Bunds and Barriers - Effective Screen Height

When considering the reduction in sound level of a source provided by a barrier, it is necessary to establish the "effective screen height". For example if a tall barrier exists between a sound source and a listener, with the barrier close to the listener, the listener will perceive the sound as being louder if he climbs up a ladder (and is closer to the top of the barrier) than if he were standing at ground level. Equally if he sat on the ground the sound would seem quieter than if he were standing. This is explained by the fact that the "effective screen height" is changing with the three cases above. In general, the greater the effective screen height, the greater the perceived reduction in sound level.

Similarly, the attenuation provided by a barrier will be greater where it is aligned close to either the source or the listener than where the barrier is midway between the two.

APPENDIX B VA2484 - 22 Bedford Square, London

Noise Impact Assessment

Lower Ground		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Daikin RXYSCQ5TV1	Lp @ 1m	51	53	52	53	47	41	34	27	53
Numbe of units	1	0	0	0	0	0	0	0	0	
Daikin RXYSQ8TY1	Lp @ 1m	60	63	55	52	49	48	42	34	56
Numbe of units	1	0	0	0	0	0	0	0	0	
Total Sound Pressure Level	Lp @ 1m	61	63	57	56	51	49	43	35	57
Distance Loss	To 12m	-22	-22	-22	-22	-22	-22	-22	-22	
Screening loss*		-14	-17	-18	-18	-18	-18	-18	-18	
Level at receiver		25	25	17	16	11	9	3	-5	18

* Screening loss limited to 18dB

Ground		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Daikin RXYSCQ5TV1	Lp @ 1m	51	53	52	53	47	41	34	27	53
Numbe of units	1	0	0	0	0	0	0	0	0	
Daikin RXYSQ8TY1	Lp @ 1m	60	63	55	52	49	48	42	34	56
Numbe of units	2	3	3	3	3	3	3	3	3	
Total Sound Pressure Level	Lp @ 1m	64	66	60	59	54	52	46	38	60
Distance Loss	To 10m	-20	-20	-20	-20	-20	-20	-20	-20	
Screening loss*		-12	-15	-18	-18	-18	-18	-18	-18	
Level at receiver		31	31	22	21	16	14	8	0	23

* Screening loss limited to 18dB

<u>First</u>		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Daikin RXYSCQ5TV1	Lp @ 1m	51	53	52	53	47	41	34	27	53
Numbe of units	1	0	0	0	0	0	0	0	0	
Daikin RXYSQ8TY1	Lp @ 1m	60	63	55	52	49	48	42	34	56
Numbe of units	2	3	3	3	3	3	3	3	3	
Total Sound Pressure Level	Lp @ 1m	64	66	60	59	54	52	46	38	60
Distance Loss	To 9m	-19	-19	-19	-19	-19	-19	-19	-19	
Screening loss*		-11	-14	-17	-18	-18	-18	-18	-18	
Level at receiver		33	34	25	22	17	15	9	1	25

* Screening loss limited to 18dB

<u>Second</u>		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
Daikin RXYSCQ5TV1	Lp @ 1m	51	53	52	53	47	41	34	27	53
Numbe of units	1	0	0	0	0	0	0	0	0	
Daikin RXYSQ8TY1	Lp @ 1m	60	63	55	52	49	48	42	34	56
Numbe of units	1	0	0	0	0	0	0	0	0	
Total Sound Pressure Level	Lp @ 1m	61	63	57	56	51	49	43	35	57
Distance Loss	To 8m	-18	-18	-18	-18	-18	-18	-18	-18	
Screening loss*		-10	-12	-15	-17	-18	-18	-18	-18	
Level at receiver		33	33	24	20	15	13	7	-1	23

* Screening loss limited to 18dB

Venta Acoustics		VA2484	4 Appendi							
		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
M&Y Q 10427-01-00 - Supply	Lp @ 1m	76	69	72	67	66	60	51	54	70
Attenuator insertion loss		-4	-9	-17	-28	-34	-32	-21	-14	
Distance Loss	To 8m	-18	-18	-18	-18	-18	-18	-18	-18	
Screening loss*		-10	-12	-14	-17	-18	-18	-18	-18	
Level at receiver		44	30	23	4	-4	-8	-6	4	21

* Screening loss limited to 18dB

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
M&Y Q 10427-01-00 - Return	Lp @ 1m	77	71	65	64	65	56	54	60	68
Attenuator insertion loss		-4	-9	-17	-28	-34	-32	-21	-14	
Distance Loss	To 8m	-18	-18	-18	-18	-18	-18	-18	-18	
Screening loss*		-10	-12	-14	-17	-18	-18	-18	-18	
Level at receiver		45	32	16	1	-5	-12	-3	10	21

* Screening loss limited to 18dB

		63 Hz	125 Hz	250 Hz	500 Hz	1 kHz	2 kHz	4 kHz	8 kHz	dB(A)
M&Y Q 10427-01-00 - Breakout	Lp @ 1m	60	54	55	50	48	42	39	45	53
Distance Loss	To 8m	-18	-18	-18	-18	-18	-18	-18	-18	
Screening loss*		-10	-12	-14	-17	-18	-18	-18	-18	
Level at receiver		32	24	23	15	12	6	3	9	19
* Screening loss limited to 18dB										
Cumulative plant noise at receiver		48	40	31	26	22	20	14	14	30 dB(A)