

All work shall be completed in line with BS3998:2010 'Recommendations for Tree Work' where appropriate
 Artemis Tree Services Ltd will check all TPO and Conservation Area clearance if not already in place

Artemis Tree Services Ltd







**QUOTATION/
WORK SCHEDULE**

Client: Cliff Carr 4 Frogna! Way Hampstead England NW3 6XE		Site address: 4 Frogna! Way Hampstead England NW3 6XE	
Our Ref: [Redacted]	Date:	16th July 2019	
	Purchase Order No:		

Details of Work Required/Recommended		[Redacted]
Tree number - T1 Tree type - Norway Maple (Acer pseudoplatanoides) Approx Height - 15m Location - Rear Garden Right hand boundary Service - Cut Back Work required - Removal Dead wood at top of tree and Cut back from building by 2m Reason - To give clearance from the house Priority code -ON		[Redacted]
Tree number - T2, T3 Tree type - x2 Sycamore (Acer psuedoplatanus) Approx Height - 15m Location - Rear Garden Right hand boundary Service - Cut Back Work required - Cut Back by 2m to give clearance to house Reason - To provide clearance between house and trees Priority code - ON		[Redacted]
Tree number - T4, T5 Tree type - x2 oval leaved Privet (Ligustrum ovalifolium) Approx Height - 9m Location - Rear Garden Right hand boundary Service - 1x Fell 1x Cut Back Work required- (T5) Fell as close to tree's current ground level as possible and leave the stump in the ground, treat with glyphosate to prevent regrowth. (T4) Cut Back by removing 1-1.5m Reason - As per clients wishes Priority code - ON		[Redacted]



All work shall be completed in line with BS3998:2010 'Recommendations for Tree Work' where appropriate
 Artemis Tree Services Ltd will check all TPO and Conservation Area clearance if not already in place

<p>Tree number - G1 Tree type - x1 Maple x1 Oak x1 Yew Hedge Approx Height - 6-9m Location - Rear Garden Rear left hand corner Service - Prune/ Trim Work required- Prune Back lowest branch on Maple back to main steam by removing approximately 3m, Prune back 2x lowest branches on Oak back to boundary by removing approximately 2-3m and Trim Yew Hedge Back To boundary as directed by client Reason - As per clients wishes Priority code -ON</p>		
<p>PN client to ensure gate is unlocked for rear access to trees</p>		
<p>P.N. Client will need to reserve 2-3 parking spaces in front of property for work vehicle.</p>		
	<p>All resulting brushwood and logs will be transported to our recycling depot awaiting transfer to Thetford Power Station to be used as bio-fuel (unless stated otherwise in the work description above).</p>	

Priorities

U – Within 2 weeks (If necessary fencing off the hazard until work can be carried out)
 A – Within 3 months B – Within 6 months C – Within 12 months ON - Owner's discretion

Tree Preservation Order/Conservation area status: **Artemis to organise once quote accepted.**

