

ARBORICULTURAL IMPACT ASSESSMENT REPORT FOR:

Belsize Lane London NW3 5AU

INSTRUCTING PARTY:

N Panigirtzoglou & M Sebastia 49 Belsize Lane London NW3 5AU

REPORT PREPARED BY

Adam Hollis MSc ARB MICFor FArbor A MRICS C Env

Ref: ESL/49BLS/AIA/01

Date: 15th August 2019

The content and format of this report are for the exclusive use of the client in planning. It may not be sold, lent, hired out or divulged to any third party, not directly involved in the subject matter without Landmark Trees' written consent

Web: www.landmarktrees.co.uk e-mail: info@landmarktrees.co.uk Tel: 0207 851 4544



London Office: Holden House, 4th Floor, 57 Rathbone Place London W1T 1JU Registered Office: 15 Abbey Road, Oxford OX2 0AD

Landmark Trees is the trading name of Landmark trees Ltd. Registered in Wales. Reg No. 3882076



Registered Consultant

PART 1: MAIN TEXT

Section	Content	Page N°
1.0	SUMMARY	3
2.0	INTRODUCTION	4
3.0	SITE CHARACTERISTICS	8
4.0	DEVELOPMENT CONSTRAINTS	11
5.0	TABLE OF IMPACTS	14
6.0	ARBORICULTURAL MPLICATIONS	15
7.0	CONCLUSION	18
8.0	RECOMMENDATIONS	19
9.0	COMPLIANCE	22
10.0	REFERENCES	23

PART 2 - APPENDICES

APPENDIX 1	Survey Data	26
APPENDIX 2	Recommended Tree Works	28
APPENDIX 3	Recommended Tree Works to Facilitate Development	30
APPENDIX 4	Trees for Urban Sites	32

PART 3 - PLANS

PLAN 1	Tree Constraints Plan	34
PLAN 2	Impact Assessment Plan(s)	36

DOCUMENT HISTORY

Revision	Status	Comments	Date
Rev 0	Approved	For Full Application	

Arboricultural Impact Assessment Report: 49 Belsize Lane, London NW3 5AU Instructing party: N Panigirtzoglou & M Sebastia, 49 Belsize Lane, London NW3 5AU Prepared by: Adam Hollis of Landmark Trees, Holden House, 4th Floor, 57 Rathbone Place, London W1T 4JU

1. SUMMARY

- 1.1 The existing site is a period terraced cottage with an existing small basement room and terrace to its rear garden which is at significantly lower level than the property.
- 1.2 There are 4 trees on the property and adjoining land outside of the application boundary that are within close proximity to the development and need to be assessed. These are judged mostly moderate and low-quality trees, although T1 has been identified as a poor quality specimen. The London Borough of Camden raised no objection (planning reference 2019/2240/T) to the removal of 2 of the 3 trees within the application site and also to the pruning of roots from the tree standing on the neighbouring property in order to facilitate the repair and deepening of the existing garden wall foundations.
- 1.3 The report has assessed the impacts of the development proposals and concludes there would be at most a negligible impact on the resource: it is necessary to remove 2 trees within the site to facilitate construction but these trees are to be removed under the aforementioned Section 211 notice regardless of development. Similarly, the pruning of any roots from the off-site T3 that may have grown beneath the existing garden wall necessary to facilitate construction of the basement level is also allowed for under the same Section 211 notice.
- 1.4 Notwithstanding the above, the report sets out a series of recommendations prior and during construction that will ensure impacts to trees are minimised. These are detailed in sections 6.3 and 8 of this report.
- 1.5 In conclusion, the proposal, through following the above recommendations, will have no, or very limited, impact on the existing trees and is acceptable.

* British Standards Institute: Trees in relation to design, demolition and construction BS 5837: 2012 HMSO, London

2. INTRODUCTION

- 2.1 Terms of Reference
 - 2.1.1 This Arboricultural Impact Assessment report has been prepared by Landmark Trees (LT) on behalf of N Panigirtzoglou & M Sebastia ('the Applicants'), to support a full planning application submitted to the London Borough of Camden ('LBC').
 - 2.1.2 The application relates to the deepening of the existing basement and extending it into the rear garden by about 4.5m. The roof of the basement extension will be at ground floor level and will therefore extend significantly above the rear garden ground level. The roof of the basement will comprise a tiled terrace.
 - 2.1.3 This report will assess the impact on trees and their constraints, identified in our survey. Although the proposals were known at the time of the survey, Landmark Trees endeavour to survey each site blind, working from a topographical survey, wherever possible, with the constraints plan informing their evolution. The purpose of the report is to provide guidance on how trees and other vegetation can be integrated into construction and development design schemes. The overall aim is to ensure the protection of amenity by trees which are appropriate for retention.
 - 2.1.4 Trees are a material consideration for a Local Planning Authority when determining planning applications, whether or not they are afforded the statutory protection of a Tree Preservation Order or Conservation Area. British Standard BS 5837:2012 Trees in Relation to Design, Demolition and Construction sets out the principles and procedures to be applied to achieve a harmonious and sustainable relationship between trees and new developments. The Standard recommends a sequence of activities (see Fig.1 overleaf) that starts in the initial feasibility and design phase (RIBA Stage 2 'Concept Design') with a survey to gualify and quantify the trees on site and establish the arboricultural constraints to development (aboveand below-ground) to inform the design in an iterative process, and continues with an assessment of the arboricultural impacts of the final design and measures to mitigate such impacts should they be negative. Detailed technical specifications for mitigation and protection measures are devised in the design phase that follows (RIBA Stage 3-4 'Developed and Technical design'), and the sequence ends with the Implementation and Aftercare phase (RIBA Stages 5-7) with the implementation of those measures once planning permission is granted, guided by Arboricultural Method Statements (RIBA Stage 4-5, 'Technical Design and Construction) and professional guidance where appropriate.
 - 2.1.5 This report is produced to support the Design Team to the Scheme Design Approvals stage in the process chart overleaf.



Figure 1 The design and construction process and tree care

2.2 Drawings Supplied

2.2.1	The drawings supplied by the client and relied upon by Landmark Trees in the formulation of
	our survey plans are:
	Existing site survey: Belsize Lane. Issue 16.04.19
	Proposals: Belsize Lane. Issue 13.08.19

2.3 Scope & Limitations of Survey

- 2.3.1 As Landmark Trees' (LT) arboricultural consultant, I surveyed the trees on site on 25th March 2019, recording relevant qualitative data in order to assess both their suitability for retention and their constraints upon the site, in accordance with British Standard 5837:2012 Trees in relation to design, demolition and construction Recommendations [BS5837:2012].
- 2.3.2 Our survey of the trees, the soils and any other factors, is of a preliminary nature. The trees were SURVEYED on the basis of the Visual Tree Assessment method expounded by Mattheck and Breloer (The Body Language of Trees, DoE booklet Research for Amenity Trees No. 4, 1994). LT have not taken any samples for analysis and the trees were not climbed but inspected from ground level.
- 2.3.3 The results of the tree survey, including material constraints arising from existing trees that merit retention, should be used (along with any other relevant baseline data) to inform feasibility studies and design options. For this reason, the tree survey should be completed and made available to designers prior to and/or independently of any specific proposals for development. Tree surveys undertaken after a detailed design has been prepared can identify significant conflicts: in such cases, the nature of and need for the proposed development should be set against the quality and values of affected trees. The extent to which the design can be modified to accommodate those trees meriting retention should be carefully considered. Where proposed development is subject to planning control, a tree survey should be regarded as an important part of the evidence base underpinning the design and access statement
- 2.3.3 A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter.
 2.3.4 The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

2.4 Survey Data & Report Layout

- 2.4.1 Detailed records of individual trees are given in the survey schedule in Appendix 1. General husbandry recommendations are distinguished at Appendix 2 from minimum requirements to facilitate development which form part of the planning application at Appendix 3. The former may still be relevant to providing a safe site of work, of course. Planning considerations notwithstanding, we trust these necessary recommendations are passed on to relevant parties with due diligence and the trees to be managed appropriately.
- 2.4.2 A site plan identifying the surveyed trees, based on the Instructing Party's drawings / topographical survey is provided in Part 3 of this report. This plan also serves as the Tree Constraints Plan with the theoretical Recommended Protection Areas (RPA's), tree canopies and shade constraints, (from BS5837: 2012) overlain onto it. These constraints are then overlain in turn onto the Instructing Party's proposals to create a second Arboricultural Impact Assessment Plan in Part 3. General observations, discussion, conclusions and recommendations follow, below.

3.0 SITE CHARACTERISTICS

3.1 Property Description & Planning Context



Photograph 1: Frontage of 49 Belsize Lane

3.1.1	The application site is a terraced, mews style property, located at the southern end of Belsize
	Lane. The road has a mixture of residential proper ties, private clinics, solicitors and multiple
	shopfronts that form Belsize Village.
3.1.2	The rear garden of the property is at a significantly lower level than the ground floor of the
	property.
3.1.3	We are not aware of the existence of any Tree Preservation Orders, but understand the site
	stands within the Belsize Park Conservation Area, which will affect the subject trees: it is a
	criminal offence to prune, damage or fell such trees without permission from the local
	authority.
3.1.4	Relevant local planning policies comprise Policy 7.21 of the London Plan 2016 and Policies
	A3, A5, D1 and D2 of the Camden Local Plan (adopted 3rd July 2017).
3.1.5	On 26th April 2019, a Section 211 notice (application reference: $2019/2240/T$)to fell T1 and
	T4 and to prune the roots of T3 to facilitate repair / deepening of the garden wall foundations
	was submitted to LBC. On 6th June 2019, LBC confirmed they did not wish to object to these
	works.

3.2 Soil Description



Figure 2: Extract from the BGS Geology of Britain Viewer

3.2.1	In terms of the British Geological Survey, the site overlies the London Clay Formation (see
	indicated location on Fig.1 plan extract above). The associated soils are generally, highly
	shrinkable clay; e.g. slowly permeable seasonally waterlogged fine loam over clay. Such
	highly plastic soils are prone to movement: subsidence and heave. The actual distribution of
	the soil series are not as clearly defined on the ground as on plan and there may be anomalies
	in the actual composition of clay, silt and sand content.
3.2.2	Clay soils are prone to compaction during development with damage to soil structure
	potentially having a serious impact on tree health. The design of foundations near problematic
	tree species will also need to take into consideration subsidence risk. Further advice from the
	relevant experts on the specific soil properties can be sought as necessary.

3.3 Subject Trees

3.3.1	Of the 4 surveyed trees, 1 is category* B (Moderate Quality), 2 are category C (Low Quality	
	and 1 is category U (Poor Quality); none are category A (High Quality).	
3.3.2	The tree species found on the site comprise false acacia, Lawson cypress, sycamore and	
	Portuguese laurel.	
3.3.3	In terms of age demographics 2 of the trees are semi-mature, 1 is early mature and the fourth	
	is mature.	

*page 9 of: British Standards Institute: Trees in relation to design, demolition and construction BS 5837: 2012 HMSO, London

3.2.4	Full details of the surveyed trees can be found in Appendix 1 of this report.	
3.2.5	There are recommended works for 1 on-site tree (T1) and 1 off-site tree (T3 – third party tree).	
	These are listed in Appendix 2.	

4.0 DEVELOPMENT CONSTRAINTS

4.1 Primary Constraints

4.1.1	A tree's primary constraint on development is the physical space it occupies or requires above
	and below ground on a given site. The current canopy spreads and heights are noted in our
	survey; allowance for further growth and broader aspects of juxtaposition are considered
	under secondary impacts below. With regard to root spread, BS5837 defines the Root
	Protection Area (RPA) as a layout design tool indicating the minimum area around a tree
	deemed to contain sufficient roots and rooting volume to maintain the tree's viability, and
	where the protection of the roots and soil structure is treated as a priority.
4.1.2	The individual RPA's are calculated in the Tree Schedule in Appendix 1 to this report, or rather
	the notional radius of that RPA, based on a circular protection zone. The prescribed radius is
	12-x stem diameter at 1.5m above ground level, except where composite formulae are used
	in the case of multi-stemmed trees.
4.1.3	Circular RPA's are appropriate for individual specimen trees grown freely, but where there is
	ground disturbance, the morphology of the RPA can be modified to an alternative polygon, as
	shown in the diagram below (Figure 2). Alternatively, one need principally remember that
	RPA's are area-based and not linear – notional rather than fixed entities.



Figure 3– Generic BS 5837 RPA Adjustments (for fictitious site)

4.1.4 In BS5837, paragraph 4.6.2 states that RPA's should reflect the morphology and disposition of the roots; where pre-existing site conditions or other factors indicate that rooting has occurred asymmetrically, a polygon of equivalent area should be produced. Modifications to the shape of the RPA should reflect a soundly based arboricultural assessment of likely root distribution.

- 4.1.5 A *priroi* modifications have been made in this instance, based upon both the likely inhibiting effect of the boundary wall on root development into the application site from T3 and also S.211 notice 2019/2240/T which allows for the pruning of roots from T3 to permit repair of the wall foundations.
- 4.1.6 In addition to these quantitative assessments, the quality of trees will also be a consideration: Category U trees are discounted from the planning process in view of their limited service life. Again, Category C trees would not normally prevent development individually, unless they provide some particular (screening) function. Nonetheless, they remain material constraints.
- 4.1.7 At paragraph 5.1.1. BS5837: 2012 notes that "Care should be exercised over misplaced tree preservation; attempts to retain too many or unsuitable trees on a site are liable to result in excessive pressure on the trees during demolition or construction work, or post-completion demands on their removal."

4.1.7	Only moderate quality trees and above are significant material constraints on development.
	However, low quality trees comprise a constraint in aggregate, in terms of any collective loss
	/ removal, where replacement planting is generally considered appropriate.
4.1.8	In this instance, LBC's lack of objection to S.211 notice 2019/2240/T means that there are
	few significant primary constraints upon development.

4.2 Secondary Constraints

4.2.1	The second type of constraint produced by trees that are to be retained is that the proximity of the proposed development to the	
	trees should not threaten their future with ever increasing demands for tree surgery or felling	
	honeydew deposition or perceived risk of harm.	Figure 3 – Generic Shading Constraints

4.2.2 The shading constraints are crudely determined from BS5837 by drawing an arc from northwest to east of the stem base at a distance equal to the height of the tree, as shown in the diagram opposite. Shade is less of a constraint on non-residential developments, particularly where rooms are only ever temporarily occupied.



4.2.3 This arc (see Figure 4) represents the effects that a tree will have on layout through shade, based on shadow patterns of 1x tree height for a period May to Sept inclusive 10.00-18.00 hrs daily.

4.2.4	Assuming that they will be retained, the orientation of the on- and off site trees will ensure
	that shading constraints are minimal, with leaf deposition and honey-dew likely to be as it is
	today. The significance of these constraints will vary depending on the location and proximity
	to the proposed re-development which is considered below (in Sections 5 & 6). As specified
	by BS5837, this section (4) of the report considers only the site as it is, not in the light of
	pending proposals.

Note: Sections 5 & 6 below will now assess the impacts of the proposals upon constraints identified in Section 4 above. Table 1 in Section 5 presents the impacts in tabular form (drawing upon survey data presented in Appendices 1 & 2). Impacts are presented in terms of whole tree removal and the effect on the landscape or partial encroachment (% of RPA) and its effect on individual tree health. Section 6 discusses the table data, elaborating upon the impacts' significance and mitigation. 5.0

Table 1: Arboricultural Impact Assessment

(Impacts assessed prior to mitigation and rated with reference to Matheny & Clark (1998))

Hide irrelevant Show All Trees

Ref: ESL_49BLS_AIA

B.S. Cat.	Tree No.	Species	Impact	Tree / RPA Affected	Age	Growth Vitality	Species Tolerance	Impact on Tree Rating	Impact on Site Rating	Mitigation
U	1	False Acacia	Felled to Facilitate Development	m² N/A %	Early Mature	Moderate	N/A	N/A	N/A	New planting <i>/</i> landscaping
В	3	Sycamore	Basement Construction within theoretical RPA Note: no impact to modified RPA	m² N/A %	Mature	Normal	Moderate	Very Low	Very Low	Hand dig top 750mm of basement line thro' RPA
С	4	Laurel, Portugese	Felled to Facilitate Development	m² N/A %	Semi-mature	Moderate	N/A	N/A	N/A	New planting <i>/</i> landscaping

6.0 ARBORICULTURAL IMPLICATIONS

6.1 Rating of Primary Impacts

6.1.1	The principal impacts in the current proposals is the removal of T1 and T4. The significance f
	the loss of these trees must be considered in the light of the lack of objection by LBC to their
	removal under Section 211 notice 2019/2240/T. This lack of objection means that these trees
	cannot be considered a constraint in terms of planning and therefore no impact arises from
	their removal. Notwithstanding this, their loss will be mitigated through planting / landscaping.
6.1.2	Whilst the pruning of T3 is required here to serve development, undertaken to best practice,
	the scale envisaged should not be altogether untoward in a more managed and occupied site
	and is recommended regardless of development proceeding. The immediate reduction in
	canopy cover through felling and / or pruning is therefore is rated as a very low impact unlikely
	to harm either the resource of the wider conservation area.
6.1.3	Further impacts to retained trees comprise the encroachments of the theoretical, but not
	modified, RPA of T3 by the extended basement level. As with the removal of T1 and T4, the
	significance of this encroachment must be viewed in the light of the extant consent to prune
	the roots of this tree to facilitate the repair and deepening of the boundary wall foundations.
	Notwithstanding the ability of the applicant to carry out this root pruning, the line of the
	basement through the conventional, circular RPA of the tree will be manually excavated to a
	minimum depth of 750mm in conjunction with pre-emptive root pruning.

6.2 Rating of Secondary Impacts

6.2.1 There will always be marginal secondary impacts of honeydew / litter deposition and partial shade on this site, regardless of development which is the salient point for planning to consider. Thus, the secondary impacts of development are minimal.

6.3 Mitigation of Impacts

- 6.3.1 The replanting scheme will offer considerable enhancement and replaces trees of low and poor quality. Replacement trees will have the advantage of being specifically selected for the proposed site, healthy and fit-for-purpose. Design can provide for a diverse range of native and ornamental species that will compliment rather than conflict with the proposals, so providing a more sustainable long-term resource for the future . A selection of tree species and cultivars for open and constricted sites is provided in Appendix 4
- 6.3.2 The path of foundations through the conventional RPA of T3 will be manually excavated to 750mm depth under arboricultural supervision; any roots encountered within the trenches / pits will be cleanly pruned back to an appropriate junction with a sharp pruning saw or secateurs back to a junction. Roots larger than 25mm diameter may only be cut in consultation with an arboriculturalist.
 6.3.3 The immediate canopy encroachment can be avoided by cutting back the encroaching limbs
 - to the property line.
- 6.3.4 Nuisance deposition can be further mitigated with routine maintenance, light pruning / deadwooding and the fitting of filtration traps on guttering (see Figure 5 below).



Figure 5: Filtration traps, as shown above, could be fitted on the gutters which can easily be maintained at 2-3m above ground.

7.0 CONCLUSION

- 7.1 Given the existing consent for tree removal and root pruning, the potential impacts of development are all very low.
- 7.2 The full potential of the impacts can be largely mitigated through design and precautionary measures. These measures can be elaborated in Method Statements in the discharge of planning conditions.
- 7.3 The species affected are generally tolerant of root disturbance / crown reduction and the retained trees are generally in good health and capable of sustaining these reduced impacts.
- 7.4 Therefore, the proposals will not have any significant impact on either the retained trees or wider landscape thereby complying with Policy 7.21 of the London Plan 2016 and Policies A3, A5, D1 and D2 of the Camden Local Plan (adopted 3rd July 2017). Thus, with suitable mitigation and supervision the scheme is recommended to planning.

8.0 RECOMMENDATIONS

8.1 Specific Recommendations

8.1.1	Tree works recommendations in Appendix 2 are not part of the current application, but
	requirements of general maintenance that will need to be applied for (subject to para. 3.3 of
	this report and any other relevant constraints in planning or leasehold) by the client separately.
	Consent for the current planning application does not impart any consent for the Appendix 2
	maintenance works. Please note, though, the owner and / or manager of a property have a
	duty to maintain a safe site of work and to protect occupiers of the surrounding land / members $% \left({{{\rm{s}}_{\rm{s}}}} \right)$
	of the public from tree hazards. Works recommended in this report should be enacted in a
	timely fashion by the relevant party regardless of the progress of the development.

- 8.1.2 Recommendations for works required to facilitate development are found in Appendix 3 and a selection of columnar tree species cultivars for constricted sites provided in Appendix 4. Any tree removals recommended within this report should only be carried out with local authority consent.
- 8.1.3 Excavation and construction impacts within the RPA's of trees identified in Table 1 above, will need to be controlled by method statements specifying mitigation methods suggested in para 6.3 above and by consultant supervision as necessary. These method statements can be provided as part of the discharge of conditions.
- 8.1.4 Replace felled trees with native ornamental nursery stock under current best practice; i.e. conforming to and planted in accordance with the following:
 - BS8545: 2014 Code of Practice for Trees from Nursery to Landscape
 - BS 3936-1: 1992 Nursery stock. Specification for trees and shrubs; and
 - BS 5236:1975 Cultivation and Planting of Trees in the Advanced Nursery Stock Category.
 - All replacement stock should be planted and maintained as detailed in BS 4428:1989 (Section 7): Recommendations for General Landscape Operations.

8.2 General Recommendations for Sites Being Developed with Trees

- 8.2.1 Any trees which are in close proximity to the proposed development should be protected with a Tree Protection Barrier (TPB). Protective barrier fencing should be installed immediately following the completion of the tree works, remaining in situ for the entire duration of the development unless otherwise agreed in writing by the Council. It should be appropriate for the intensity and proximity of the development, usually comprising steel, mesh panels 2.4m in height ('Heras') and should be mounted on a scaffolding frame (shown in Fig 2 of BS5837:2012). The position of the TPB can be shown on plan as part of the discharge of conditions, once the layout is agreed with the planning authority. The TPB should be erected prior to commencement of works, remain in its original form on-site for the duration of works and be removed only upon full completion of works.
- 8.2.2 A TPB may no longer be required during soft landscaping work but a full arboricultural assessment must be performed prior to the undertaking of any excavations within the RPA of a tree. This will inform a decision about the requirement of protection measures. It is important that all TPBs have permanent, weatherproof notices denying access to the RPA.
- 8.2.3 The use of heavy plant machinery for building demolition, removal of imported materials and grading of surfaces should take place in one operation. The necessary machinery should be located above the existing grade level and work away from any retained trees. This will ensure that any spoil is removed from the RPAs. It is vital that the original soil level is not lowered as this is likely to cause damage to the shallow root systems.
- 8.2.4 Any pruning works must be in accordance with British Standard 3998:2010 Tree work [BS3998].
- 8.2.5 Where sections of hard surfacing are proposed in close proximity to trees, it is recommended that "No-Dig" surfacing be employed in accordance with BS5837:2012 and 'The Principles of Arboricultural Practice: Note 1, Driveways Close to Trees, AAIS 1996 [APN1]'.
- 8.2.6 If the RPA of a tree is encroached by underground service routes then BS5837:2012 and NJUG VOLUME 4 provisions should be employed. If it is deemed necessary, further arboricultural advice must be sought.
- 8.2.7 Numerous site activities are potentially damaging to trees e.g. parking, material storage, the use of plant machinery and all other sources of soil compaction. In operating plant, particular care is required to ensure that the operational arcs of excavation and lifting machinery, including their loads, do not physically damage trees when in use.

8.2.8	To enable the successful integration of the proposal with the retained trees, the following									
	points w	ill need to be taken into account:								
	1)	Plan of underground services.								
	2)	Schedule of tree protection measures, including the management of harmful								
		substances.								
	3)	Method statements for constructional variations regarding tree proximity (e.g.								
		foundations, surfacing and scaffolding).								
	4)	Site logistics plan to include storage, plant parking/stationing and materials								
		handling.								
	5)	Tree works: felling, required pruning and new planting. All works must be carried								
		out by a competent arborist in accordance with BS3998.								
	6)	Site supervision: the Site Agent must be nominated to be responsible for all								
		arboricultural matters on site. This person must:								
		 be present on site for the majority of the time; 								
		 be aware of the arboricultural responsibilities; 								
		 have the authority to stop work that is causing, or may cause harm to any 								
		tree;								
		 ensure all site operatives are aware of their responsibilities to the trees on 								
		site and the consequences of a failure to observe these responsibilities;								
		 make immediate contact with the local authority and/or a retained 								
		arboriculturalist in the event of any tree related problems occurring.								
8.2.9	These p	oints can be resolved and approved through consultation with the planning authority								
	via their	Arboricultural Officer.								
8.2.10	The seq	uence of works should be as follows:								
	i) ir	itial tree works: felling, stump grinding and pruning for working clearances;								
	ii) ir	stallation of TPB for demolition & construction;								
	iii) ir	istallation of underground services;								
	iv) ir	istallation of ground protection;								
	v) m	nain construction;								
	vi) re	emoval of TPB;								
	vii) s	oft landscaping.								

9.0 COMPLIANCE: Trees and the Planning System

- 9.1 Under the UK planning system, local authorities have a statutory duty to consider the protection and planting of trees when granting planning permission for proposed development. The potential effect of development on trees, whether statutorily protected (e.g. by a tree preservation order or by their inclusion within a conservation area) or not, is a material consideration that is taken into account in dealing with planning applications. Where trees are statutorily protected, it is important to contact the local planning authority and follow the appropriate procedures before undertaking any works that might affect the protected trees.
- 9.2 The nature and level of detail of information required to enable a local planning authority to properly consider the implications and effects of development proposals varies between stages and in relation to what is proposed. Table B.1 provides advice to both developers and local authorities on an appropriate amount of information. The term "minimum detail" is intended to reflect information that local authorities are expected to seek, whilst the term "additional information" identifies further details that might reasonably be sought, especially where any construction is proposed within the RPA.
- 9.3 This report delivers information appropriate to a full planning application and to these specific proposals as per BS5837 Table B.1 below, providing both minimum details and further additional material in the form of general tree protection recommendations and constructional variation.

Stage of process	Minimum detail	Additional information		
Pre-application	Tree survey	Tree retention/removal plan (draft)		
Planning application	Tree survey (in the absence of pre-application discussions)	Existing and proposed finished levels		
	Tree retention/removal plan (finalized)	Tree protection plan		
	Retained trees and RPAs shown on proposed layout	Arboricultural method statement – heads of terms		
	Strategic hard and soft landscape design, including species and location of new tree planting	Details for all special engineering within the RPA and other relevant construction details		
	Arboricultural impact assessment			
Reserved matters/ planning conditions	Alignment of utility apparatus (including drainage), where outside the RPA or	Arboricultural site monitoring schedule		
	where installed using a trenchless method	Tree and landscape management plan		
	Dimensioned tree protection plan	Post-construction remedial works		
	Arboricultural method statement – detailed	Landscape maintenance schedule		
	Schedule of works to retained trees, e.g. access facilitation pruning			
	Detailed hard and soft landscape design			

Table B.1 Delivery of tree-related information into the planning system

Arboricultural Impact Assessment Report: 49 Belsize Lane, London NW3 5AU

Instructing party: N Panigirtzoglou & M Sebastia, 49 Belsize Lane, London NW3 5AU

Prepared by: Adam Hollis of Landmark Trees, Holden House, 4th Floor, 57 Rathbone Place, London W1T 4JU

10.0 REFERENCES

•	Barlow JF & Harrison G. 1999. Shade By Trees, Arboricultural Practice Note 5, AAIS, Farnham, Surrey.
•	British Standards Institute. 2012. Trees in Relation to Design, Demolition and Construction - Recommendations
	BS 5837: 2012 HMSO, London.
•	Centre for Ecology & Hydrology. 2006. Tree Roots in the Built Environment, HMSO, London.
•	Helliwell R (1980) Provision for New Trees; Landscape Design; July/August issue
•	International Society of Arboriculture (ISA). 1994. The Landscape Below Ground. ISA, Champaign, Ilinois. USA.
•	Lonsdale D 1999. Research for Amenity Trees No.7: Principles of Tree Hazard Assessment and Management,
	HMSO, London.
•	Matheny, N; Clark, J. R.1998. Trees and Development: A Technical Guide to Preservation of Trees during Land
	Development. ISA, Champaign, Ilinois. USA.
•	Mattheck C. & Breloer H. 1994. Research for Amenity Trees No.2: The Body Language of Trees, HMSO, London.
•	Thomas P, 2000 & 2014. Trees: Their Natural History, Cambridge University Press, Cambridge.
•	Trowbridge J & Bassuk N (2004) Trees in the Urban Landscape: Site Assessment, Design, and Installation; J
	Wiley & Sons inc. NJ USA



Caveats

This report is primarily an arboricultural report. Whilst comments relating to matters involving built structures or soil data may appear, any opinion thus expressed should be viewed as qualified, and confirmation from an appropriately qualified professional sought. Such points are usually clearly identified within the body of the report. It is not a full safety survey or subsidence risk assessment survey. These services can be provided but a further fee would be payable. Where matters of tree condition with a safety implication are noted during a survey they will of course appear in the report.

A tree survey is generally considered invalid in planning terms after 2 years, but changes in tree condition may occur at any time, particularly after acute (e.g. storm events) or prolonged (e.g. drought) environmental stresses or injuries (e.g. root severance). Routine surveys at different times of the year and within two - three years of each other (subject to the incidence of the above stresses) are recommended for the health and safety management of trees remote from highways or busy access routes. Annual surveys are recommended for the latter.

Tree works recommendations are found in the Appendices to this report. It is assumed, unless otherwise stated ("ASAP" or "Option to") that all husbandry recommendations will be carried out within 6 months of the report's first issue. Clearly, works required to facilitate development will not be required if the application is shelved or refused. However, necessary husbandry work should not be shelved with the application and should be brought to the attention of the person responsible, by the applicant, if different. Under the Occupiers Liability Act of 1957, the owner (or his agent) of a tree is charged with the due care of protecting persons and property from foreseeable damage and injury.' He is responsible for damage and/or nuisance arising from all parts of the tree, including roots and branches, regardless of the property on which they occur. He also has a duty under The Health and Safety at Work Act 1974 to provide a safe place of work, during construction. Tree works should only be carried out with local authority consent, where applicable.

Inherent in a tree survey is assessment of the risk associated with trees close to people and their property. Most human activities involve a degree of risk, such risks being commonly accepted if the associated benefits are perceived to be commensurate.

Risks associated with trees tend to increase with the age of the trees concerned, but so do many of the benefits. It will be appreciated, and deemed to be accepted by the client, that the formulation of recommendations for all management of trees will be guided by the cost-benefit analysis (in terms of amenity), of tree work that would remove all risk of tree related damage.

Prior to the commencement of any tree works, an ecological assessment of specific trees may be required to ascertain whether protected species (e.g. bats, badgers and invertebrates etc.) may be affected.

24



PART 2 – APPENDICES

APPENDIX 1

TREE SCHEDULE

Botanical Tree Names Acacia, False (Robinia) Cypress, Lawson

: Robinia Pseudoacacia : Chamaecyparis lawsonia Laurel, Portuguese Sycamore : Prunus lusitanica : Acer pseudoplatanus

Notes for Guidance:

- 1. Height describes the approximate height of the tree measured in metres from ground level.
- The Crown Spread refers to the crown radius in meters from the stem centre and is expressed as an average of NSEW aspect if symmetrical.
- 3. Ground Clearance is the height in metres of crown clearance above adjacent ground level.
- 4. Stem Diameter (Dm) is the diameter of the stem measured in millimetres at 1.5m from ground level for single stemmed trees. BS 5837:2012 formula (Section 4.6) used to calculate diameter of multi-stemmed trees. Stem Diameter may be estimated where access is restricted and denoted by '#'.
- 5. Protection Multiplier is 12 and is the number used to calculate the tree's protection radius and area
- 6. Protection Radius is a radial distance measured from the trunk centre.
- Growth Vitality Normal growth, Moderate (below normal), Poor (sparse/weak), Dead (dead or dying tree).
- Structural Condition Good (no or only minor defects), Fair (remediable defects), Poor Major defects present.
- Landscape Contribution High (prominent landscape feature), Medium (visible in landscape), Low (secluded/among other trees).
- B.S. Cat refers to (British Standard 5837:2012 section 4.5) and refers to tree/group quality and value;
 'A' High, 'B' Moderate, 'C' Low, 'U' Unsuitable for retention. The following colouring has been used on the site plans:
 - High Quality (A) (Green),
 - Moderate Quality (B) (Blue),
 - Low Quality (C) (Grey),
 - Unsuitable for Retention (U) (Red)
- 11. Sub Cat refers to the retention criteria values where 1 is Arboricultural, 2 is Landscape and 3 is Cultural including Conservational, Historic and Commemorative.
- 12. Useful Life is the tree's estimated remaining contribution in years.



Appendix 1

Landmark Trees Ltd 020 7851 4544

Ref:

BS5837 Tree Constraints Survey Schedule

Adam Hollis Surveyor(s): ESL_49BLS_AIA

Tree No.	English Name	Height	Crown Spread	Ground Clearance	Stem Diamete	Age Class	Protection Radius	Growth Vitality	Structural Condition	B.S. Cat	Sub Cat	Useful Life	Comments
1	False Acacia	11	1643	3.5	410	Early Mature	4.9	Moderate	Poor	U		<10	Decay in swollen base, bark necrosis Topped at 8m To be removed under CAN 2019/2240/T
2	Cypress, Lawson	6	2121	1.5	180	Semi- mature	2.2	Normal	Fair	С	2		Remote survey only (RS) Topped at 5.5m
3	Sycamore	12	5453	6.0	500	Mature	6.0	Normal	Fair	В	2	40+	Unsuitable species for position Crown reduced 2017/18 To be root pruned under CAN 2019/2240/T
4	Laurel, Portugese	5	1312	2.0	150	Semi- mature	1.8	Moderate	Fair	С	2	10+	Suppressed by nearby tree To be removed under CAN 2019/2240/T

APPENDIX 2

RECOMMENDED TREE WORKS

Notes for Guidance:						
Husbandry 1 - Urgent (ASAP), 2 - Standard (within 6 months), 3 - Non-urgent (2-3 years)						
CB - Cut Back to boundary/clear from structure.						
CL# - Crown Lift to given height in meters.						
CT#% - Crown Thinning by identified %.						
CR#% - Crown Reduce by given maximum % (of outermost branch & twig length)						
DWD - Remove deadwood.						
Fell - Fell to ground level.						
FInv - Further Investigation (generally with decay detection equipment).						
Pol - Pollard or re-pollard.						
 Check / monitor progress of defect(s) at next consultant inspection which should be <18 months in frequented areas and <3 years in areas of more occasional use. Where clients retain their own ground staff, we recommend an annual in- house inspection and where 						
practical, in the aftermath of extreme weather events.						
Svr Ivy / Clr Bs - Sever ivy / clear base and re-inspect base / stem for concealed defects.						

Landma	Site: Date: Date:	49 Belsize 25/03/2019		R	A ecomme	ppendix 2 ended Tree Works	Surveyor(s): Ref:	Adam Hollis ESL_49BLS_AIA	Hide irrelevant Show All Trees
Tree No.	English Name	B.S. Cat	Height	Ground Clearance	Crown Spread	Recommended Works	Comments	/ Reasons	
1	False Acacia	U	11	3.5	1643	Fell	Decay in swollen Topped at 8m To be removed u Recommended h	base, bark necrosis Inder CAN 2019/224 Iusbandry 2	D/T
3	Sycamore	В	12	6.0	5453	CB Cut back 1.5m from boundary wall	Unsuitable specie Crown reduced 2 To be root prune Recommended h	es for position 2017/18 d under CAN 2019/2 nusbandry 2	240/T

APPENDIX 3

RECOMMENDED TREE WORKS TO FACILITATE DEVELOPMENT (See Table 1)

Notes for Guidance:						
 RP - Pre-emptive root pruning of foundation encroachments under arboricultural supervision. CB - Cut Back to boundary/clear from structure. CL# - Crown Lift to given height in meters. CT#% - Crown Thinning by identified %. CCL - Crown Clean (remove deadwood/crossing and hazardous branches and stubs)*. CR#% - Crown Reduce by given maximum % (of outermost branch & twig length) DWD - Remove deadwood. Fell - Fell to ground level. FInv - Further Investigation (generally with decay detection equipment). Pol - Pollard or re-pollard. Mon - Check / monitor progress of defect(s) at next consultant inspection which should be <18 months in frequented areas and <3 years in areas of more occasional use. Where clients retain their own ground staff, we recommend an annual in- house inspection and where practical, in the aftermath of extreme weather events. Svr Ivy / Clr Bs - Sever ivy / clear base and re-inspect base / stem for concealed defects. 						

*Not generally specified following BS3998:2010

Landmar	Site: 49 Bels Date: 25/03/2	size 2019	R	ecommend	A ed Tree W	oppendix 3 forks To Facilitate Deve	Surveyor(s): Ref: elopment	Adam Hollis ESL_49BLS_AIA	Hide irrelevant Show All Trees
Tree No.	English Name	B.S. Cat	Height	Ground Clearance	Crown Spread	Recommended Works	Comments/ Reasons	S	
1	False Acacia	U	11	3.5	1643	Feli	Decay in swollen base, bark Topped at 8m To be removed under CAN To facilitate development	k necrosis 2019/2240/T	
3	Sycamore	В	12	6.0	5453	CB Cut back to boundary wall	Unsuitable species for posit Crown reduced 2017/18 To be root pruned under CA To facilitate development	tion AN 2019/2240/T	
4	Laurel, Portugese	С	5	2.0	1312	Fell	Suppressed by nearby tree To be removed under CAN To facilitate development	2019/2240/T	

APPENDIX 4: TREE SELECTION FOR URBAN LOCATIONS

Common Name	Species	(Columnar Form for discrete usage)
Hawthorn	Crataegus monogyna	Stricta
Cockspur	Crataegus prunifolia	Splendens
Cherry	Prunus x hillieri	Spire
Bird cherry	Prunus padus	Albertii
Rowan / Mountain ash	Sorbus aucuparia	Cardinal Royal
Swedish whitebeam	Sorbus intermedia	Brouwers
B. whitebeam	Sorbus x thuringiaca	Fastigiata

Table A4.1: Small Ornamental Tree Species

Table A4.2: Medium Specimen Tree Species

Common Name	Species	(Columnar Form for discrete usage)
Chinese red bark birch	Betula albosinensis	Fascination
Mongolian lime	Tilia mongolica	
Hornbeam	Carpinus betulus	Fastigiata Frans Fountaine
Turkish hazel	Corylus colurna	
Maidenhair tree	Gingko biloba	
Pride of India	Koelreuteria paniculata	Fastigiata
European larch	Larix decidua	Sheerwater Seedling
Tulip tree	Liriodendron tulipfera	Fastigiata

Table A4.3: Larger Specimen Tree Species

Common Name	Species	(Columnar Form for discrete usage)
English oak	Quercus robur	f. Koster
American elm	Ulmus americana Princeton	
Cedar of Lebanon	Cedrus libani	



PART 3 – PLANS

PLAN 1

TREE CONSTRAINTS PLAN





ARBORICULTURAL IMPACT ASSESSMENT PLAN (S)

- i. Basement
- ii. Ground Floor



NOTE:

10m

5m

This survey is of a preliminary nature. The trees were inspected from the ground only on the basis of the Visual Tree Assessment method. No samples were taken for analysis. No decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

Branch spread in metres is taken at the four cardinal points to derive an accurate representation of the crown.

Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base).





NOTE:

10m

5m

This survey is of a preliminary nature. The trees were inspected from the ground only on the basis of the Visual Tree Assessment method. No samples were taken for analysis. No decay detection equipment was employed. The survey does not cover the arrangements that may be required in connection with the laying or removal of underground services.

Branch spread in metres is taken at the four cardinal points to derive an accurate representation of the crown.

Root Protection Areas (RPA) are derived from stem diameter measured at 1.5 m above adjacent ground level (taken on sloping ground on the upslope side of the tree base).

