


Printed on \_\_\_\_% Post-Consumer Recycled Content Paper




TYPICAL SLAB JOINT DETAIL BETWEEN
NEW AND EXISTING SLABS




TYPICAL NEW GROUND BEARING SLAB DETAIL



SERVICE PENETRATION THROUGH
EXISTING MASONRY
1:10



SERVICE PENETRATION THROUGH RC WALL



# TYPICAL UNDERPINNING DETAIL

# UNDERPINNING; EXISTING WALLS

1. DETAIL ABOVE TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS AND

SPECIFICATIONS.

2. CONCRETE MIX. REFER TO URS SPECIFICATION.

3. DRY PACK MORTAR TO BE 3:1 SHARP SAND/CEMENT WITH NON-SHRINK ADDITIVE BY

CEBEX OR SIMILAR APPROVED.

4. SEQUENCE OF UNDERPINNING SECTIONS TO BE;

DAY.1 - EXCAVATE SECTION.1 AND CAST CONCRETE UPTO 75.m.m FROM THE

UNDERSIDE OF THE EXISTING CLEANED FOOTING.
DAY.3 - RAM IN TIGHT DRY PACK MORTAR BETWEEN UNDERPINNING AND EXISTING

FOOTING.

DAY.5 - COMMENCE NEXT SECTION AND REPEAT AS BEFORE.
5. ANY DRAINS EXPOSED MUST BE ADEQUATELY SUPPORTED OR REPLACED IF REMOVED OR

DAMAGED DURING THE WORKS.
6. MAXIMUM LENGTH OF ANY ONE SECTION NOT TO BE GREATER THAN 1100.m.m. CONSULT

S/ENG FOR APPROVAL.
7. THE CONTRACTOR MUST ENSURE THAT ALL TEMPORARY WORKS ARE ADEQUATELY

7. THE CONTRACTOR MUST ENSURE THAT ALL TEMPORARY WORKS ARE ADEQUATELY PROPPED AND SUPPORTED DOWN TO GROUND LEVEL.

8. THE CONTRACTOR TO AGREE THE SEQUENCE OF UNDERPINNING, PRIOR TO COMMENCING

WORKS, WITH THE STRUCTURAL ENGINEER. [TYPICAL SEQUENCE 1,3,5,2,4]

# CLIENT MIDDLESEX ANNEXE LLP

### CONSULTANT

AECOM Aldgate Tower 2 Leman Street London, E1 8FA

### **GENERAL NOTES**

www.aecom.com

1. FOR GENERAL NOTES REFER TO DRAWING No. MHA-ACM-XX-XX-GN-S-00001

**AECOM** 

DEVELOPMENT

BEDFORD PASSAGE

# ISSUE/REVISION

| artie                                   |     |            |                    |
|---|-----|------------|--------------------|
| oroduced or relied upon by third partie |     |            |                    |
|   |     |            |                    |
|   |     |            |                    |
|   |     |            |                    |
|   |     |            |                    |
|   | C1  | 09.08.2019 | CONSTRUCTION ISSUE |
|   | I/R | DATE       | DESCRIPTION        |

# KEY PLAN

# PROJECT NUMBER

60516144

SHEET TITLE

TYPICAL DETAILS SHEET 3

SHEET NUMBER

MHA-ACM-XX-XX-DE-S-00003