



The area on the ground floor is currently occupied as reception to the floors above and building managers office, It has direct access to the single lift which serves the designated floors Second, third and fourth floors above. It is intended to remove all of the partitions and doors forming managers office and dispose of all material.

Terminate the electricity supply back to the existing distribution board and remove all the existing light fittings including all fixings.

Remove all existing furniture and fittings and dispose of.

Remove the all existing suspended ceilings together with all light fittings , smoke detectors, CCTV, Emergency lighting units. Also remove all associated fixings within the slab. Dispose of all redundant materials



Scales	1/100 (at A3)	Date	February 2019
Drawn	AA	Checked	
Contract No	Drawing No	Revision	
19/01/Li	G/12	A	