

SCHEDULE OF TREES

110 Greencroft Gardens, London,

Surveyed By: Nick Hayden Date: 01/10/2019

Managed By: Nick Hayden

TreeNo	Species	DBH	Height		Visual	Crown Spread	Problems / Comments	BS Cat	Work Required	Priority
		Min Dist	Crown Base	Lowest Branch	Age	Water Demand				
		RPA (m ²)	Aspect	Aspect	SULE	Ground Cover				
T002	False Acacia	630	17		High	N5.5, E8.5, S6, W4	Location off-site impeded a detailed inspection. Foreign object encased in stem at base on western aspect. Service runs above ground along eastern aspect. Contorted stem with asymmetrical crown, biased to eastern aspect. Contorted stem with asymmetrical crown, biased to eastern aspect. Bifurcates at circa. 8m above ground level. Tearout wound, close to building, on north western aspect at circa. 9m above ground level, partially occluded. Crown historically reduced and thinned. Branch tip dysfunction and reduced leaf density. Vitality fair, structurally good.	C1	Reduce height of upper crown by 3m to the ridge height of the adjacent buildings. Reduce eastern extending limb by circa. 4m in length. Reduce southern and north western extending limbs back to historic reduction points. The annotated photographs included at item 3.6 show in detail where pruning is proposed.	2
		7.56	2.1-4m		M	Moderate				
No		179.6			10+ years	Grass, Shrub bed				

)

y

—

]

—