



Crown spreads are represented as coloured lines that reflect the crown spread measurements indicated in the tree schedule and accord with BS 5837/2012.

Tree numbers are preceded with a "T" for individual trees, a "G" for groups.

- G Crown Spread (Group)
- T Crown Spread (Individual tree)
- B.S.Tree Category A
- B.S.Tree Category B
- B.S.Tree Category C
- B.S.Tree Category U
- Tree proposed for removal

The root protection areas (RPA) are shown as symmetrical brown circles plotted at the appropriate radial distance from the centre of the tree as specified in the tree schedule.

- Protective fencing in accordance with BS 5837/2012 to be installed and maintained as specified in the AMS
- Basement construction Zone
- Ground Floor Extension Construction Zone

**ASHLEY
TREE
SURVEYS**

kateashley8@yahoo.co.uk
07967 013187



Job		
INVESTIGATION INTO ROOT PROTECTION AREAS FOR PREAPP APPLICATION AT:		
20a FERNCROFT AVENUE LONDON, NW3 7PH		
Title		
TREE PROTECTION PLAN		
Scale		
1:100 @ A3		
Drawing No	Date	Revision
-	04/12/19	-