



## Structural Proposals

to

### Replace the Brick Boundary Wall at Chamberlain Street London NW1 8BX with a new brick faced Reinforced Concrete Retaining Wall

for

Mr Jonny Bucknell of 8 Chamberlain Street  
London, NW1 8XB

**Frampton-Martin Sage Design  
Ltd**

Reference: J102/1649

The Garden Studio  
29 Park Road  
Radlett  
Herts. WD7 8EG  
Tel: 01923 289777  
[www.fms-design.co.uk](http://www.fms-design.co.uk)  
Contact L Goodman  
[lgoodman@fms-design.co.uk](mailto:lgoodman@fms-design.co.uk)



#### Document History

Produced by:	Date:	Issue Status:	Issued to:
L Goodman	18 <sup>th</sup> April 2019	For Information	Mr J Bucknell Simon Levy Associates

## 1.0 Introduction and Brief

At the request of Mr Simon Levy of Simon Levy Associates on behalf of our client, Mr John Bucknell, Owner of number 8 Chamberlain Street, we visited the site on 22<sup>nd</sup> October 2018 to undertake our preliminary structural condition review of the existing brick wall shown in the photographs on Appendix A.

Following our initial structural review of the wall which forms the end of road/back of pavement and all or part of the rear gardens of 15, 16 and 17 Ainger Road, we have been commissioned to provide structural details for a replacement reinforced concrete wall with masonry facing.

No assessment of the adjacent or adjoining building structures has been carried out as part of this review

This report is for the personal use of the fee-paying Client only and is not assignable. As such Frampton-Martin Sage Ltd., offer no liability to any third parties for any opinions or facts stated within this report.

Our inspections and appraisal are based on a visual inspection and plumb line survey only. No physical probes, removal of finishes or foundation excavations have been carried out as part of this initial review.

We have not inspected woodwork or other parts of structures, which are covered, unexposed or inaccessible and we are therefore unable to report that any such part of the property is free from defect.

References to right and left hand are made when viewing the property from the front elevation.

Appendix A contains photographs of the existing wall

Appendix B contains structural details of the replacement reinforced concrete wall and bar bending schedules together with our site notes from the initial review.

Appendix C contains the pile specification

Review undertaken by

*Laurence Goodman*

Laurence Goodman  
Chartered Structural Engineer.

<p style="writing-mode: vertical-rl; transform: rotate(180deg);"><b>2.0 Existing Structure and Demolition</b></p>	<p><b>2.0 Existing Structure and Demolition</b></p> <p>The existing 215 brick wall is approximately 12m long and varies from 2400 to 2000 high above pavement level.</p> <p>The wall retains soil to the gardens of numbers 15, 16 and 17 Ainger Road.</p> <p>Soil pressure, direct tree pressure and indirect tree root activity have in combination resulted in wall being up to 380mm out of plumb. We have included our initial reporting plumb line survey notes in Appendix B (Site Notes sheet 03 and 04) of this report, such the contractor can understand the instability of the existing wall, which has of course been propped over part of its length..</p> <p>No investigation of the foundations have been made at this stage, however foundations typical to this age and construction of wall are likely to be traditional shallow brick step, possibly on clinker concrete foundation. Foundation bearing soils typical to this location, would be a mix if clays/gravels and fill material.</p> <p><b>The contractor is to take extreme caution in the staged removal of propping/ demolition of the wall and will provide a detailed method statement and risk assessment of how the wall is to be demolished safely bearing in mind the close proximity of residents and public etc.</b></p>
<p style="writing-mode: vertical-rl; transform: rotate(180deg);"><b>3.0 Wall Condition</b></p>	<p><b>3.0 Wall Condition</b></p> <p>With reference to the site notes sheet 03 and 04, our plumb line survey showed that adjacent to the existing Hawthorn tree, the wall is between 300 and 380mm out of plumb.</p> <p>In reality a 215mm thick wall would be unstable with this degree of lean. It is likely therefore that the Hawthorn tree is both pushing the wall over and holding the wall from collapse.</p> <p><b>3.1 Walls reference A and B</b></p> <p>Reference to site notes, Walls A and B do not appear to be leaning and shall remain as existing.</p> <p><b>3.2 Wall reference C</b></p> <p>The wall is approx 2600 high and has a top section lean towards the garden behind for the first 1500mm length from number 8 Chamberlain. The lean of the wall then becomes progressively worse in the other direction closer to the Hawthorn tree as noted on the site notes.</p> <p>This wall has a straight joint with wall B at the left side and returns to form the garden boundary between 15 and 16 Ainger Road, where again it has a straight joint with Wall D</p> <p><b>3.3 Wall reference D</b></p> <p>Again this wall varies in lean of between 220 and 300mm, also theoretically beyond its point of stability. At the location of the shed, the wall has a vertical fracture, indicating that the shed is in fact providing some buttrance effect to the wall</p>

## 4.0 Proposed Works

### 4.1 General

Clearly wall sections C and D are in a dangerous state and the current propping is providing support. In reality a 215mm thick wall would be unstable with this degree of lean, and it is likely that the Hawthorn tree is directly affecting the wall in as much as it is both pushing the wall over and holding the wall from collapse.

In the rear garden of number 15 Ainger is a mature Sycamore tree located some 1400mm away from the wall.

A Sycamore tree, although of moderate water demand, in such close proximity to a soil mass, retained by a fragile structure, is likely to have a negative effect, either by direct pressure from the roots, or indirectly from fluctuating moisture content of the retained, typically clay content soils.

In addition, the soil levels of the gardens to the properties on Ainger road are some 1200 to 1400 mm above the pavement level of Chamberlain street. We noted no drainage within the retaining wall.

Without question, the lean and movement of the wall towards Chamberlain Road is as a direct result of the pressure from the un-drained soil to the gardens of 15 and 16 Ainger road. This movement has been enhanced by the Hawthorn tree, and possibly to a lesser effect by the Sycamore tree.

Careful removal and replacement of both wall sections C and D will be required as set out within Appendix B.

**The Hawthorn Tree will have to be completely removed as it has grown into the existing brick wall. The Sycamore should also be removed, if it is not to be the case, the tree canopy must be reduced significantly, the roots trimmed back where the new retaining wall is to be installed and a suitable root barrier installed to protect the new wall and back of wall drainage.**

We believe the shed to number 9 Chamberlain will have to be removed/reconstructed as it appears to be providing a buttrance to Wall D. Wall D has a vertical fracture at the shed location

**Again extreme caution must be employed in demolishing the shed to ensure a wall collapse does not occur.**

### 4.2 Replacement structure

We recommend that both walls C and D are replaced with a reinforced concrete structure faced with brickwork.

The base of the retaining wall would be set into the existing soil and supported onto small diameter concrete cast insitu piles to provide the necessary resistance to overturning and sliding.

## **5.0 Ground Conditions, Piling, Services Investigation etc**

### **5.1 Ground Conditions**

No site investigation has been carried out as part of this design. The contractor shall undertake all necessary bore hole and geotechnical site investigation to enable the design of the piles to be undertaken in accordance with the piling specification set out within Appendix C.

Should moisture sensitive clays be encountered below or to the rear of the new wall, the contractor will allow for providing suitable anti-heave measures as agreed with FMS Design and SLA.

### **5.2 Piling**

The piling will be designed and installed by the specialist subcontractor in accordance with the requirements set out in Appendix C

### **5.3 Services Investigation**

Prior to undertaking any bore hole investigation or pile installation, a statutory services search shall be undertaken by the contractor to establish the presence and depth of any services below the proposed retaining wall base.

This report is to be provided to FMS/SLA. If any concern is raised as to the possible presence of services, hand excavations shall be undertaken as appropriate to locate such services.

Should any deviation from the proposed structural arrangement be required, this is to be agreed with FMS

### **5.4 Demolition and Temporary Support**

As noted above, the contractor is to take extreme caution in the staged removal of propping/demolition of the wall and will provide a detailed method statement and risk assessment of how the wall is to be demolished safely bearing in mind the close proximity of residents and public etc. The method statement and risk assessment shall be agreed in principle with the principle designer.

The contractor shall provide all necessary temporary propping for the staged demolition works and retention of existing garden soil to the houses on Ainger Road

End of report

*L P Goodman*

**L P Goodman**

Chartered Structural Engineer

For and on behalf of Frampton-Martin Sage Ltd



## Appendix A Photographs of the existing wall



*Photograph 01*



*Photograph 02*



*Photograph 03*



*Photograph 04*





*Photograph 05*



*Photograph 06*



*Photograph 07*



*Photograph 08*





*Photograph 09*



*Photograph 09*





## **Appendix B**

### **Structural details of the replacement reinforced concrete wall, bar bending schedules and structural calculations**







 Frampton-Martin Sage Limited Garden Studio 29 Park Road Radlett Herts WD7 8EG T. 01923 289 777 M. 07956 476 179	<b>CLIENT:</b> Simon Levy Associates	<b>JOB N°:</b> 102/1731
	<b>ADDRESS:</b> Chamberlain Street London NW1	<b>SHEET</b>
<b>SUBJECT:</b> Retaining Wall	<b>DATE:</b> April 19 <b>ENGINEER:</b> LPG	<b>APPROVED:</b>
	<b>CLIENT REF:</b>	





Frampton-Martin Sage Limited  
Garden Studio  
29 Park Road  
Radlett  
Herts WD7 8EG

T. 01923 289 777 M. 07956 476 179

CLIENT:  
Simon Levy Associates

ADDRESS:  
Chamberlain Street - London  
NW3

SUBJECT:  
Retaining Wall Site Notes

JOB N°: 102/1731


SHEET OF: *SITE NOTES*

DATE: Oct 18

ENGINEER: LPG

APPROVED:

CLIENT REF:





Frampton-Martin Sage Limited  
Garden Studio  
29 Park Road  
Radlett  
Herts WD7 8EG  
T. 01923 289 777 M. 07956 476 179

**CLIENT:**  
Simon Levy Associates

**ADDRESS:**  
Chamberlain Street – London  
NW3

**SUBJECT:**  
Retaining Wall Site Notes

**JOB N°:** 102/1731


**SHEET** OF: *SITE NOTES CA.*

**DATE:** Oct 18

**ENGINEER:** LPG

**APPROVED:**

**CLIENT REF:**











Frampton-Martin Sage Limited  
Garden Studio  
29 Park Road  
Radlett  
Herts WD7 8EG  
T. 01923 289 777 M. 07956 476 179

**CLIENT:**  
Simon Levy Associates

**JOB N°:** 102/1731

**SHEET** OF: 01

**ADDRESS:**  
Chamberlain Street – London  
NW3

**DATE:** Oct 18

**ENGINEER:** LPG

**SUBJECT:**  
Retaining Wall Site Notes

**APPROVED:**

**CLIENT REF:**

## 1) SCHEME

IT IS PROPOSED TO REPLACE THE EXISTING BRICK BOUNDARY RETAINING WALL WHICH FORMS THE REAR CARDSHED WALL TO N. 10 & 15 AVENUE & PAVEMENT EDGE TO THE END OF CHAMBERLAIN ST AS SET OUT ON FMS SITE NOTES SHEETS 01 TO 04 IN APPROX A OF THESE PLANS.

BECAUSE OF ACCESS PROBLEMS TO THE REAR CARDSHED, OF 10 & 15 AVENUE, THE WALL WILL HAVE TO BE CONSTRUCTED FROM CHAMBERLAIN STREET.

THE NEW WALL WILL PROVIDE RETENTION TO THE CARDSHED OF 10 & 15 AVENUE.

IT IS LIKELY THAT THE GROUND BELOW THE NEW RETAINING WALL IS FILL, SO TO PROVIDE PROTECTION OF THE WALL, WE PROPOSE TO PROVIDE A PILED BASE.

## 2) PILING WORKS

IT IS ANTICIPATED THAT 300 Ø BORED CAST IN PLACE PILES WILL BE UTILISED.

PILES ARE TO BE DESIGNED BY A SPECIALIST SUB-CONTRACTOR.

SITE INVESTIGATION & STAT'S SERVICES WILL BE UNDERTAKEN AS PART OF THE CONTRACT.







Frampton-Martin Sage Limited  
 Garden Studio  
 29 Park Road  
 Radlett  
 Herts WD7 8EG  
 T. 01923 289 777 M. 07956 476 179

**CLIENT:**  
 Simon Levy Associates

**JOB N°:** 102/1731

**SHEET OF:** 05

**ADDRESS:**  
 Chamberlain Street - London  
 NW3

**DATE:** Oct 18

**ENGINEER:** LPG

**SUBJECT:**  
 Retaining Wall Remedial

**APPROVED:**

**CLIENT REF:**

Surcharge  $10 \text{ kN/m}^2$  - Assume no water behind wall.  
 Active Pressure due to soil =  $\frac{1}{3} \times 19 \times 1.75 = 11.1 \text{ kN/m}$   
 Active Pore Surcharge =  $0.5 \times 17.5 \times 10 = 8.8 \text{ kN/m}$   
 Wind Load say  $1.0 \text{ kN/m}^2 \times 1.8 = 1.8 \text{ kN/m}$   
 $\Sigma 22 \text{ kN/m}$

Calculate overturning moments about 'O'

$$(1.8 \times 2.8) + (8.8 \times 0.875) + (11.1 \times 0.85) = 24.5 \text{ kNm}$$

Max force in pile due to overturning  $24.5 \times 2 / 0.85 = 58 \text{ kN}$

Calculate Moments about 'R'

$$W_1 = \text{weight of beam} = 0.25 \times 1.5 \times 24 = 6.9 \text{ kN/m}$$

$$W_2 = \text{weight of brick} = 0.105 \times 1.5 \times 18 + 0.25 \times 1.85 \times 18 = 10.4 \text{ kN/m}$$

$$W_3 = \text{weight of wall} = 0.25 \times 1.5 \times 24 = 9 \text{ kN/m}$$

$$W_4 = \text{Passive} = 0.15 \times 0.9 \times 18 = 2.43 \text{ kN/m}$$

$$W_5 = \text{Surcharge (Passive)} = 10 \times 0.9 = 9 \text{ kN/m}$$

$$\left[ (0.25 \times 0.85 \times 24) \frac{0.85}{2} \right] + [10.4 \times 0.6] + [9 \times 0.725] + [0.15 \times 18 \times \frac{0.45}{2}] + [9 \times \frac{0.45}{2}] = 2.17 + 6.24 + 6.53 + 0.61 + 2.03 = 17.6 \text{ kNm}$$







Frampton-Martin Sage Limited  
Garden Studio  
29 Park Road  
Radlett  
Herts WD7 8EG  
T. 01923 289 777 M. 07956 476 179

CLIENT:  
Simon Levy Associates

JOB N°: 102/1731

SHEET OF: 04.

ADDRESS:  
Chamberlain Street - London  
NW3

DATE: Oct 18

ENGINEER: LPG

SUBJECT:  
Retaining Wall Remedial

APPROVED:

CLIENT REF:

$$\begin{matrix} \curvearrowright & w_1 & 0.3 & & w_3 & 0.41 & & w_4 & 1.5 & \text{(moments } \curvearrowright) \\ & & & & & & & & & \\ (0.25 \times 24 \times 0.3/2) & + & (0.15 \times 0.3 \times 1.5) & + & (10 \times 0.3/2) & + & 24.5 & = & 27.3 \text{ kNm.} \end{matrix}$$

$$R_2 = (17.6 - 27.3) / 0.55 = -18 \text{ kN}$$

Assuming Piles at 2m/c MAY UPLIFT =  $\boxed{-36 \text{ kN}}$

Moments about R<sub>2</sub>

$$\begin{matrix} \curvearrowleft & & w_1 & & w_3 & & w_4 \\ 24.5 & + & (0.25 \times 24 \times 0.3/2) & + & (0.15 \times 0.3 \times 1.5) & + & (10 \times 0.3/2) & = & -32.5 \text{ kNm.} \end{matrix}$$

$$\begin{matrix} \curvearrowright & w_2 & 0.523 & & w_3 & 1.55 \\ (0.45 \times 0.05) & + & (9 \times 0.175) & = & 2.1 \text{ kNm.} \end{matrix}$$

$$R_1 = (32.5 - 2.1) / 0.55 = +55.3 \text{ kN}$$

Assuming Piles at 2m/c MAY COMPRESSIVE LOAD

$$= \boxed{111 \text{ kN}}$$

Specify Provide 125kN capacity Piles.  
For as safe working load to be 2.5


Refer to following pages for wall design.

Specify Provide 250 Re wall U12 @  
150% reinforcement to cover c/c's.

Project Chamberlain Street				Job no. 102/1497	
Calcs for				Start page no./Revision 5	
Calcs by LPG	Calcs date 21/04/2019	Checked by	Checked date	Approved by	Approved date

### RETAINING WALL ANALYSIS (BS 8002:1994)

TEDDS calculation version 1.2.01.06



#### Wall details

Retaining wall type

Height of wall stem

Length of toe

Overall length of base

Height of retaining wall

Depth of downstand

Position of downstand

Depth of cover in front of wall

Height of ground water

Density of wall construction

Angle of soil surface

Mobilisation factor

Moist density

Design shear strength

Design shear strength

Moist density

#### Using Coulomb theory

Active pressure

At-rest pressure

#### Loading details

Surcharge load

Vertical dead load

Horizontal dead load

#### Cantilever

$h_{stem} = 1500$  mm

$l_{toe} = 850$  mm

$l_{base} = 1100$  mm

$h_{wall} = 1750$  mm

$d_{ds} = 0$  mm

$l_{ds} = 850$  mm

$d_{cover} = 150$  mm

$h_{water} = 0$  mm

$\gamma_{wall} = 23.6$  kN/m<sup>3</sup>

$\beta = 0.0$  deg

$M = 1.5$

$\gamma_m = 18.0$  kN/m<sup>3</sup>

$\phi' = 24.2$  deg

$\phi'_b = 24.2$  deg

$\gamma_{mb} = 18.0$  kN/m<sup>3</sup>

$K_a = 0.369$

$K_0 = 0.590$

Surcharge = 10.0 kN/m<sup>2</sup>

$W_{dead} = 10.4$  kN/m

$F_{dead} = 0.0$  kN/m

Wall stem thickness

Length of heel

Base thickness

Thickness of downstand

Unplanned excavation depth

Density of water

Density of base construction

Effective height at back of wall

Saturated density

Angle of wall friction

Design base friction

Allowable bearing

Passive pressure

Vertical live load

Horizontal live load

$t_{wall} = 250$  mm

$l_{heel} = 0$  mm

$t_{base} = 250$  mm

$t_{ds} = 250$  mm

$d_{exc} = 200$  mm

$\gamma_{water} = 9.81$  kN/m<sup>3</sup>

$\gamma_{base} = 23.6$  kN/m<sup>3</sup>

$h_{eff} = 1750$  mm

$\gamma_s = 21.0$  kN/m<sup>3</sup>

$\delta = 18.6$  deg

$\delta_b = 18.6$  deg

$P_{bearing} = 75$  kN/m<sup>2</sup>

$K_p = 4.187$

$W_{live} = 0.0$  kN/m

$F_{live} = 0.0$  kN/m


Project Chamberlain Street				Job no. 102/1497	
Calcs for				Start page no./Revision 6	
Calcs by LPG	Calcs date 21/04/2019	Checked by	Checked date	Approved by	Approved date

Position of vertical load

$l_{load} = 850 \text{ mm}$

Height of horizontal load

$h_{load} = 0 \text{ mm}$



Loads shown in kN/m, pressures shown in kN/m<sup>2</sup>

**Calculate propping force**

Propping force  $F_{prop} = 5.7 \text{ kN/m}$

**Check bearing pressure**

Total vertical reaction  $R = 28.0 \text{ kN/m}$

Distance to reaction

$x_{bar} = 393 \text{ mm}$

Eccentricity of reaction  $e = 157 \text{ mm}$

**Reaction acts within middle third of base**

Bearing pressure at toe  $p_{toe} = 47.2 \text{ kN/m}^2$

Bearing pressure at heel

$p_{heel} = 3.7 \text{ kN/m}^2$

**PASS - Maximum bearing pressure is less than allowable bearing pressure**



Project Chamberlain Street				Job no. 102/1497	
Calcs for				Start page no./Revision 7	
Calcs by LPG	Calcs date 21/04/2019	Checked by	Checked date	Approved by	Approved date

### RETAINING WALL DESIGN (BS 8002:1994)

TEDDS calculation version 1.2.01.06

#### Ultimate limit state load factors

Dead load factor  $\gamma_{f_d} = 1.4$       Live load factor  $\gamma_{f_l} = 1.6$   
Earth pressure factor  $\gamma_{f_e} = 1.4$

#### Calculate propping force

Propping force  $F_{prop} = 5.7$  kN/m


#### Design of reinforced concrete retaining wall toe (BS 8002:1994)

##### Material properties

Strength of concrete  $f_{cu} = 35$  N/mm<sup>2</sup>      Strength of reinforcement  $f_y = 500$  N/mm<sup>2</sup>

##### Base details

Minimum reinforcement  $k = 0.13$  %      Cover in toe  $C_{toe} = 40$  mm



#### Design of retaining wall toe

Shear at heel  $V_{toe} = 32.2$  kN/m      Moment at heel  $M_{toe} = 31.3$  kNm/m  
**Compression reinforcement is not required**

#### Check toe in bending

Reinforcement provided **12 mm dia. bars @ 150 mm centres**  
Area required  $A_{s_{toe_{req}}} = 370.8$  mm<sup>2</sup>/m      Area provided  $A_{s_{toe_{prov}}} = 754$  mm<sup>2</sup>/m  
**PASS - Reinforcement provided at the retaining wall toe is adequate**

#### Check shear resistance at toe

Design shear stress  $V_{toe} = 0.158$  N/mm<sup>2</sup>      Allowable shear stress  $V_{adm} = 4.733$  N/mm<sup>2</sup>  
**PASS - Design shear stress is less than maximum shear stress**  
Concrete shear stress  $V_{c_{toe}} = 0.600$  N/mm<sup>2</sup>  
 **$V_{toe} < V_{c_{toe}}$  - No shear reinforcement required**

#### Design of reinforced concrete retaining wall stem (BS 8002:1994)

##### Material properties

Strength of concrete  $f_{cu} = 35$  N/mm<sup>2</sup>      Strength of reinforcement  $f_y = 500$  N/mm<sup>2</sup>


##### Wall details

Minimum reinforcement  $k = 0.13$  %  
Cover in stem  $C_{stem} = 40$  mm      Cover in wall  $C_{wall} = 40$  mm



Sage Design Services Ltd  
29 Park Road  
Radlett  
WD7 8EG

Project Chamberlain Street				Job no. 102/1497	
Calcs for				Start page no./Revision 8	
Calcs by LPG	Calcs date 21/04/2019	Checked by	Checked date	Approved by	Approved date



#### Design of retaining wall stem

Shear at base of stem  $V_{stem} = 5.7 \text{ kN/m}$       Moment at base of stem  $M_{stem} = 22.8 \text{ kNm/m}$   
**Compression reinforcement is not required**

#### Check wall stem in bending

Reinforcement provided **12 mm dia.bars @ 150 mm centres**  
Area required  $A_{s\_stem\_req} = 325.0 \text{ mm}^2/\text{m}$       Area provided  $A_{s\_stem\_prov} = 754 \text{ mm}^2/\text{m}$   
**PASS - Reinforcement provided at the retaining wall stem is adequate**

#### Check shear resistance at wall stem

Design shear stress  $v_{stem} = 0.028 \text{ N/mm}^2$       Allowable shear stress  $v_{adm} = 4.733 \text{ N/mm}^2$   
**PASS - Design shear stress is less than maximum shear stress**  
Concrete shear stress  $v_{c\_stem} = 0.600 \text{ N/mm}^2$   
 **$v_{stem} < v_{c\_stem}$  - No shear reinforcement required**

#### Check retaining wall deflection

Max span/depth ratio  $ratio_{max} = 14.00$       Actual span/depth ratio  $ratio_{act} = 7.35$   
**PASS - Span to depth ratio is acceptable**






Sage Design Services Ltd  
29 Park Road  
Radlett  
WD7 8EG

Project		Chamberlain Street			Job no.		102/1497
Calcs for					Start page no./Revision		9
Calcs by	Calcs date	Checked by	Checked date	Approved by	Approved date		
LPG	21/04/2019						

**Indicative retaining wall reinforcement diagram**



Toe bars - 12 mm dia. @ 150 mm centres - (754 mm<sup>2</sup>/m)  
Stem bars - 12 mm dia. @ 150 mm centres - (754 mm<sup>2</sup>/m)

## **Appendix C**

### **Pile specification**





---

## Pile Specification

at

## Chamberlain Street

for

## SLA

**Frampton-Martin Sage Design Ltd**

FMS Job Reference: J102/1731

The Garden Studio  
29 Park Road  
Radlett  
Herts. WD7 8EG  
Tel: 01923 289777  
[www.fms-design.co.uk](http://www.fms-design.co.uk)  
Contact L Goodman  
[lgoodman@fms-design.co.uk](mailto:lgoodman@fms-design.co.uk)

### Document History

Produced by:	Date:	Issue Status:	Issued to:
L Goodman	April 19	Tender	_____

<b>Section</b>	<b>Contents</b>
<b>1.0</b>	<b>Proposed Development and contractor design requirement</b>
<b>2.0</b>	<b>General</b>
<b>3.0</b>	<b>Bearing Piles</b>
<b>4.0</b>	<b>Superstructure Loading, Pile Diameters and Working Loads</b>
<b>5.0</b>	<b>Contractor's Design Details</b>
<b>6.0</b>	<b>Site Investigation and Existing Services</b>
<b>7.0</b>	<b>Records</b>
<b>8.0</b>	<b>Reinforcement</b>
<b>9.0</b>	<b>Concrete</b>
<b>10.0</b>	<b>Testing</b>
<b>11.0</b>	<b>Method and Sequence of Construction</b>

## **1.0 Proposed Development and Contractor design requirement**

The construction of a piled reinforced concrete retaining wall

The contractor will be required to design, supply and install the cast in situ reinforced concrete piles, including:

- All pile design and specification
- All site investigation deemed necessary by the contractor to establish the piled raft design

## **2.0 General**

General requirements, materials, workmanship, tolerances, contract documentation and measurement etc. are to be in accordance with the Institute of Civil Engineers "Specification for Piling" published by Thomas Telford.

### **3.0 Bearing Piles**

Bearing piles shall be installed at the positions shown on the Drawings. Piles will be of the following type:- **Bored cast insitu concrete.**

### **4.0 Superstructure Loading, Pile Diameters and Working Loads**

#### **Pile Diameters**

Bearing piles shall have a cross-sectional area not less than that of a circle of 300mm diameter.

#### **4.3 Working Loads**

Bearing piles shall be designed and installed by the contractor to carry the working loads as follows

Max compressive load/pile – 125kN

Max uplift/pile – 40kN

Max shear/pile – 44kN

and to have an ultimate bearing capacity of at least three times the working load if no pile test is to be performed.

### **5.0 Contractor's Design Details**

The Contractor shall submit for comment to the Engineer the following details:-

- a) The size and type of pile
- b) In case of driven piles, the definition "of final set" recorded as the penetration in mm per 10 blows
- c) Reinforcement and concrete class where this is not specified
- d) An undertaking that the piles will have an ultimate load carrying capacity of at least three times the working loads shown on the Drawings. The ultimate load is defined as that load applied to the head of the pile which causes the head of the pile to settle no greater than 10% of the pile diameter or 10% of the diameter of the circle of equivalent area to the gross area of non-circular pile.

### **6.0 Site Investigation and Existing Services**

6.1 SI to be undertaken by the contractor

6.2 The Piling Contractor shall take all reasonable steps to locate and avoid existing underground services.



## 7.0 Records

- 7.1 The following records shall be kept of every pile:-
- Pile identification number and location
  - Original ground level related to Ordnance
  - Nominal diameter
  - Date driven or bored
  - Date concreted
  - Depth from ground level to top of the concrete
  - Depth from ground level to bearing stratum
  - Final set for driven piles, weight and drops of hammer from commencement of the bearing stratum
  - Details of any obstruction observed
  - Details of offcuts and supplements.
- 7.2 All records shall be accurately kept in duplicate as the work proceeds and one copy shall be sent to the Engineer at the completion of the day's work.

## 8.0 Reinforcement

- 8.1 As a minimum, Piles to be continually reinforced through their length with 4 number H16 diameter longitudinal and H10 diameter helical link. Contractor to confirm details of proposals if otherwise.
- 8.2 Pile reinforcement to project a minimum of 600mm above the top of the pile, such that it may be bent into the line of raft reinforcement

## 9.0 Concrete

- 9.1 Concrete in piles and raft to be FND3 to BS5328 Sulphate Resisting.

## 10.0 Testing

- 10.1 Maintained Load Tests - **Not required.**

### 10.2 Indirect Methods for Testing Piles

Carry out continuity tests on all piles. All testing to be undertaken by specialist. Details of equipment to be used and of the method of analysis of test results shall be provided before the commencement of testing.

### 10.3 Soil Tests

Carry out sufficient sampling and testing required for pile design.

#### 10.4 Probing

Carry out sufficient sampling and testing required for pile design.

### 11.0 Method and Sequence of Construction

- 11.1 To be such as not to damage piles already constructed or adjacent structures or such as to cause disturbance to neighbours through noise or vibration.
- 11.3 **Note - The piles are to be designed against heave for the type of subsoils and trees encountered within and surrounding the site**
- 11.4 **Tolerance** - Piles are to be cast to a tolerance of plus or minus 75mm from the grid line on plan. Costs arising from remedial design/work on site will be borne by the piling contractor.