




The use of this data by the recipient acts as an agreement of the following statements. Do not use this data if you do not agree with any of the following statements:-

All drawings are based upon site information supplied by third parties and as such their accuracy cannot be guaranteed. All features are approximate and subject to clarification by a detailed topographical survey, statutory service enquiries and confirmation of the legal boundaries.

Do not scale the drawing. Use figured dimensions in all cases. Check all dimensions on site.

Report any discrepancies in writing to Palmer Lunn Architects before proceeding.



Schedule of Proposed Stripping out Works

Proposed Stripping out Works All existing services and associated fixings 1. 2. All modern doors, windows, frames and architraves 3. All modern fixed and free-standing joinery and associated fixings 4. All modern sanitary ware and associated fixings 5. All modern finishes, fixtures and fittings generally NB: All original finishes and fixtures, such as the staircase, skirting and floorboards are to be retained for refurbishment P01 Issued for Plannning 03.02.20 AMe APa Rev Description Date Drn Chk Status PLANNING Client Bohemia Club

Project The Apple Tree Public House 45 Mount Pleasant London WC1X 0AE Drawing

West Elevation as Existing Showing Demolitions and Stripping out

Project No.Drawing No.Revision1800312OS-A-P-052P01Scale @ A3Drawn By1:100AMe

palmer lunn architects

www.palmerlunn.com

10m