



NSB Casements Ltd

3 Steele Road, Park Royal, London, NW10 7AR.
Tel. 020 8961 3090, Fax. 020 8961 3050
email: info@nsbcasements.co.uk

Site: Camden Methodist Chapel 'Draft'

Drawn: DCN

Date: 16/05/19

Job No.

O/No:

Drwg No. CMC0001/1

Scale :

Estimate No: E 22030

Our Ref: HJP/DRN

Your Ref:

Date: 5th June 2019

Manalo & White
Unit 301
Metropolitan Wharf Building
70 Wapping Wall
London
E1W 3SS

For the attention of Mr T Oura

Dear Sir

Re: Camden Methodist Hall

We thank you for your enquiry and have pleasure in submitting our estimate as follows:-

STEEL windows constructed from W20 sections, all corners mitred and welded, finished hot dip galvanized with standard colour polyester powder coat, all opening lights weatherstripped, prepared for glazing with clip-on beads.

- | | |
|----------|---|
| A – 2 no | 950 wide x 2400 high comprising:-
1 - twenty pane radius head fixed light |
| B – 3 no | Ditto but 950 wide x 2100 high |
| C – 2 no | 950 wide x 1900 high comprising:-
1 - sixteen pane radius head fixed light |

D – 2 no 950 wide x 600 high comprising:-
1 - nine pane radius head fixed light

E 22030

Page 2

E – 3 no Ditto Type A but 1100 wide x 2100 high

F – 10 no Ditto Type A but 1200 wide x 2600 high

G – 1 no 1800 wide x 1750 high comprising:-
1 - six pane radius head fixed light

H – 4 no 1100 wide x 1650 high comprising:-
1 - six pane fixed light

Ia – 5 no 1200 wide x 2450 high comprising:-
1 - eighteen pane fixed light

Ib – 3 no 1200 wide x 2450 high comprising:-
1 - twenty four pane fixed light

J – 1 no 1250 wide x 1900 high comprising:-
1 - twenty pane fixed light

K – 1 no 700 wide x 1500 high comprising:-
1 - six pane fixed light

To supply the above new steel windows and fix into openings prepared by others. Mastic point perimeter up to 7mm fillet. Supply 16mm clear sealed units to suit and glaze with clip-on beads, silicone capped internally and externally. Our price includes for all necessary fixing and glazing materials but is exclusive of any making good, plastering, decoration etc.

**FOR THE TOTAL SUM OF
VAT**

£90,942.00 +

Please note:

1. All necessary scaffold and/or access equipment to be supplied (erected, maintained and dismantled) by others, free of charge for the duration of the works.

Terms: Nett. 40% Deposit + 40% Interim Payment + Balance with 7 days of completion of our works on site. Please note that we do not accept self-billing and invoices will be raised for payment as and when due.

Delivery: 10-12 working weeks from receipt of official order and all relevant details and sizes. However, this is our current delivery period and subject to change.

Prices remain open for acceptance for a period of 60 days from the date of estimate. Customers are advised to confirm prices at the time of placing order.

Yours faithfully
for NSB CASEMENTS LTD

H J Pearce (Mrs)